



GENERAL NOTES - ROOF

1. REFER TO ALL OTHER SHEETS FOR ADDITIONAL NOTES AND INFORMATION.
2. THE CONTRACTOR SHALL NOTIFY THE DESIGN CONSULTANT, ARCHITECT AND ENGINEERS FOR INSTRUCTIONS / CLARIFICATIONS PRIOR TO CONSTRUCTION.
3. CONTRACTOR IS TO VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS AT THE JOB SITE. DESIGN CONSULTANTS AND ARCHITECTS ARE TO BE NOTIFIED IN WRITING OF ANY DISCREPANCIES.
4. ALL WORK SHALL COMPLY TO THE INTERNATIONAL BUILDING CODE AND ALL ADOPTED SUB-CODES. DESIGN CONSULTANT AND ARCHITECTS ARE NOT RETAINED FOR ANY ON SITE SUPERVISION OR CONTRACT ADMINISTRATION.
5. ALL WORK IS TO BE PERFORMED TO THE HIGHEST STANDARDS OF THE TRADES.
6. CONTRACTOR IS TO COMPLY TO ALL STATE AND LOCAL ORDINANCES.
7. IT SHALL BE THE RESPONSIBILITY OF THE GENERAL CONTRACTOR TO COORDINATE ALL WORK WITH THE STRUCTURAL, MECHANICAL, ELECTRICAL AND OTHER TRADES. THE GENERAL CONTRACTOR SHALL SUBMIT A NEW LAYOUT IF IT BECOMES NECESSARY FOR APPROVAL.
8. SUPPORT ALL ACCESS NEW WORK PROCEDURES.
9. THE CONTRACTOR SHALL FAMILIARIZE HIMSELF WITH ALL EXISTING CONDITIONS AT THE JOB SITE PRIOR TO THE START OF ANY WORK.
10. CONTRACTOR IS TO PROVIDE ACCESS PANELS AS REQUIRED NEEDED OR DIRECTED BY ARCHITECT, ENGINEER, CONSTRUCTION OFFICIAL OR OWNER.
11. CONTRACTOR AND/OR OWNER SHALL PROVIDE FOR THE SAFETY OF ALL JOB RELATED PERSONNEL AS WELL AS THE GENERAL PUBLIC.
12. SEE ALL DRAWINGS FOR ADDITIONAL NOTES AND DETAILS.
13. VERIFY LOCATIONS OF ALL ROOF PENETRATIONS WITH STRUCTURE AND MECHANICAL.
14. IT IS THE GENERAL CONTRACTOR'S RESPONSIBILITY TO VERIFY, COORDINATE AND/OR INSTALL ALL ADJACENT AND/OR RELATED FLASHING, BLOCKING, NAILER, INSULATION STOPS, CRICKETS, ETC. NECESSARY FOR THE COMPLETE INSTALLATION OF THE ROOF MEMBRANE WHICH ARE REQUIRED FOR A COMPLETE, WARRANTED, WATER TIGHT, WEATHERPROOF INSTALLATION.
15. LOCATION OF ROOF ACCESSORIES & MATERIALS ARE SCHEMATIC IN NATURE. EXACT LOCATIONS SHALL BE DETERMINED BY INFORMATION ELSEWHERE ON THE DRAWINGS.
16. OMISSION OF ANY ACCESSORY FROM THE ROOF PLAN SHALL NOT RELIEVE THE CONTRACTOR FROM THE RESPONSIBILITY FOR SUCH ITEMS.
17. GENERAL CONTRACTOR TO FIELD VERIFY ALL ROOF CURBS OPENING SIZE PER UNITS ON THE SITE.
18. ROOFING SUBCONTRACTOR TO PROVIDE WATER TIGHT CONNECTIONS AT ALL ROOF PENETRATIONS PER MANUFACTURER'S RECOMMENDATION.
19. GENERAL CONTRACTOR TO COORDINATE ROOFING WITH ALL FUTURE ROOF PENETRATIONS SO AS TO MAINTAIN ROOF WARRANTY.
20. GENERAL CONTRACTOR COORDINATE ACCESS PANELS TO ALLOW MOVEMENT THROUGH ALL INTERIOR TRUSS AND TOLER AREAS.
21. CONTRACTOR SHALL COORDINATE PROPOSED ROOF CURB LOCATIONS WITH STRUCTURAL STEEL AND ADJUST ACCORDINGLY TO CENTER BETWEEN JOISTS.
22. CONTRACTOR SHALL COORDINATE WITH MECHANICAL TO DETERMINE SIZE OF CURBS REFER TO STRUCTURE DETAILS FOR FRAMING REQUIREMENT.

Order Plans

1 ROOF PLAN
A105 SCALE: 1/8" = 1'-0"

DESIGN BUILD
BLACKWATER CONSTRUCTION GROUP, LLC
2200 SATELLITE BLVD, DULUTH GA 30092
Phone: 404-740-7589

DESIGN CONSULTANTS
DESIGN SOLUTIONS LLC
www.designsolutionsllc.com
Phone: 404-740-7589

ARCHITECT OF RECORD
ROBERT J LARA, AIA
8450 SW 291 ST
CUTLER BAY, FL 33189

STATE OF GEORGIA
ROBERT JERRY LARA
REGISTERED ARCHITECT
Nov 9 2014

STRUCTURAL
ENGQUEST
3550 ENGINEERING DRIVE, SUITE 175
PEACHTREE CORNERS, GA 30092
TEL: (404) 966-4670
www.engquest.com

MEP
ENGQUEST
3550 ENGINEERING DRIVE, SUITE 175
PEACHTREE CORNERS, GA 30092
TEL: (404) 966-4670
www.engquest.com

NOTES:

REVISION #	DATE	REMARKS

ISSUE DATE	ISSUED TO:	ISSUED FOR:
10-02-2014	COUNTY	PERMITS

PROJECT ADDRESS:
MASJID AL-MOMINEEN
837 NORTH INDIAN CREEK DRIVE
CLARKSTON, DEKALB COUNTY
GEORGIA, 30021

LAYOUT:
ROOF PLAN

PAPER SIZE: 24X36 (ARCH D)

SCALE: AS NOTED

SHEET NUMBER:
A105