www.LDILine.com
Order Plans @ W

BARCLAY DR
(APPARENT 60' R/W)

APPROX. EDGE OF EX. PAVEMENT

EX. TRAIL (APPROX.)

N 1430818
E 2257379

REMOVE 259 L.F. CURB GUTTER
N 1430779
E 2257123

REMOVE 58 L.F. CURB GUTTER
N 1430687
E 2256860

REMOVE DROP INLET
39 L.F. 27" CMP

REMOVE
EX. DROP INLET
221 L.F. 27" CMP

REMOVE
EX. HEADWALL
AND 59 L.F. OF 12" CMP

REMOVE 18" HEADWALL

REMOVE SOCCER GOAL
(APPROX. LOCATION)

REMOVE
EX. DROP INLET

SALVAGE AND STORE SIGN FOR FUTURE PLACEMENT

EX. GATE POSTS TO BE DEMOLISHED AND REPLACED WITH NEW. SEE SITE PLAN, SHEET C-1.0. CONTRACTOR TO MAINTAIN ACCESS CONTROL THROUGHOUT CONSTRUCTION

REMOVE 371 L.F.
OF 36" CMP

REMOVE 162 L.F.
CHAIN LINK FENCING

REMOVE
BLEACHERS

REMOVE
184 L.F.
30" CMP

REMOVE
DROP INLET

REMOVE
LIGHTPOST

REMOVE
EX. DROP INLET
169 L.F. 36" CMP

REMOVE 4 METAL APPURTENANCES

REMOVE DUGOUTS
AND ALL FENCING

REMOVE
EX. DROP INLET
189 L.F. 36" CMP

REMOVE DROP INLET
51 L.F. 24" RCP

REMOVE
LIGHTPOST

REMOVE DUGOUT
2" PVC PIPE

REMOVE
TRASH RECEPTICLE

REMOVE
TRASH
RECEPTICLE

REMOVE
159 L.F. 27" CMP

REMOVE
DROP INLET
112 L.F. 36" CMP

REMOVE CATCH BASIN
33 L.F. 24" RCP

REMOVE
BLEACHERS

REMOVE
LIGHTPOST

REMOVE
34 L.F. 15"
DIP

REMOVE
IRRIGATION
CONTROL VALVES

REMOVE
LIGHTPOST

REMOVE
IRRIGATION
CONTROL
VALVE

REMOVE
LIGHTPOST

DEMOLITION PLAN

NORTH

GRAPHIC SCALE: 1" = 30'

15 0 15 30 60 120

Dirt and Company
Architects, Planners
229 Peachtree Street, N.E., Suite 2600
Atlanta, Georgia 30303
404 577-4000 FAX: 404 577-7119

SKYLINE
LANDSCAPE ARCHITECTURE & CONSULTING
P 888.706.0661 F 770.217.7530 www.skyline-ec.com

SYMBOL	DATE	BY	REVISION

SEAL

CLIENT: City of Dunwoody

PROJECT: Baseball Facilities at Brook Run Park

DESIGNED: MDC | DRAWN: BKJ | CHECKED: | DATE: 04/12/2017 | SCALE:

PROJECT NO.

DRAWING TITLE: DEMOLITION PLAN

DRAWING NO. CD-1.0

SHEET OF