

FINISH SCHEDULE																
ROOM NUMBER	SPACE NAME	FLOOR		BASE	NORTH WALL		SOUTH WALL		EAST WALL		WEST WALL		CEILING			REMARKS
		MATERIAL	FINISH	MATERIAL	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	MATERIAL	FINISH	HEIGHT	
FIELDHOUSE																
101	MEETING ROOM	CONC	EPX	EPX	CMU	PT	CMU	PT	CMU	PT	CMU	PT	PLYWD	PT	9'-0"	NOTE 1
102	SERVER CLOSET	CONC	EPX	EPX	CMU	PT	CMU	PT	CMU	PT	CMU	PT	PLYWD	PT	9'-0"	NOTE 1
103	WOMAN S TOILET	CONC	EPX	EPX	CMU	PT-E	CMU	PT-E	CMU	PT-E	CMU	PT-E	PLYWD	PT-E	9'-0"	NOTE 1
104	MEN S TOILET	CONC	EPX	EPX	CMU	PT-E	CMU	PT-E	CMU	PT-E	CMU	PT-E	PLYWD	PT-E	9'-0"	NOTE 1
105	FAMILY TOILET	CONC	EPX	EPX	CMU	PT-E	CMU	PT-E	CMU	PT-E	CMU	PT-E	PLYWD	PT-E	9'-0"	NOTE 1
106	UTILITY ROOM	CONC	CS	-	CMU	-	CMU	-	CMU	-	CMU	-	EXPD	-	-	
107	GENERAL STORAGE (LARGE)	CONC	CS	-	CMU	-	CMU	-	CMU	-	CMU	-	EXPD	-	-	
108	CONCESSIONS	CONC	EPX	EPX	CMU	PT-E	CMU	PT-E	CMU	PT-E	CMU	PT-E	PLYWD	PT-E	9'-0"	NOTE 1
109	CONCESSIONS WASHROOM	CONC	EPX	EPX	CMU	PT-E	CMU	PT-E	CMU	PT-E	CMU	PT-E	PLYWD	PT-E	9'-0"	NOTE 1
110	CONCESSIONS STORAGE	CONC	EPX	EPX	CMU	PT-E	CMU	PT-E	CMU	PT-E	CMU	PT-E	PLYWD	PT-E	9'-0"	NOTE 1
111	GENERAL STORAGE (SMALL)	CONC	CS	-	CMU	-	CMU	-	CMU	-	CMU	-	EXPD	-	-	
112	UMPIRE S LOCKER ROOM	CONC	EPX	EPX	CMU	PT	CMU	PT	CMU	PT	CMU	PT	PLYWD	PT	9'-0"	NOTE 1
113	LOCKER ROOM TOILET	CONC	EPX	EPX	CMU	PT	CMU	PT	CMU	PT	CMU	PT	PLYWD	PT	9'-0"	NOTE 1
DUGOUT																
DW1	DUGOUT STORAGE	CONC	CS	-	CMU-2	-	CMU-2	-	CMU-2	-	CMU-2	-	EXPD	-	VARIES	NOTE 2,3
DW2	DUGOUT STORAGE	CONC	CS	-	CMU-2	-	CMU-2	-	CMU-2	-	CMU-2	-	EXPD	-	VARIES	NOTE 2,3
DE1	DUGOUT STORAGE	CONC	CS	-	CMU-2	-	CMU-2	-	CMU-2	-	CMU-2	-	EXPD	-	VARIES	NOTE 2,3
DE2	DUGOUT STORAGE	CONC	CS	-	CMU-2	-	CMU-2	-	CMU-2	-	CMU-2	-	EXPD	-	VARIES	NOTE 2,3
ABBREVIATIONS:																
CMU	CONCRETE MASONRY UNIT			PLYWD	PLYWOOD											
CMU-2	ARCHITECTURAL CMU			PT	PAINT											
CONC	CONCRETE			PT-E	PAINT (EPOXY PAINT)											
CS	CONCRETE SEALER															
EPX	EPOXY COATING															
EXPD	EXPOSED															
FINISH SCHEDULE NOTES:																
1. TRIM BOARD. INSTALL 1 X 4 TRIM BOARD ON WALL AT THE CEILING (AS CROWN MOLDING), FINISH TRIM BOARD TO MATCH CEILING PAINT COLOR.																
2. ARCHITECTURAL CMU, CMU-2 IS FOR ARCHITECTURAL CMU. THE DUGOUTS ARE BEING CONSTRUCTED WITH ARCHITECTURAL CMU. SEE DRAWING A-101 DUGOUT FLOOR PLAN FOR LAYOUT OF CMU-1 AND CMU-2 AND INFORMATION PROVIDED IN FLOOR PLAN NOTES.																
3. DUGOUT FLOOR, SEE A-101 FLOOR PLAN NOTES REGARDING FINISH FOR DUGOUT SPACE FLOOR.																

FURNISHING AND EQUIPMENT (FFE) SCHEDULE							
FEE NO.	TY.	LOCATION	DESCRIPTION	SIZE			REMARKS
				WIDTH	HEIGHT	DEPTH	
1	6	FH	LOCKERS	18"	72"	18"	
2	2	FH	LOCKER ROOM BENCH	12"	16"	36"	MOVEABLE
3	12	D	DUGOUT BENCH	7'-6"	34'-3/8"	30"	2-TIERED STYLE WITH UPPER AND LOWER SEATING. THREE (3) BENCHES PER DUGOUT. HEIGHT NOTED IS BENCH TOTAL HEIGHT
4	4	D	DUGOUT BAT/ EQUIPMENT BIN	65"	33'-3/4"		ONE (1) PER DUGOUT
5	1	FH	TACK BOARD (L)	7'-0"	4'-0"		
6	1	FH	BULLETIN BOARD DISPLAY CASE (L)	7'-0"	44"		
7	1	FH	TACK BOARD (S)	38"			
8	1	FH	BULLETIN BOARD DISPLAY CASE (S)	38"	44"		
ABBREVIATIONS:							
D	DUGOUT						
FH	FIELD HOUSE						
NOTES:							

FURNISHING AND EQUIPMENT SPECIFICATIONS	
FEE NO.	PRODUCT
3	DUGOUT BENCH BENCH BASIS OF DESIGN SHALL BE: -- ELITE BENCH, SKU ELTE, PROVIDED BY BASEBALL RACKS, OR APPROVED EQUAL. CONTACT: DAVE PAYTON -BASEBALL RACKS 2908 W 99TH PLACE EVERGREEN PARK, IL 60805 CELL: 708-636-1047 FAX: 708-634-2948 DAVE -BASEBALLRACKS.COM HTTP://WWW.BASEBALLRACKS.COM BENCH SHALL HAVE: A. 2-TIERED STYLE UPPER AND LOWER LEVEL SEATING B. SPIKE RESISTANT COMPOSITE DECKING C. TREATED WOOD FRAME D. BOLT TOGETHER TO FORM ONE CONTINUOUS STRING
4	BAT, HELMET, EQUIPMENT STORAGE BIN STORAGE UNIT BASIS OF DESIGN SHALL BE -- YANKEE CLIPPER, SKU YNCL, PROVIDED BY BASEBALL RACKS, OR APPROVED EQUAL. CONTACT: DAVE PAYTON -BASEBALL RACKS 2908 W 99TH PLACE EVERGREEN PARK, IL 60805 CELL: 708-636-1047 FAX: 708-634-2948 DAVE -BASEBALLRACKS.COM HTTP://WWW.BASEBALLRACKS.COM STORAGE UNIT SHALL HAVE: A. TWELVE (12) HELMET CUBBIES CUBBIES SHALL BE ABLE TO HOLD HELMETS WITH OR WITHOUT FACE MASKS B. TWO (2) LARGE CATCHER GEAR COMPARTMENTS C. COACH STORAGE COMPARTMENT D. BAT BOX COMPARTMENTS E. ONE PIECE CONSTRUCTION (NO ASSEMBLY REQUIRED) F. PROVIDE HARDWARE FOR ATTACHING UNIT TO DUGOUT WALL
NOTES: THIS SCHEDULE IS PROVIDED TO FURNISH PRODUCT DATA INFORMATION ON THE PRODUCTS LISTED. THE PRODUCTS CORRESPOND TO THE PRODUCTS LISTED IN THE FURNISHING AND EQUIPMENT (FFE) SCHEDULE. SEE APPLICABLE SPECIFICATION SECTION FOR INFORMATION ON ANY FURNISHINGS AND/OR EQUIPMENT NOT SPECIFICALLY LISTED IN THIS SCHEDULE.	

Order Plans @

SKYLINE
ENGINEERING & CONSTRUCTION

100 Airport and Company
Engineers, Architects, Planners
225 Foxshire Street, N.E. International Tower
Atlanta, Georgia 30328
404-577-4000 FAX 404-977-7119

DESIGNED DRAWN
AH TS

CHECKED DATE
AH

SCALE
AS SHOWN

PROJECT NO.
C-1610-10

DRAWING TITLE
FINISH SCHEDULES AND FFE

CLIENT: City of **Dunwoody**

PROJECT: **BASEBALL FACILITIES AT BROOK RUN PARK**

SYMBOL

DATE

BY

REVISION

SHEET **A-6.00** OF

RAC #: 1700200