DEMOLITION NOTES:

1. REMOVE DRAIN VALVE BACK TO MAIN. REMOVE TEE FROM MAIN AND PROVIDE NEW PIPING AND FIBERGLASS INSULATION.
2. REMOVE (3) VERTICAL DEADLEGS WITH DRAIN VALVES BACK TO MAIN. REMOVE TEE FROM MAIN AND PROVIDE NEW PIPING AND FIBERGLASS INSULATION.
3. REMOVE DEADLEG BACK TO MAIN. REMOVE TEE FROM MAIN AND PROVIDE NEW PIPING AND FIBERGLASS INSULATION.
4. REMOVE 3/4 INCH DEADLEG WITH VALVE BACK TO MAIN. REMOVE TEE FROM MAIN AND PROVIDE NEW PIPING AND FIBERGLASS INSULATION.
5. REMOVE 6 INCH LONG DEADLEG IN VERTICAL BACK TO MAIN. REMOVE TEE FROM MAIN AND PROVIDE NEW PIPING AND FIBERGLASS INSULATION.
6. FIRESTOP OPENING IN SLAB UPON REMOVAL OF PIPE.
7. SEE DRAWING PD-77-401 FOR CONTINUATION.
8. REMOVE 4 INCH LONG 1/2" DEADLEG AND DRAIN VALVE BACK TO MAIN. REMOVE TEE FROM MAIN AND PROVIDE NEW PIPING AND FIBERGLASS INSULATION.
9. REMOVE 6 INCH LONG DEADLEG AND 3/4" DRAIN VALVE BACK TO MAIN. REMOVE TEE FROM MAIN AND PROVIDE NEW PIPING AND FIBERGLASS INSULATION.

CRAWL SPACE MAY CONTAIN ASBESTOS. ASBESTOS AWARENESS TRAINING, RESPIRATORS AND PROTECTIVE CLOTHING ARE REQUIRED.

PLAN NORTH 1 **CRAWL SPACE PLUMBING DEMOLITION PLAN**
SCALE: 1/8" = 1'-0"

PLAN NORTH 2 **CRAWL SPACE PARTIAL PLUMBING DEMOLITION PLAN**
SCALE: 1/4" = 1'-0"

PLAN NORTH 3 **CRAWL SPACE PARTIAL PLUMBING DEMOLITION PLAN**
SCALE: 1/4" = 1'-0"

Order Plans @ WWW.LDLine.com

Revisions	Date
-	-

Atriax, pllc
102 3rd Avenue, NE
PO Box 1629,
Hickory, NC 28603
Phone: 828.315.9962
Fax: 828.315.9984
www.atriaxgroup.com

Wiley|Wilson
Wiley|Wilson
127 Nationwide Drive
Lynchburg, VA 24502
Phone: 434.847.1901
www.wileywilson.com

COMMONWEALTH OF VIRGINIA — MICHAEL V. GEHL — Lic. No. 24298 — 4/22/2017 — PROFESSIONAL ENGINEER

Approved: Energy Engineer	Approved: Safety Manager	Approved: Service Chief
CONSTRUCTION DOCUMENTS	Approved: Infection Control Officer	Approved: Chief of Staff
	Approved: GEMS Coordinator	Approved: Associate Director

Drawing Title: PD-77-101 BLDG 77 CRAWL SPACE PLUMBING PLAN DEMOLITION	Project Title: RENOVATE FOR WATER QUALITY		Date: 04/ 28 / 2017
Approved: Chief of Facility Management Svc.	Building Number: 77	Checked: MJG / Drawn: JPH	Project No.: 658-15-101
Approved: Medical Center Director	Location: VA MEDICAL CENTER, SALEM, VA 24153		DRAWING SET: 2592 Dwg. 49 Of 155

Veterans Affairs