



- CONSTRUCTION NOTES:**
- INSULATE PIPING WITH FIBERGLASS INSULATION.
 - REPLACE EXISTING GATE VALVE WITH BALL VALVE.
 - PROVIDE NEW BALL VALVE.
 - REPLACE EXISTING GATE VALVE ON DHWR WITH COMBINATION SHUTOFF / CALIBRATED BALANCING VALVE. BALANCE TO 0.5 GPM.
 - PROVIDE COMBINATION SHUTOFF / CALIBRATED BALANCING VALVE ON DHWR. BALANCE TO 0.5 GPM.
 - CONNECT NEW DDC PANEL IN SUB-BASMENT MECHANICAL ROOM TO EXISTING BAS NETWORK VIA EXISTING SHUNT MODEL 538 865 HIGH SPEED TRUNK ISOLATOR EXTENDER. MODIFY AS REQUIRED TO PROVIDE NETWORK CONNECTION. REFER TO DWG 12-INS-CS-102 FOR NEW DDC PANEL.
 - PROVIDE NEW BUTTERFLY VALVE.

CRAWL SPACE MAY CONTAIN ASBESTOS. AWARENESS TRAINING, RESPIRATORS AND PROTECTIVE CLOTHING ARE REQUIRED.

PLAN NORTH
 1 CRAWL SPACE PLUMBING PLAN
 SCALE: 1/8" = 1'-0"

Order Plans @

Revisions	Date

Atrix
 Atrix, plc
 102 3rd Avenue, NE
 PO Box 1628,
 Hickory, NC 28603
 Phone: 828.315.9962
 Fax: 828.315.9964
 www.atraxisgroup.com

Wiley/Wilson
 Wiley/Wilson
 127 Natterville Drive
 Lynchburg, VA 24502
 Phone: 434.947.1901
 www.wileywilson.com



Approved: Energy Engineer
 Approved: Safety Manager
 Approved: Infection Control Officer
 Approved: GEMS Coordinator

CONSTRUCTION DOCUMENTS

Approved: Service Chief
 Approved: Chief of Staff
 Approved: Associate Director

Drawing Title
 PL-12-101
 BLDG 12 CRAWL SPACE PLUMBING PLAN
 NEW WORK

Approved: Chief of Facility Management Svcs.
 Approved: Medical Center Director

Project Title
 RENOVATE FOR WATER QUALITY

Building Number 12
 Location VA MEDICAL CENTER, SALEM, VA 24153

Date 04/28/2017
 Project No. 658-15-101
 DRAWING SET
 2592
 Dwg. 92 Of 155

Veterans Affairs