



- CONSTRUCTION NOTES:**
- 1 INSULATE PIPING WITH FIBERGLASS INSULATION.
 - 2 REPLACE EXISTING GATE VALVE WITH BALL VALVE.
 - 3 PROVIDE NEW BALL VALVE.
 - 4 REPLACE EXISTING GATE VALVE WITH COMBINATION SHUTOFF/CALIBRATED BALANCING VALVE ON DHWR. BALANCE TO 0.5 GPM.
 - 5 PROVIDE COMBINATION SHUTOFF/CALIBRATED BALANCING VALVE ON DHWR. BALANCE TO 0.5 GPM.
 - 6 REPLACE EXISTING GATE VALVE WITH COMBINATION SHUTOFF/CALIBRATED BALANCING VALVE ON DHWR. BALANCE TO 1.0 GPM.

CRRAWL SPACE MAY CONTAIN ASBESTOS. ASBESTOS AWARENESS TRAINING, RESPIRATORS AND PROTECTIVE CLOTHING ARE REQUIRED.

1 CRAWL SPACE PLUMBING PLAN
SCALE: 1/8" = 1'-0"

2 CRAWL SPACE PARTIAL PLUMBING PLAN
SCALE: 1/4" = 1'-0"

3 CRAWL SPACE PARTIAL PLUMBING PLAN
SCALE: 1/4" = 1'-0"

Order Plans

three inches = one foot
 one and one-half inches = one foot
 one inch = one foot
 three-quarters inch = one foot
 one-half inch = one foot
 one-quarter inch = one foot
 three-eighths inch = one foot
 one-eighth inch = one foot

Revisions Date	 Atrix, LLC 102 3rd Avenue, NE PO Box 1628, Hickory, NC 28603 Phone: 828.315.9962 Fax: 828.315.9964 www.atrigrp.com	 Wiley Wilson 127 Nantowite Drive Lynchburg, VA 24502 Phone: 434.947.1901 www.wileywilson.com		Approved: Energy Engineer <div style="text-align: center; font-weight: bold; font-size: 1.2em;">CONSTRUCTION DOCUMENTS</div>	Approved: Safety Manager Approved: Infection Control Officer Approved: GEMS Coordinator	Approved: Service Chief Approved: Chief of Staff Approved: Associate Director	Drawing Title PL-77-101 BLDG 77 CRAWL SPACE PLUMBING PLAN NEW WORK	Project Title RENOVATE FOR WATER QUALITY	Date 04/28/2017 Project No. 658-15-101	Building Number 77 Checked MUG Drawn JPH	Location VA MEDICAL CENTER, SALEM, VA 24153	DRAWING SET 2592 Dwg. 97 Of 155	Veterans Affairs
-------------------	--	--	--	---	---	---	--	--	---	---	--	--	-------------------------