DOMESTIC WATER PIPE REINSULATION SCHEDULE

BUILDING NUMBER	FLOOR NUMBER	INSULATION NUMBER	ROOM	USE (HOT WATER, HOT WATER RECIRC OR COLD WATER)	IS INSULATION ACCESSIBLE WITHOUT ARCH DEMOLITION OF SURFACE (Y/N)?	ABOVE LAY-IN CEILING (Y/N)?	PIPING MATERIAL	PIPE SIZE (INCH)	PIPE LENGTH (INCHES)	NUMBER OF 90 DEG ELBOWS	ADDITIONAL FITTINGS/VALVES	REFERENCE DRAWING
2	BASEMENT	2-INS-B-01	MECH ROOM (32)	HOT WATER RECIRC	Y	N	COPPER	1"	420	7	(1) UNION, (1) GATE VALVE	PL-2-401
2	BASEMENT	2-INS-B-02	MECH/LIFE SAFETY EQUIP ROOM (21A)	COLD WATER	Y	N	COPPER	4"	170	4	(2) GATE, (2) CHECK, (1) STRAINER, (1) FLANGE	PL-2-401
2	2	2-INS-2-01	CORRIDOR (C2-2) CORRIDOR (C2-5)	HOT WATER RECIRC	Y	Y	COPPER	3/4"	240	2	–	PL-2-103
2	3	2-INS-3-01	CORRIDOR (C3-1) LOBBY (C3-1A) CORRIDOR (C3-2)	HOT WATER RECIRC	Y	Y	COPPER	1/2"	400	2	(1) BALANCING VALVE	PL-2-104
2	3	2-INS-3-02	MEDICATION (302) LOBBY (C3-1A)	HOT WATER	Y	Y	COPPER	1/2"	280	1	–	PL-2-104
2A	BASEMENT	2A-INS-B-01	MECHANICAL ROOM (G068)	COLD WATER	Y	N	COPPER	1 1/2"	60	3	(2) GATE, (2) CHECK, (1) STRAINER, (1) FLANGE	PL-2A-401
2A	BASEMENT	2A-INS-B-02	MECHANICAL ROOM (G068)	COLD WATER	Y	N	COPPER	4"	60	3	(2) GATE, (2) CHECK, (1) STRAINER, (1) FLANGE	PL-2A-401
2A	BASEMENT	2A-INS-B-03	OBSERVATION ROOM (G012) CORRIDOR (CG-3)	COLD WATER	Y	Y	COPPER	1 1/4"	200	–	–	PL-2A-101
2A	BASEMENT	2A-INS-B-04	CORRIDOR #2 (CG-28)	HOT WATER RECIRC	Y	Y	COPPER	1"	300	1	(2) BALL VALVES	PL-2A-101
2A	1	2A-INS-1-01	CORRIDOR (C1-11) HEMATOLOGY (1A-1028)	COLD WATER	Y	Y	COPPER	1"	480	4	(1) BALL VALVE	PL-2A-102
2A	1	2A-INS-1-02	EEG (1A-1003A) CORRIDOR (C1-13) KITCHEN (1A-1001)	COLD WATER	Y	[illegible]ER	[illegible]	1/2"	170	–	–	PL-2A-102
2A	1	2A-INS-1-03	EEG (1A-1003A) CORRIDOR (C1-13) KITCHEN (1A-1001)	HOT WATER	Y	[illegible]	COPPER	[illegible]2	170	–	–	PL-2A-102
2A	1	2A-INS-1-04	HEMATOLOGY (1A-1028)	COLD WATER	Y	Y	COPPER	3/4"	260	–	–	PL-2A-102
2A	1	2A-INS-1-05	HEMATOLOGY (1A-1028)	HOT WATER	Y	Y	COPPER	3/4"	260	–	–	PL-2A-102
7	BASEMENT	7-INS-B-01	HVAC RM (37)	COLD WATER	Y	N	COPPER	4"	100	–	(3) GATE, (2) CHECK, (1) STRAINER	PL-7-401
7	BASEMENT	7-INS-B-02	HVAC RM (37)	COLD WATER	Y	N	COPPER	2"	100	–	(3) GATE, (2) CHECK, (1) STRAINER	PL-7-401
7	BASEMENT	7-INS-B-03	CORRIDOR (CB-4, CB-6), STORAGE (25), HVAC RM (37)	HOT WATER RECIRC	Y	Y	COPPER	3/4"	450	1	–	PL-7-101
7	BASEMENT	7-INS-B-04	CORRIDOR (CB-4, CB-6), STORAGE (25), HVAC RM (37)	HOT WATER	Y	Y/N	COPPER	3"	360	1	–	PL-7-101
7	BASEMENT	7-INS-B-05	NURSE STATION (20), OFFICE (21), CORRIDOR (CB-5)	HOT WATER	Y	Y	COPPER	3"	230	1	–	PL-7-101
7	BASEMENT	7-INS-B-06	CORRIDOR (CB-7, CB-10)	COLD WATER	Y	Y	COPPER	1 1/2"	180	1	–	PL-7-101
7	BASEMENT	7-INS-B-07	OFFICE AREA (18), COMM HEALTH NURSE (19)	HOT WATER RECIRC	Y	Y	COPPER	3/4"	180	1	–	PL-7-101
7	BASEMENT	7-INS-B-08	CORRIDOR (CB-7), UNISEX TOILET (30)	COLD WATER	Y	Y	COPPER	1 1/2" 2 1/2"	300 180	13 2	(1) GATE VALVE	PL-7-101
7	BASEMENT	7-INS-B-09	CORRIDOR (CB-7), UNISEX TOILET (30)	HOT WATER	Y	Y	COPPER	1/2" 1 1/2"	210 180	9 2	(1) GATE VALVE	PL-7-101

Order Plans @ WWW.DLine.com

Revisions	Date

Atriax, pllc
102 3rd Avenue, NE
PO Box 1629,
Hickory, NC 28603
Phone: 828.315.9962
Fax: 828.315.9994
www.atriaxgroup.com

WileyWilson
127 Nationwide Drive
Lynchburg, VA 24502
Phone: 434.947.1901
www.wileywilson.com

COMMONWEALTH OF VIRGINIA
MICHAEL J. GEHL
Lic. No. 24288
4/28/2017
PROFESSIONAL ENGINEER

Approved: Energy Engineer

CONSTRUCTION DOCUMENTS

Approved: Safety Manager
Approved: Infection Control Officer
Approved: GEMS Coordinator

Approved: Service Chief
Approved: Chief of Staff
Approved: Associate Director

Drawing Title: PL-602 SCHEDULES

Approved: Chief of Facility Management Svc.
Approved: Medical Center Director

Project Title: RENOVATE FOR WATER QUALITY

Building Number | Checked: MJG | Drawn: WJC

Location: VA MEDICAL CENTER, SALEM, VA 24153

Date: 04/28/2017
Project No.: 658-15-101
DRAWING SET: 2592
Dwg. 124 Of 155

Veterans Affairs