

www.LDOnline.com

CONTRACTOR SHALL VERIFY THERE IS A FLOOR OR LANDING AT THE SAME ELEVATION ON EACH SIDE OF THE DOOR. NOTIFY ARCHITECT IF VARIES.

METAL DECK CANOPY - SEE 6/A-2.0

FIRE EXTINGUISHER - SEE NEW WORK NOTE 2.

PROVIDE 5'X8" SIGN TO READ "AREA FOR FLEX CONVEYOR STORAGE WHEN NOT IN USE".

ALARM SYSTEM. REFER TO DETAIL B/A-2.6

PAINT SOLID (WHITE) FOR FLEX CONVEYOR STORAGE

PAINT SOLID (YELLOW) 36" IN FRONT AND 1'-6" ON SIDES OF FREIGHT DOORS AS DEDICATED CLEAR SPACE.

HELIUM TANKS AND STORAGE

SHELVING - SEE DETAIL 2/A-2.6

PAINT 6" WHITE STRIPE AT PERIMETER OF STOCKROOM

PAINT SOLID (YELLOW) 42" IN FRONT OF AND TO THE SIDE OF ELECT PANEL AS DEDICATED CLEAR FLOOR SPACE.

5 1/2" X 1 1/2" (18 GA) STEEL ANGLE - SEE DETAIL 6/A-3.1

APPROX LOCATION OF ELECTRICAL PANELS

METAL DECK CANOPY - SEE 1/A-4.0

CONTRACTOR SHALL VERIFY THERE IS A FLOOR OR LANDING AT THE SAME ELEVATION ON EACH SIDE OF THE DOOR. NOTIFY ARCHITECT IF VARIES.

CONTRACTOR SHALL VERIFY THERE IS A FLOOR OR LANDING AT THE SAME ELEVATION ON EACH SIDE OF THE DOOR. NOTIFY ARCHITECT IF VARIES.

FIRE EXTINGUISHER - SEE NEW WORK NOTE 2.

EXISTING COLUMN - PAINT YELLOW AND PROVIDE STAINLESS STEEL COVER TO 4'-0" AFF. (TYP OF 4) REFER TO DETAIL 3/A-2.6 AND NEW WORK NOTE 6.

**GENERAL INFORMATION:**

SHOPPING CENTER:	FEE DEV.
CITY:	COLUMBUS
STATE:	GEORGIA
CEILING HEIGHT (SALES AREA):	10'-0"
<b>SPRINKLERED:</b>	
<b>SQUARE FOOTAGES</b>	
TOTAL SPACE LEASED:	8,245 SF
SALES FLOOR AREA:	1,702 SF 17.1 %
NON-SALE AREA:	856 SF 8.6 %
USABLE STOCKROOM:	7,690 SF
USABLE SALES FLOOR:	7,690 SF
DOOR HEIGHT:	18'-2 1/2"

**WALL CONSTRUCTION TYPES**

- EXTERIOR DEMISING WALL: CMU VENEER OVER 1" EXTRUDED POLYSTYRENE FOAM OVER METAL STUDS AND BATT INSULATION OVER GWB BELOW 4'-0" AFF. EIFS OVER SHEATHING OVER METAL STUDS AND BATT OVER GWB ABOVE 4'-0" AFF. SEE DETAIL 1 & 3/A-4.1. FINISH PER FINISH SCHEDULE, SHEET A-3.1.
- PARTITION WALL: 6" (20 GA) METAL STUDS @ 16" OC WITH ONE LAYER 5/8" GWB EACH SIDE TO ROOF DECK ON SALES AREA SIDE AND TO 12'-0" AFF ON STOCKROOM SIDE. SEE DETAIL 1/A-4.2 FOR ADDITIONAL REQUIREMENTS AND BRACING. FINISH PER FINISH SCHEDULE, SHEET A-3.1.
- PARTITION WALL: 6" (20 GA) METAL STUDS @ 16" OC WITH ONE LAYER 5/8" GWB EACH SIDE TO ROOF DECK ON STOCKROOM / SALES AREA SIDE AND TO FINISHED CEILING ON TOILET SIDE. PLUMBING WALLS ON INTERIOR OF TOILETS SHALL HAVE WATER RESISTANT GWB. SEE DETAIL 2/A-4.2 FOR ADDITIONAL REQUIREMENTS AND BRACING. FINISH PER FINISH SCHEDULE, SHEET A-3.1.
- PARTITION WALL: 3 5/8" (20 GA) METAL STUDS @ 16" OC WITH ONE LAYER 5/8" GWB TO FINISHED CEILING. PLUMBING WALLS ON INTERIOR OF TOILETS SHALL HAVE WATER RESISTANT GWB. SEE DETAIL 2/A-2.4. FINISH PER FINISH SCHEDULE, SHEET A-3.1.
- PARTITION WALL: 3 5/8" (20 GAGE) METAL STUDS @ 16" OC WITH ONE LAYER 5/8" GWB TO ROOF DECK ON SALES AREA SIDE AND TO 12'-0" AFF ON OFFICE SIDE. SEE DETAIL 3/A-2.3. FINISH PER FINISH SCHEDULE SHEET A-3.1.
- PARTITION WALL: 3 5/8" (18 GAGE) METAL STUDS @ 12" OC WITH ONE LAYER 5/8" GWB EACH SIDE TO 5'-0" AFF. SEE DETAIL 1/A-2.4. FINISH PER FINISH SCHEDULE SHEET A-3.1.

FLOOR PLAN  
SCALE: 1/8" = 1'-0"



	<b>DOLLAR TREE</b> COLUMBUS, GA	
	INTERIOR FLOOR PLAN & WALL CONSTRUCTION TYPES	
PROJ. NO. 17138-73	DWG. NO. A-1.1	DATE: 08/08/17 REV: DRN, LGS, CHK

Order Plans