



| Symbol | Qty | Label | Arrangement | Description | LLF | Tot. LamPum | Arr. Watts |
|--------|-----|-------|-------------|--|-------|-------------|------------|
| SL1 | 6 | SL1 | SINGLE | NEL-AL150 TWIN 22' POLE WITH 2' BASE | 0.950 | 20069 | 152.93 |
| SL4 | 3 | SL4 | SINGLE | NEL-AL150 T4 22' POLE WITH 2' BASE | 0.950 | 18597 | 154.1 |
| WM | 12 | WM | SINGLE | N-L-WE-10 MTD 12' AFG | 0.950 | 4383.8 | 41.2 |
| UMA | 2 | UMA | SINGLE | N-L-WE-10 MTD 12' AFG | 0.950 | N.A. | 34 |
| SL4T | 2 | SL4T | 2 @ 9' | NEL-AL150 T4 TWIN ON 22' POLE WITH 2' BASE | 0.950 | 18597 | 308.2 |

GENERAL NOTE:
 ALL FIXTURES & POLES ARE PROVIDED BY DOLLAR TREE FOR INSTALLATION BY CONTRACTOR. ANY SONOTUBES, CONDUIT, ETC. ARE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE & INSTALL. SEE SCHEDULE ABOVE FOR MOUNTING HEIGHTS. CONTRACTOR SHALL CONTACT UTILITIES TO VERIFY LOCATIONS AS SOON AS NOTICE TO PROCEED IS ISSUED FOR ORDERING DOLLAR TREE SUPPLIED SITE LIGHTING.

PETER COLON PROJECT MANAGER
 617-510-7540
 eterc@nelcom.com

MI SCHMIDT
 617-510-7540
 scmidt@nelcom.com

POLE NOTE:
 22" STEEL ROUND TAPERED POLE - 5" TAPER WITH BRONZE COLOR.
 POLE SHALL BE RATED TO 130 MPH

SITE LIGHTING PLAN
 SCALE: 1"=20'-0"

| | | | | |
|--|------|------|--------|------------------|
| | REV. | DATE | BY/CHK | DESCRIPTION |
| | | | | |
| | | | | DOCUMENT CONTROL |

| | |
|--------------------|-----------------|
| | |
| COLUMBUS, GA | |
| SITE LIGHTING PLAN | |
| PROJ. NO. 605617 | DWG. NO. ES-1.1 |