

HVAC GENERAL NOTES

- MECHANICAL CONTRACTOR SHALL FURNISH ALL LABOR, MATERIAL AND EQUIPMENT REQUIRED FOR THE COMPLETE INSTALLATION AND OPERATION OF ALL SYSTEMS IN THIS SECTION OF WORK IN ACCORDANCE WITH RECOMMENDED PRACTICE AND ALL APPLICABLE CODES ADOPTED BY THE AUTHORITY HAVING JURISDICTION.
- DO NOT SCALE DRAWINGS. SEE ARCHITECTURAL DRAWINGS FOR EXACT LOCATION OF WALLS, DOORS, WINDOWS, FURNITURE, LIGHTS, CEILING DIFFUSERS, ETC.
- ALL MECHANICAL PERMITS AND INSPECTION FEES SHALL BE OBTAINED AND PAID FOR BY THE MECHANICAL CONTRACTOR.
- MECHANICAL CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS FOR ONE YEAR. REFRIGERANT COMPRESSORS SHALL BE GUARANTEED FOR FIVE YEARS. WARRANTY PERIOD SHALL BE EFFECTIVE THE DAY THE PROJECT IS ACCEPTED BY THE OWNER.
- DRAWINGS ARE DIAGRAMMATIC AND MAY NOT SHOW ALL REQUIRED FITTINGS. MECHANICAL CONTRACTOR IS RESPONSIBLE FOR COORDINATING THE TYPE, SIZE AND LOCATION OF ALL AIR DEVICES, DUCTWORK, PIPING AND EQUIPMENT WITH THE CEILING PLAN, LIGHTS, STRUCTURAL ELEMENTS AND OTHER TRADES. MECHANICAL CONTRACTOR TO FURNISH AND INSTALL ALL BENDS, OFFSETS, ELBOWS, ETC. AS REQUIRED. VERIFY ALL CLEARANCES PRIOR TO FABRICATING DUCTWORK, OR ORDERING ANY EQUIPMENT, PIPING, ETC.
- MECHANICAL CONTRACTOR IS RESPONSIBLE FOR PROVIDING MATERIALS AND INSTALLING THE WORK IN ACCORDANCE WITH ALL APPLICABLE LOCAL, STATE AND NATIONAL CODES ADOPTED BY THE AUTHORITY HAVING JURISDICTION.
- DUCTWORK
 - ALL DUCTWORK SHALL BE GALVANIZED SHEET METAL CONSTRUCTED IN ACCORDANCE WITH SMACNA STANDARDS WITH A MINIMUM PRESSURE CLASSIFICATION OF 2", SEAL CLASS C, WITH A MAXIMUM LEAKAGE RATE OF 5K.
 - ALL SQUARE ELBOWS SHALL HAVE TURNING VANES.
 - ALL DUCT DIMENSIONS SHOWN ARE INTERNAL CLEAR DIMENSIONS.
 - PROVIDE A MANUAL BALANCING DAMPER AT ALL SUPPLY AND RETURN BRANCH TAKEOFFS, AS WELL AS ALL OUTSIDE AIR MAIN & BRANCH DUCTS.
 - FLEXIBLE DUCT, IF SHOWN ON DRAWINGS, SHALL BE INSULATED ROUND DUCT WITH AN OUTER GLASS REINFORCED SILVER MYLAR JACKET ENCLOSING GLASS FIBER INSULATION AROUND A CONTINUOUS INNER LINER, AND SHALL CONFORM TO THE REQUIREMENTS OF UL 181 FOR CLASS 1 FLEXIBLE AIR DUCTS. MAXIMUM LENGTH OF FLEXIBLE DUCT SHALL BE 6 FEET. R-6 VALUE TO MEET/EXCEED ENERGY CODE (M.C. SECTION 603.8.8) DUCT INSULATION IS TO BE MIN. R-6 WHEN LOCATED WITHIN THE CONDITIONED BUILDING ENVELOPE; MIN. R-8 WHEN LOCATED IN THE ATTIC, OUTSIDE THE BUILDING ENVELOPE OR UNCONDITIONED SPACES.
 - ALL SHEET METAL DUCTWORK WITHIN 10' OF THE AIR HANDLING UNIT SHALL BE PROVIDED WITH ACOUSTICAL DUCT LINER. THIS IS IN ADDITION TO THERMAL INSULATION REQUIREMENTS.
 - ALL DUCT SYSTEMS ARE TO BE PER U.L. STANDARDS. DUCTS ARE TO BE INSTALLED WITH NO RESTRICTIONS AND AN ABSOLUTE MINIMUM AMOUNT OF AIR LEAKAGE.
 - ALL DUCT INSULATION SHALL BE RUN CONTINUOUSLY THROUGH FLOORS AND PARTITIONS.
 - KITCHEN GREASE HOOD EXHAUST SHALL BE 16 GA. STEEL WITH LIQUID TIGHT WELDED JOINTS. DUCT SHALL SLOPE NOT LESS THAN 1/4" PER F-0' TOWARD THE HOOD PER IMC SECTION 506.3.7. WHERE HORIZONTAL DUCT RUNS EXCEED 75 FEET, THEN DUCT SHALL SLOPE NOT LESS THAN 1/8" PER F-0'. PROVIDE GREASE TIGHT ACCESS DOORS OF THE SAME MATERIAL AS THE DUCT FOR CLEANING AT ALL CHANGES IN DIRECTION, AT 20' INTERVALS AND AT THE HOOD AND FAN CONNECTIONS.
- PIPING
 - CONDENSATE DRAINS SHALL BE SCHEDULE 40 PVC OR TYPE L COPPER WITH SOLDERED JOINTS WHEN INSTALLED BELOW CEILING LEVEL. DRAINS INSTALLED IN A RETURN AIR PLENUM SHALL BE TYPE L COPPER WITH SOLDERED JOINTS OR SCHEDULE 40 CPVC.
- INSULATION
 - DUCT LINER - FIBROUS GLASS DUCT LINER, WITH COATED SURFACE EXPOSED TO AIR STREAM. APPLY WITH MECHANICAL FASTENERS AND 100% COVERAGE OF ADHESIVE LINER TO BE COATED WITH AN EPA REGISTERED ANTI-MICROBIAL AGENT. DUCT INSULATION VALUE IS TO BE MIN. R-6 WHEN LOCATED WITHIN THE CONDITIONED BUILDING ENVELOPE; MIN. R-8 WHEN LOCATED IN THE ATTIC, OUTSIDE THE BUILDING ENVELOPE OR UNCONDITIONED SPACES. DUCT LINER USED FOR ACOUSTICAL PURPOSES ONLY SHALL BE 1" THICK.
 - DUCT WRAP - MINERAL FIBER BLANKET, WITH REINFORCED FOIL AND PAPER VAPOR RETARDANT JACKET. APPLY WITH MECHANICAL FASTENERS AND ADHESIVE. DUCT INSULATION IS TO BE MIN. R-6 WHEN LOCATED WITHIN THE CONDITIONED BUILDING ENVELOPE; MIN. R-8 WHEN LOCATED IN THE ATTIC, OUTSIDE THE BUILDING ENVELOPE OR UNCONDITIONED SPACES.
 - INTERIOR CONDENSATE DRAINS - INSULATE CONDENSATE DRAINS LOCATED IN THE ATTIC, EXTERIOR WALLS OR UNCONDITIONED SPACES WITH 1/2" THICK FLEXIBLE ELASTOMERIC PIPE INSULATION.
 - AIR DISTRIBUTION - INSULATE THE TOP-SIDE OF ALL AIR DISTRIBUTION DEVICES.
- ALL PIPING, DUCTS, VENTS, ETC., EXTENDING THROUGH WALLS & ROOF SHALL BE FLASHED & COUNTER-FLASHED IN A WATERPROOF MANNER.
- EXTEND ALL CONDENSATE DRAINS TO SPLASH BLOCKS ON ROOF OR AS REQUIRED PER CODE. DRAINS FROM MECHANICAL EQUIPMENT SHALL BE PROVIDED W/ A DEEP SEAL TRAP. SLOPE CONDENSATE DRAIN PIPING AT MIN. 1/8" PER FOOT.
- LOCATE ALL THERMOSTATS, SWITCHES AND OTHER CONTROL DEVICES AT 4'-0" ABOVE FINISHED FLOOR. FURNISH A THERMOSTATIC CONTROL DEVICE FOR EVERY DEVICE REQUIRING ONE WHETHER SHOWN ON DRAWINGS OR NOT.
- ALL EQUIPMENT SHALL BE INSTALLED PER CODE & MANUFACTURERS REQUIREMENTS FOR PROPER OPERATION AND SERVICE/ACCESS CLEARANCES.
- ALL EQUIPMENT SHALL BE UL LISTED.
- MECHANICAL CONTRACTOR SHALL CONTRACT A CERTIFIED 3RD PARTY TEST & BALANCE COMPANY TO BALANCE ALL MECHANICAL SYSTEMS TO AIR QUANTITIES INDICATED ON PLANS AND PROVIDE A COMPLETE BALANCING REPORT IN ACCORDANCE WITH NEBB OR AABC STANDARDS.
- CONTROL WIRING FOR ALL MECHANICAL SYSTEMS WITHIN THIS SCOPE OF WORK SHALL BE BY THE MECHANICAL CONTRACTOR.
- DUCT SMOKE DETECTORS SHALL BE INSTALLED IN THE RETURN AIR DUCT OR PLENUM UPSTREAM OF ANY FILTERS OR DECONTAMINATION EQUIPMENT UPON ACTIVATION THE SMOKE DETECTOR SHALL SHUT DOWN THE AIR HANDLING UNIT.
 - * IF THERE IS A FIRE ALARM SYSTEM DETECTORS SHALL BE FURNISHED AND WIRED BY THE ELECTRICAL CONTRACTOR, INSTALLED BY THE MECHANICAL CONTRACTOR. ACTIVATION OF THE DUCT SMOKE DETECTOR SHALL INITIATE A VISIBLE AND AUDIBLE SUPERVISORY SIGNAL AT A CONSTANTLY ATTENDED LOCATION.
 - * IF THERE IS NOT A FIRE ALARM SYSTEM DETECTORS SHALL BE FURNISHED, WIRED AND INSTALLED BY THE MECHANICAL CONTRACTOR. ACTIVATION OF THE DUCT SMOKE DETECTOR SHALL INITIATE A VISIBLE AND AUDIBLE SUPERVISORY SIGNAL AT A CONSTANTLY ATTENDED LOCATION.
- PROVIDE A CLEAN SET OF FILTERS FOR ALL AIR HANDLING EQUIPMENT AT SUBSTANTIAL COMPLETION.
- MAINTAIN A MINIMUM 10'-0" BETWEEN OUTDOOR AIR INTAKES AND EXHAUST FAN DISCHARGE AND PLUMBING VENTS, ETC. FIELD COORDINATE FINAL LOCATIONS.
- ROOF CURBS SHALL HAVE A BASE THAT FITS SLOPE AND TYPE OF ROOF AS REQUIRED. TOP OF CURB SHALL BE LEVEL. SEE STRUCTURAL PLANS FOR SLOPE INFORMATION AND ARCHITECTURAL PLANS FOR EXACT ROOF TYPE.
- RUN DUCT UP WITHIN STRUCTURE OR THROUGH JOIST WEBS WHERE POSSIBLE & WHERE REQUIRED TO MAINTAIN CEILING HEIGHTS. PROVIDE OFFSETS AND/OR TRANSITIONS IN DUCT WHERE REQUIRED WITH MAX. 45 DEG. ELBOWS. MAKE BRANCH TAPS TO TOP, SIDES OR BOTTOM AS REQUIRED. BACK TO BACK 90 DEG. ELBOWS ALLOWED.
- ALL EQUIPMENT SHALL BE LABELED ACCORDING TO NUMBERING / IDENTIFICATION SYSTEM PER TRADE.
- ALL EQUIPMENT SUPPORTS ARE REQUIRED TO MEET ASCE 8.6.
- MECHANICAL CONTRACTOR SHALL PROVIDE UL LISTED FIRE DAMPERS, RADIATION DAMPERS AND/OR FIRE SMOKE DAMPERS WHERE REQUIRED FOR FIRE PROTECTION AS REQUIRED BY LOCAL CODES. M.C. SHALL PROVIDE A NOTICE OF ACCESS TO TEST & RESET ALL SUCH DAMPERS AND/OR ACTUATORS.
- ON MAKING PIPE CONNECTIONS TO EQUIPMENT, CARE SHOULD BE TAKEN TO CHANGE PIPES SO AS NOT TO INTERFERE WITH OPENING OF ACCESS DOORS.
- ELECTRICAL CONTRACTOR TO PROVIDE ALL HIGH VOLTAGE (100V AND GREATER) ELECTRICAL WIRING, CONDUIT, DISCONNECT SWITCHES, FUSES, ETC. TO ALL MECHANICAL EQUIPMENT WITHIN THIS SCOPE OF WORK. FINAL ELECTRICAL CONNECTIONS ARE BY ELECTRICAL CONTRACTOR. MECHANICAL CONTRACTOR SHALL COORDINATE ELECTRICAL REQUIREMENTS FOR ALL APPROVED MECHANICAL EQUIPMENT WITH THE ELECTRICAL CONTRACTOR.
- PRIOR TO BEGINNING ANY WORK MECHANICAL CONTRACTOR IS RESPONSIBLE TO NOTIFY THE OWNER'S REPRESENTATIVE, ARCHITECT OR ENGINEER IF THE MECHANICAL DESIGN CONFLICTS WITH EXISTING OR UNDISCOVERED FIELD CONDITIONS.
- MECHANICAL CONTRACTOR SHALL PROVIDE A MIN. OF FOUR COPIES OF SHOP DRAWINGS TO THE ARCHITECT/ENGINEER FOR ALL INSTALLED EQUIPMENT AND MATERIALS NEEDED APPROX. PRIOR TO INSTALLATION. IN ADDITION, M.C. SHALL PROVIDE THE OWNER WITH TWO COPIES OF OPERATION & MAINTENANCE MANUALS FOR ALL INSTALLED EQUIPMENT, MANUFACTURERS & INSTALLERS WARRANTIES AND TRAINING FOR CONTROLS OF ALL SUCH EQUIPMENT.

PACKAGED DX COOLING / GAS HEATING ROOF TOP UNIT SCHEDULE																						
UNIT DESIG.	NOMINAL COOLING (TONS)	SUPPLY - FAN DATA					COOLING CAPACITY		HEATING CAPACITY		FILTER DATA			ELECTRICAL DATA			EQUIPMENT EFFICIENCY		CONTROL SCHEME	MANUFACTURER & MODEL NO.	WEIGHT (LBS)	ACCESSORIES/ NOTES
		TOTAL AIRFLOW (CFM)	MINIMUM O.A. (CFM) (HIGH/LOW)	MINIMUM E.S.P. (IN.WG)	FAN SPEED (RPM)	MOTOR HP	TOTAL (MBH)	SENSIBLE (MBH)	INPUT (MBH) (HE/LC)	OUTPUT (MBH) (HE/LC)	TYPE	THICK (IN)	FACE VELOCITY (FT/MIN)	VOLT/PH	FLA	MCA/MOCP	COOLING EFFICIENCY (EER)	HEATING EFFICIENCY (OUT/INP)				
RTU-1	6.0	2,400	600	0.8	BY MFG.	2.4	68.3	36.3	115.0	83.0	THROWAWAY	2	-	208/3Ø	36.0	36/50	11.0	82.0X	THERMOSTAT	CARRIER 48TCD047B	662	1 - 8
RTU-2	8.5	3,400	750	0.8	BY MFG.	1.7	103.6	61.8	180.0/120.0	148.0/88.0	THROWAWAY	2	-	208/3Ø	49.0	47/60	11.0	82.0X	THERMOSTAT	CARRIER 48TCD048B	930	1 - 8

NOTES

- COOLING CAPACITIES ARE RATED IN ACCORDANCE WITH ARI STANDARD 210/290 AT 89° AMBIENT OUTDOOR AIR TEMP, 80° DRY BULB, 67° WET BULB ENTRANCE AIR TEMP, AND NOMINAL AIR QUANTITY LISTED.
- PRE-FABRICATED ROOF CURB
- PROVIDE W/ 7-DAY PROGRAMMABLE THERMOSTAT W/ CLEAR, LOCKING COVER.
- FIELD MOUNTED DISCONNECT SWITCH - TO BE PROVIDED & INSTALLED BY E.C.
- PROVIDE NEW HIGH EFFICIENCY FILTERS FOR EACH UNIT. FILTERS SHOULD BE REPLACED REGULARLY.
- LOW AMBIENT CONTROL.
- VERTICAL SUPPLY DISCHARGE & RETURN.
- PROVIDE DUAL ENTHALPY ECONOMIZER AND BAROMETRIC RELIEF.

FAN SCHEDULE												
UNIT DESIG.	SERVICE	AREA SERVED	MANUFACTURER & MODEL NO.	FAN TYPE & ARRANGEMENT	AIRFLOW (CFM)	MIN. E.S.P. (IN.WG)	FAN SPEED (RPM)	MOTOR FLA	DRIVE TYPE	ELECTRICAL DATA (VOLT/PH)	CONTROL SCHEME NOTE	ACCESSORIES/ NOTES
KEF-1	EXHAUST	NEW TYPE-1 HOOD										
KSF-1	MAKEUP AIR	NEW TYPE-1 HOOD										
EF-1, 2 & 3	EXHAUST	RESTROOMS	GREENHECK SF-550	CEILING CENTER/EGAL		0.25	BY MFG.	0.50	DIRECT	3Ø W	120V/1Ø	A 1 - 7

NOTES

- SCREEN
- BACKDRAFT DAMPER
- COLOR BY ARCHITECT
- INTEGRAL DISCONNECT SWITCH
- UL
- VIBRATION ISOLATION
- ROOF CAP W/ CURB (SEE PLANS FOR TERMINATION LOCATIONS AND ASSOCIATED ACCESSORIES)

CONTROL

- A. INTERLOCK W/ LIGHTS


DIFFUSER SCHEDULE											
SYMBOL	CFM	NECK SIZE	MODULE SIZE	FRAME TYPE	PATTERN	DAMPER	MATERIAL	SERVICE	FINISH	MANUFACTURER & MODEL NO.	ACCESSORIES/ NOTES
(A)	AS NOTED	AS NOTED	24x24	LAY-IN	4-WAY	YES	STEEL	SUPPLY	NOTE 2	PRICE SCD	1, 2
(B)	AS NOTED	AS NOTED	NECK SIZE + 5-5/8"	SURFACE	4-WAY	YES	ALUMINUM	SUPPLY	NOTE 2	PRICE PDF	1, 2
(C)	AS NOTED	AS NOTED	AS NOTED	DUCT MOUNTED	FIXED	YES	ALUMINUM	SUPPLY	NOTE 2	PRICE SDGE	1, 2
(D)	AS NOTED	AS NOTED	24x24	LAY-IN/SURFACE WALL MOUNTED	PERF.	NO	STEEL	RETURN	NOTE 2	PRICE FLOOR	1, 2
(E)	AS NOTED	AS NOTED	NECK SIZE + 1-3/4"	WALL MOUNTED	FIXED LOUVER	NO	STEEL	RETURN	NOTE 2	PRICE 520	1, 2

NOTES

- DIFFUSER DESIGNATIONS ON PLANS AS FOLLOWS:
 DIFFUSER OR NECK SIZE AIR QUANTITY → 8x4 (A) 75 → DIFFUSER TYPE AS NOTED ABOVE
- FINISH TO MATCH CEILING, WALL, STRUCTURE OR DUCT. COORDINATE FINISH W/ ARCHITECT.

MECHANICAL LEGEND			
	SUPPLY DIFFUSER	AHU	AIR HANDLING UNIT
	RETURN GRILLE	HP	HEAT PUMP UNIT
	CEILING EXHAUST FAN/GRILLE	AC	AIR CONDITIONING UNIT
	THERMOSTAT AT 48° AFF	S.A.	SUPPLY AIR
	SPACE SENSOR AT 48° AFF	R.A.	RETURN AIR
	SMOKE DETECTOR	O.A.	OUTSIDE AIR
	REMOTE PULL STATION	E.A.	EXHAUST AIR
	SQUARE DUCT	M.P.	MEDIUM PRESSURE
	ROUND METAL DUCT	L.P.	LOW PRESSURE
	ROUND FLEX DUCT	SP	STATIC PRESSURE
	DUCT ELBOW W/TURNING VANES	REL.	RELOCATE
	FIRE DAMPER	V.D.	VOLUME DAMPER
	CEILING RADIATION DAMPER	CFM	CUBIC FEET PER MINUTE
	PIPE UP	BDD	BACK DRAFT DAMPER
	PIPE DOWN	AFF	ABOVE FINISHED FLOOR
	TURNING VANES	±	DOOR UNDER CUT 1-1/2"
	TURNING VANES	±	DOOR LOUVER AT 12" AFF

MECHANICAL DRAWING INDEX	
M1	MECHANICAL SCHEDULES, NOTES AND LEGEND
M2	MECHANICAL FLOOR PLAN
M3	MECHANICAL DETAILS
M4	KITCHEN HOOD DETAILS
M5	KITCHEN HOOD DETAILS
M6	KITCHEN SUPPLY FAN DETAILS
M7	KITCHEN EXHAUST FAN DETAILS



VP ENGINEERING
 VRETTOS PAPPAS CONSULTING ENGINEERS, P.A.
 193 Line 31547, Charlotte, NC 28223
 2815 Colonnade Circle, Suite 100, Charlotte, NC 28227
 704.372.7765 vpc@vpce.com

COOK OUT
 975 W. Poplar Ave.
 Collierville, TN

Mk Date Description
 Revisions

MECHANICAL SCHEDULES,
 NOTES AND LEGEND

Date 07-11-17
 Drawn By MM
 Check By SP
 Job No. 17-019-000
 Sheet

M1