


Issued:	Date:
A Client Review Set	04/07/17
B Permit Set	04/07/17
C Bid Set	09/05/17
D	
Revisions:	Date:
1	
2	
3	
4	
5	
6	
7	
8	
9	


**DO NOT SCALE PLANS**  
 Copying, Printing, Software and other processes required to produce these prints can stretch or shrink the actual paper or layout. Therefore, scaling of this drawing may be inaccurate. Contact us consultants with any need for additional dimensions or clarifications.



**ms consultants, inc.**  
 engineers, architects, planners  
 2221 Schrock Road  
 Columbus, Ohio 43229-1547  
 phone 614.898.7100  
 fax 614.898.7570

DRAWN BY: CJH  
 REVIEWED BY: CEM

Seal  
 PROFESSIONAL OF RECORD:  
 CRAIG E. METZGER No. 0402057475  
 EXP. DATE: 03/31/2019



**ALDI Inc.** Store #: 161  
 VA Beach Blvd & Thalia  
 4220 Virginia Beach Blvd  
 Virginia Beach, VA 23452  
 Willis Wayside  
 Project Name & Location:

<b>Slab Plan</b>	
Drawing Name:	Prototype Rls. 02/08/17
Type: RHSD-V7	Project No. 40320-40
Scale: As Noted	Drawing No. S-102

- ELEVATIONS ARE REFERENCED FROM FINISHED FLOOR DATUM ELEVATION. SEE GSN.
- ALL SUB-BASE MATERIAL THICKNESS AND PREPARATION SHALL BE IN ACCORDANCE WITH THE GEOTECHNICAL REPORT. SUB-BASE BENEATH TRUCK DOCK SLAB SHALL BE PER GEOTECHNICAL RECOMMENDATIONS FOR "HEAVY DUTY" PAVEMENT. SOIL BENEATH FOOTINGS SHALL BE INSPECTED AND APPROVED BY THE GEOTECHNICAL CONSULTANT PRIOR TO PLACING THE CONCRETE.
- SIDEWALK SLABS SHALL BE 4" SLAB-ON-GRADE WITH 6x6 - W2.1xW2.1 WELDED WIRE FABRIC.
- [Pattern] = FREEZER SLAB LOCATION.
- SEE ARCHITECTURAL DRAWINGS FOR FLOOR FINISH REQUIREMENTS.
- PLACE A VAPOR BARRIER BETWEEN THE SOIL SUB-GRADE AND THE GRAVEL SUB-BASE.
- DO NOT SCALE DRAWINGS. SEE ARCHITECTURAL FLOOR PLANS FOR DIMENSIONS NOT INDICATED ON STRUCTURAL DRAWINGS.
- SECTIONS INDICATED ON PLAN ARE TYPICAL FOR SIMILAR CONDITIONS.
- "CJ" = SUGGESTED SLAB CONTROL JOINT LOCATIONS. SEE SPEC.
- FLATNESS AND LEVELNESS REQUIREMENTS FOR INTERIOR SLABS PER ASTM E1155; OVERALL FLATNESS, F(1) 20 AND LEVELNESS, F(1) 20. TESTS MUST BE PERFORMED PER ASTM E1155 AND FINDINGS COMMUNICATED TO THE ALDI CONSTRUCTION REPRESENTATIVE UPON COMPLETION OF THE TESTING. THE OFFICIAL REPORT MUST BE PROVIDED WITHIN 5 WORKING DAYS OF CONCRETE PLACEMENT.

Order Plans @ WWW.DLINE.COM