BREAKER SIZE	MINIMUM CONDUCTOR SIZE (CMIL)	MINIMUM CONDUIT SIZE	MAX. CONDUCTOR LENGTH (IN FEET) TO INSURE VOLTAGE DROP DOES NOT EXCEED (3) 1.5 % (E.G. REQUIREMENTS CLOSELY ASSUMED - 80% BREAKER RATING) VOLTAGE/PHASE		
			120/1Φ	208/3Φ	208/3Φ*
15	#12	1/2"	78	135	
20	#12	1/2"	59	98	
30	#10	3/4"	63	108	
40	#8	1"	72	125	
50	#6	1"	82	142	
60	#6	1"	77	133	
70	#6	1 1/4"		150	138
80	#4	1 1/4"		157	121
90	#3	1 1/4"		173	133
100	#3	1 1/4"		156	120
110	#1	1 1/2"		222	171
125	#1	1 1/2"		195	150
150	1/0	1 1/2"			167
175	2/0	2"			172
200	3/0	2"			180
225	4/0	2 1/2"			212
250	250 MCM	2 1/2"			222
275	300 MCM	2 1/2"			243
300	350 MCM	3"			257
350	2/0	EA. OF (2) 2"			172
400	3/0	EA. OF (2) 2"			190
500	250 MCM	EA. OF (2) 2½"			222
600	350 MCM	EA. OF (2) 3"			257
700	500 MCM	EA. OF (3) 3½"			315
800	300 MCM	EA. OF (3) 3½"			250
1000	400 MCM	EA. OF (3) 3"			273
1200	350 MCM	EA. OF (4) 3"			263
3000	500 MCM	EA. OF (6) 3½"			297
4000	600 MCM	EA. OF (8) 4"			328

NOTE:
IS A GFPDS IS REQUIRED BY EQUIPMENT MANUFACTURER

CONTRACTOR TO VERIFY VOLTAGE DROP IF CONDUCTOR/BREAKER COMBINATION INSTALLED IS NOT AS LISTED ABOVE

CONTRACTOR TO UP-SIZE CONDUIT & CONDUCTORS TO ALLOW MAX. VOLTAGE DROP OF 3% FOR FEEDER CIRCUITS AND MAX. OF 3% FOR BRANCH CIRCUITS IF INSTALLED LENGTHS EXCEED THE LISTED ABOVE.

* DISTANCES INDICATED ALLOW FOR A MAX. OF 3% VOLTAGE DROP FOR BRANCH CIRCUITS IF INSTALLED LENGTHS DO NOT EXCEED THE LISTED ABOVE.

** DISTANCES INDICATED ALLOW FOR A MAX. OF 3% VOLTAGE DROP FOR FEEDER CIRCUITS IN COMPLIANCE WITH 0L13 OF F.B.C.

SHORT CIRCUIT OUTPUT DATA

LABEL	VOLTS	PH	MOTOR CONN STATUS	CALC TYPE	PER UNIT REACTN.	PER UNIT RESISTN.	X/R RATIO	SYMMT. CURRENT
XFMR	208	3	NEITHER	P.U	0.76508	0.05101	15.000	36,220 A
MDP	208	3	NEITHER	P.U	0.80319	0.07535	10.659	34,408 A
SFL	208	3	NEITHER	P.U	0.98718	0.36797	2.683	26,347 A
A	208	3	NEITHER	P.U	2.82686	7.17594	0.394	3,599 A
B	208	3	NEITHER	P.U	2.82686	7.17594	0.394	3,599 A
C	208	3	NEITHER	P.U	2.82686	7.17594	0.394	3,599 A
D	208	3	NEITHER	P.U	0.98718	0.36797	2.683	26,347 A
ATS-E	208	3	NEITHER	P.U	0.97715	0.54503	1.794	26,787 A
E	208	3	NEITHER	P.U	1.02767	0.56337	1.549	22,593 A
EA	208	3	NEITHER	P.U	3.80587	0.98196	0.749	4,372 A
EB	208	3	NEITHER	P.U	3.85853	1.22989	0.736	4,271 A
ATS-EM	208	3	NEITHER	P.U	0.97183	0.56707	1.457	22,548 A
EM	208	3	NEITHER	P.U	0.99818	0.74103	1.347	22,328 A
F	208	3	NEITHER	P.U	1.35515	0.93322	1.452	16,733 A
H	208	3	NEITHER	P.U	1.43359	2.29429	0.626	10,256 A
J	208	3	NEITHER	P.U	1.43359	2.29429	0.626	10,256 A
K	208	3	NEITHER	P.U	2.33174	6.16064	0.422	4,179 A
L	208	3	NEITHER	P.U	0.45842	0.36019	2.603	17,767 A
M	208	3	NEITHER	P.U	1.52074	1.22658	1.250	14,253 A
N	208	3	NEITHER	P.U	2.33928	2.50611	0.931	8,115 A
P	208	3	NEITHER	P.U	2.27623	2.56329	0.927	7,941 A
Q	208	3	NEITHER	P.U	3.56299	4.46468	0.798	4,859 A
R	208	3	NEITHER	P.U	2.82686	7.17594	0.394	3,599 A
S	208	3	NEITHER	P.U	3.38597	4.49427	0.798	4,828 A
MC1	208	3	NEITHER	P.U	1.20986	0.30108	4.018	22,264 A
MC2	208	3	NEITHER	P.U	1.20272	0.29712	4.048	22,405 A

VOLTAGE DROP

FED BY	PANEL NAME	LENGTH	WIRE SIZE	CONNECTED LOAD (Amps)	% DROP
MDP	SFL	25	4/0	113	0.15%
MDP	A	192	1	62 **	1.48%
MDP	B	192	1	47 **	1.13%
MDP	C	192	1	55	1.32%
MDP	D	25	4/0	152	0.20%
MDP	F	70	4/0	84	0.30%
MDP	H	68	1	52	0.43%
MDP	R	192	1	26	0.62%
MDP	J	62	1	21	0.16%
MDP	K	174	1	48	1.05%
MDP	L	76	500	372	0.06%
MDP	M	78	4/0	102	0.41%
MDP	N	175	4/0	134 **	1.21%
MDP	Q	303	4/0	104 **	1.63%
MDP	MC1	116	600 ***	869	0.78%
MDP	MC2	111	600 ***	822	0.48%
MDP	EM	25	1	39	0.12%
MDP	E	31	1/0	108	0.34%
N	* P	2	4/0	82	1.22%
Q	* S	2	4/0	44	1.64%
E	* EA	290	2/0	69	1.98%
EA	* EB	2	4	45	2.00%
MC2	* AC-1	167	400	302	1.96%
MC2	* AC-2	244	1	70	2.76%
MC2	* AC-3	194	2	73	2.88%
MC2	* AC-4	31	2	70	0.84%
MC2	* AC-5	249	1	70	2.81%
MC2	* AC-6	205	4	37	2.47%

* INDICATES BRANCH BREAKER OR SUB-FED PANEL WITH TOTAL VOLTAGE DROP BACK TO THE MDP.

** INDICATED IS TOTAL LOAD AT FEED THRU LUGS.

*** INDICATED PARALLEL FEEDERS

SUMMARY OF LOADS

Description	Connected (kVA)	Demand Factor	Demand (kVA)
1 Lighting	58.4	1.25	73.0
2 Air Conditioning	216.2	1.00	216.2
Total Strip Heat	56.9		
3 Refrigeration (units)	336.0	1.00	336.0
(non-concedental)	101.4		
4 Kitchen Equipment	278.9	0.65	181.3
5 Misc. Equipment	146.6	1.00	146.6
6 Receptacles (1st 10.0 kW)	10.0	1.00	10.0
(Remaining)	47.8	0.50	23.9
(Total)	57.8		33.9
Total kVA	1195.4	0.83	987.0
Total Amps	3320		2742

ELECTRICAL CHARACTERISTICS

VOLTAGE = 120/208Y VOLTS 3PH, 4 WIRE LOADS
MAIN SWITCHGEAR RATING: 1600A B.I.C.
MAIN FEEDER BREAKER RATING TO BE 1600A B.I.C.

MAXIMUM AVAILABLE FAULT CURRENT VALUE PROVIDED BY LOCAL UTILITY IS 36,200A AMPS SYMM.
THE CURRENT SYSTEM IS DESIGNED AND BRACED FOR A FAULT CURRENT OF 100,000 AMPS SYMM.

MAIN SWITCHBOARD SCHEDULE

SQUARE 'D' 3000 AMP FRAME SWITCHBOARD RATED 100,000 AIC SYM

CKT. NO.	OVERCURRENT DEVICE FRAME	TRIP	POLES	DEVICE SERVED	CONNECTED VA PHASE A	PHASE B	PHASE C	TOTAL CONNECTED	PANEL DEMAND
	3000	3000	3	MAIN BREAKER	438649	369510	388295	1196578	
1	100	100	3	PANEL N	19182	15819	14767	44268	27320
2	100	100	3	PANEL P	15781	20411	20552	60744	11736
3	100	100	3	PANEL 'C'	17720	21170	18033	56923	22281
4	225	225	3	PANEL 'J'	19944	19304	19337	58585	46801
5	1200	1200	3	PANEL MC-1*	99122	99120	99122	297365	291350
6	1200	1200	3	PANEL MC-2	87886	87888	87888	263708	263708
7	225	150	3	PANELS 'K', 'M' & 'EB'	17327	15417	19003	49747	49747
8	225	125	3	PANEL 'EM'	5182	21941	2393	8851	12885
9	225		3	SPACE ONLY				0	
10	225	225	3	PANEL 'F'	13151	8227	12859	35290	29307
11	225	225	3	SPARE				0	
12	100	100	3	PANEL 'H'	7992	5327	5332	17388	18535
13	100	100	3	PANEL J	3021	2955	2955	10731	10731
14				BUSSED SPACE(UNUSABLE)				0	
15	100	100	3	PANEL 'K'	6772	7345	4123	18240	18132
16	400	400	3	PANEL 'L'	67322	59428	53431	180176	139877
17	100	100	3	SPARE				0	
18	100		3	SPACE ONLY				0	
19	225	225	3	PANEL 'M'	17452	15812	16988	50248	37446
20	225	225	3	PANEL 'M & P'	21361	25136	18227	65723	44127
21	225	225	3	PANELS 'Q' & 'S'	12703	8526	13122	34351	3670
22	100	100	3	PANEL 'E'	3883	2190	3240	9223	9523
23	225		3	SPACE ONLY				0	
24	100		3	SPACE ONLY				0	
25				BUSSED SPACE(UNUSABLE)				0	
26	100		3	SPACE ONLY				0	
27	225		3	SPACE ONLY				0	
28	225	225	3	PANEL 'EFL'	12660	5282	8826	26768	26125
29	225		3	SPACE ONLY				0	
30	225		3	SPACE ONLY				0	
31	225		3	SPACE ONLY				0	
32								0	

NOTES:

1. ALL CONDUCTORS SHALL BE COPPER UNLESS NOTED OTHERWISE.
   - ALL CONDUCTORS IN DRY/DAMP LOCATIONS SHALL BE THHN OR EQUAL.
   - ALL CONDUCTORS UNDERGROUND OR IN WET LOCATIONS SHALL BE THWN-2 OR EQUAL.
2. CONTRACTOR TO VERIFY MAXIMUM BREAKER SIZES WITH ACTUAL EQUIPMENT NAME PLATES, PRIOR TO ORDERING BREAKERS.
3. CONTRACTOR TO PROVIDE PLAQUES AT ALL LOCATIONS TO IDENTIFY POINTS OF SERVICE IN ACCORDANCE WITH NEC 230-2.
4. ***AUTOMATIC TRANSFER SWITCHES (ATS) ARE GNAH GTPC. MDP CIRCUIT BREAKER FEEDING EMERGENCY ATS TO BE SELECTED TO PROVIDE ATS 100KAIC RATING (MIN.) ACCEPTABLE BREAKER TYPES BY MANUFACTURER:***

   FOR 'EFR' (SR-4 RATED) AC-225, AMPS:
   SQ'D': HD, HG, HJ, HL, HJ, JG, JJ, & JL
   SIEMENS: CD6A, CF6A, CJ6A, & SCJ6A
   GE: SEL, SFL, TEC, TEC4, TEL, TEL, & TFL

   FOR 'EFR' (SR-4 RATED) 400-960, AMPS:
   SQ'D': HD, HG, HJ, HL, JG, JJ, & JL
   SIEMENS: CD6A, CF6A, CJ6A, CG6A, SCJ6A, & SCJ6
   GE: SEL, SFL, SSL, TEC, TEC4, TEL, TEL, & TFL

5. SEE PANELBOARD SCHEDULE SHEET E-16 & E-17 FOR PANELBOARD AIC MINIMUM RATING
6. NO INTEGRAL CONTACTORS PERMITTED
7. UTILITY TRANSFORMER SHOWN HERE IS FOR PROTOTYPE DESIGN. ELECTRICAL CONTRACTOR TO SEE CIVIL UTILITY PLANS FOR EXACT LOCATION FOR BIDDING AND INSTALLATION. ELECTRICAL CONTRACTOR TO COORDINATE ALL UTILITY REQUIREMENTS.
8. EDCO SURGE SUPPRESSION UNIT BY ELECTRICAL CONTRACTOR, MODEL HVP120Y-RM1050, CONTACT KENNICK, INC. 1-800-362-9997 REFERENCE: PUBLIX STORE NUMBER WITH ORDER.
9. ELECTRICAL CONTRACTOR FIELD MARK ALL SWITCHGEAR AND PANELBOARDS WITH A WARNING CONCERNING THE POTENTIAL ARC FLASH HAZARD, PER NFPA 70 SECTION 110-16. COORDINATE REQUIREMENTS WITH THE AHJ.
10. ELECTRICAL CONTRACTOR TO COORDINATE WITH GENERATOR FIELD REP THAT THE GENERATOR PHASE ROTATION MATCHES THE UTILITY SERVICE.
11. GENERATOR OUTPUT BREAKERS ARE SQ 'D' TYPE NGL. CONTRACTOR TO SELECT PANEL EM BREAKERS TO PROVIDE SELECTIVE COORDINATION PER NFPA 70 700.27.
12. ALL CIRCUIT BREAKERS TO BE ARRANGED AS INDICATED ON PANEL SCHEDULE. ANY DEVIATION MUST BE APPROVED BY THE ENGINEER.
13. ***WHERE SERIES RATING IS APPLIED, THE SERIES RATING COMBINATION INTERRUPTING RATING SHALL BE FIELD MARKED ON THE RESPECTIVE PANELBOARD PER NFPA 70, ENGLISH AND 70.22. SUBMITTALS SHALL INCLUDE MANUFACTURERS' SERIES RATING CHART. CHARTS SHALL INCLUDE VOLTAGE RATING FOR EACH TYPE OF BREAKER INVOLVED (i.e. 120/208 OR SIMILAR FOR 1 PH.)***
14. ALL PANELBOARD BUSSING, NEUTRAL/GROUND BUSSES TO BE COPPER. USE OF BRANCH MOUNTED MAIN CIRCUIT BREAKER IS NOT ALLOWED.
15. ***ALL BREAKERS IN AN 800 AMP FRAME OR LARGER SHALL BE ELECTRONIC TRIP. SHALL PROVIDE LSI, LSIG, ZSI & STPU, AND INST. ADJUSTMENTS. SUBMITTALS SHALL INCLUDE TIME/CURRENT CURVES (TCC) AND TCC No. FOR ALL ADJUSTABLE BREAKERS.***
16. SELECTIVE COORDINATION IS A REQUIREMENT FOR ALL ELECTRONIC/ADJUSTABLE CIRCUIT BREAKERS AS WELL AS ANY FEEDER AND BRANCH BREAKERS ASSOCIATED WITH THE ELECTRONIC/ADJUSTABLE CIRCUIT BREAKERS. ADDITIONALLY THE EMERGENCY SYSTEM SHALL BE SELECTIVELY COORDINATED PER NFPA 70 700.27 AND NFPA 70 701.27. THE ELECTRICAL CONTRACTOR SHALL CONTACT PUBLIX REP AND PROVIDE TO PUBLIX ENGINEER OF RECORD THE INSTALLED UTILITY TRANSFORMER SIZE AND SERVICE LATERAL CONDUCTOR TYPE AND QTY. AT WHICH TIME A SELECTIVE COORDINATION STUDY WILL BE PERFORMED BY PUBLIX. THE BREAKER SETTINGS WILL BE PROVIDED TO THE ELECTRICAL CONTRACTOR FOR FINAL ADJUSTMENT WITHIN TWO WEEKS AFTER RECEIPT OF THE FIELD INFORMATION. THE REQUEST FOR THE CIRCUIT BREAKER SETTINGS SHALL BE AT WHEN PERMANENT POWER AND INSTALLATION OF THE REFRIGERATION MACHINE ROOM. UPON COMPLETION OF THE COORDINATION STUDY ANY CIRCUIT BREAKERS PROVIDED BY THE ELECTRICIAN THAT DO NOT COORDINATE, SHALL BE CHANGED (AT NO COST TO PUBLIX) TO BREAKERS THAT PROVIDE PROPER SELECTIVE COORDINATION. THE MECHANICAL CONTRACTOR SHALL MARK ALL CIRCUIT BREAKER SETTINGS AND HAVE THE PUBLIX ELECTRICAL REPRESENTATIVE WITNESS COMPLETION PROPER ADJUSTMENT PRIOR TO ATC/CO.
17. ELECTRICAL CONTRACTOR TO PROVIDE INDEPENDENT 3RD PARTY INSULATION RESISTANCE TESTING OF SERVICE LATERAL AND GENERATOR FEEDERS. TEST SHALL BE PERFORMED AFTER THE CONDUCTORS ARE INSTALLED IN CONDUIT AND BEFORE ANY CONDUCTOR TERMINATION OR CONNECTION IS MADE. TEST SHALL BE IN ACCORDANCE TO MANUFACTURER'S RECOMMENDATIONS. MEGGER INSULATION RESISTANCE TESTER SHALL BE A SPRADSHEET FORMAT WITH RECORDED AMBIENT TEMPERATURE, AND HUMIDITY AT THE TIME OF TEST. THE SPREADSHEET SHALL BE SENT TO THE PUBLIX REP AT THE SAME TIME THE FIELD INFORMATION IS SUPPLIED TO ENGINEER OF RECORD FOR COORDINATION. ANY RESISTANCE VALUES OF TEST CABLES FALLING OUTSIDE ACCEPTABLE MANUFACTURER/ANSI/NETA STANDARDS SHALL BE REPLACED AND COST TO THE OWNER. IF ANY CABLES ARE REPLACED, ALL CABLES IN THE RESPECTIVE SERVICE LATERAL AND/OR GENERATOR FEEDER SHALL BE TESTED. ADDITIONAL REQUIREMENTS IN ELECTRICAL SPECIFICATION, DIVISION 26 00 00, SECTION 1.4.5 AND 2.2.1.

ELECTRICAL CONTRACTOR TO PROVIDE AND INSTALL THE FOLLOWING HARDWARE FOR PROPER INSTALLATION OF CONDUCTORS FOR THE 1600KW GENERATOR, WHEN 1600KW GENERATOR IS USED:

BURNDY YA26K3 COMPRESSION CONNECTORS FOR 600 MCM CONDUCTORS

BURNDY YA32K3 COMPRESSION CONNECTORS FOR 400 MCM CONDUCTORS

½"x2" STAINLESS STEEL BOLTS

½" STAINLESS STEEL NUTS, WASHERS, AND LOCK WASHERS


AC-1
AC-2
AC-3
AC-4
AC-5
AC-6
PANELS 'MCP' AND 'MCS' ARE LOCATED IN MOTOR CENTER, SUPPLIED, INSTALLED & WIRED BY MOTOR CENTER MANUFACTURER.
PANEL MCP
PANEL MCS
ROOF
3-600 MCM & 1-3/0GRD IN EACH OF (3) - 4"C
3-600 MCM & 1-3/0GRD IN EACH OF (3) - 4"C
3#12 ½"C
3#12 ½"C
GENERATOR ANNUNCIATOR (POWER COMMAND T1-100) AT EXIT VESTIBULE, SEE DWG. E-3 FOR EXACT LOCATION
SEE GENERAL NOTE B
PANEL 'LA'
PANEL 'LEB'
PANEL 'G'
PANEL 'S'
PANEL 'A'
PANEL 'B'
PANEL 'C'
PANEL 'R'
PANEL 'H'
PANEL 'J'
PANEL 'F'
PANEL 'K'
PANEL 'N'
PANEL 'P'
PANEL 'L'
PANEL 'M'
PANEL 'D'
PANEL 'EFL'
PANEL 'EM'
4-#1 & 1-#6GRD Cu-1½"C
ATS-E 3-POLE 1600A, 3 POLE) (SOURCE 'G' & NORM. END BUS
ATS-EM (1600A, 3 POLE)
BOND TO C.W.P. WITHIN 5'-0" OF ENTRANCE TO BUILDING AS REQ'D. BY N.E.C. 250-50(A)(3)
BOND TO STRUCTURAL STEEL AS REQ'D. BY N.E.C. 250-50(A)(3)
4-1/0, 1-6GRD & 1-#6GRD Cu-2"C
MOBILE NEC 702 GENERATOR QUICK CONNECT SECTION
3000 A MAIN BREAKER SECTION
2000A VERTICAL BUS MIN.
M.D.P. TO BE DEAD FRONT & SIDE ACCESS ONLY WITH 3000A RATED HORIZONTAL BUS. ALL VERTICAL BUSBARS TO BE FULL HEIGHT.
3000A VERTICAL BUS MIN.
ALL SECTIONS TO BE 48" DEEP
3#12 ½"C
3#12 ½"C
EMERGENCY GEN. LOCK-OUT SWITCH (BREAK GLASS TYPE)
UTILITY METER (PUBLIX REQUESTS A TIME OF USE METER INSTALLED)
"MDP" SHUNT TRIP P.B. (BREAK GLASS TYPE)
UTILITY TRANSFORMER (WITH CTs)
FINISHED GRADE
4-#1 & 1-#6GRD Cu-1½"C
4-#1/0, 1-#6GRD Cu-2"C
4-#1/0, 1-#6GRD-2½"C
4-#1/0, 1-#6GRD-2½"C
4-#1/0, 1-#6GRD-2½