RESPONSIBILITY SCHEDULE

ITEM	FURNISHED: LANDLORD	FURNISHED: TENANT	FURNISHED: G.C.	INSTALLED: LANDLORD	INSTALLED: TENANT	INSTALLED: G.C.	REMARKS
STOREFRONT							
NEUTRAL PIERS							VERIFY WITH MALL MANAGER
3/4" BLACK REVEALS			●			●	
STOREFRONT GLAZING			●			●	
ROLLING GRILLE							DESIGNED, BUILT AND INSTALLED BY GRILLE SUPPLIER - COORDINATED WITH GRILLE SUPPLIER
STOREFRONT TILE		●				●	
ADDRESS (SPACE) NUMBER			●			●	COORDINATE WITH MALL MANAGER
WIRE GRID PANEL		●				●	PROVIDED BY FIXTURE CONTRACTOR
ALUMINUM ANGLE TRIM		●				●	1" x 1" x 1/16"
'MOZ' METAL PANELS ON 1/2" (FRT) PARTICLE BOARD		●				●	
WALLS							
DEMISING PARTITION STUDS	●			●			
DEMISING PARTITION DRYWALL			●			●	
NEW WALLS FRAMING/ BLOCKING/ GYP. BD.			●			●	
TOILET ROOM FRAMING/ BLOCKING/ GYP. BD.			●			●	
INTERIOR COLUMN FURRING			●			●	
WALL PREPARATION AND PAINT			●			●	
1/2" PRE-FINISHED OSB		●				●	
ALUMINUM ANGLE TRIM		●				●	1 1/2" x 1 1/2" x 1/16"
DOORS							
TOILET ROOM DOOR/ FRAME/HARDWARE			●			●	
REAR DOOR AND FRAME/HARDWARE			●			●	KEY ALL DOOR(S) ALIKE
ACCESS PANELS AS REQUIRED FOR MOTORS/VAV/ETC.			●			●	N/A
CEILING							
GYP. BD. CEILINGS AND SOFFITS			●			●	
SUSPENDED ACOUST. CEILING		●				●	
FLOORING / BASE							
FLOOR CORING/CONCRETE INFILL/PATCH EXISTING			●			●	PREPARE EXISTING FLOOR FOR NEW FINISHES
TILE FLOORING		●				●	
PAINTED CONCRETE			●			●	STOCKROOM ONLY
TOILET ROOM		●				●	
FLOOR TRANSITIONS			●			●	
WOOD BASE		●				●	
PATCH/INFILL MALL FLOORING			●			●	COORDINATE WITH MALL MANAGER
VINYL BASE			●			●	
SALES AREA FIXTURES							
FREE STANDING FLOOR FIXTURES		●				●	G.C. TO ASSEMBLE
CASHWRAP/COUNTERS		●				●	G.C. TO ASSEMBLE
WALL AND DISPLAY FIXTURES		●				●	G.C. TO ASSEMBLE
HARDWARE & SHELVING		●				●	
UNPACK/DISPOSE OF FIXTURE WRAPPING			●			●	OFFLOAD FROM TRUCK
WIRE GRID, PANELS AND CLIPS		●				●	
STOCKROOM							
STRUCTURAL SUPPORT FOR TRANSFORMER IF REQUIRED			●			●	
SHELVING		●				●	INCLUDE SHELVES, UPRIGHTS AND BRACKETS
SHELF BACKING			●			●	
WIRE GRID		●				●	
SIGNAGE							
STOREFRONT SIGNAGE		●			●		INSTALLED BY TENANT'S SIGN CONTRACTOR
BLADE SIGN BRACKET		●			●		INSTALLED BY TENANT'S SIGN CONTRACTOR
BLADE SIGN		●			●		INSTALLED BY TENANT'S SIGN CONTRACTOR
REAR DOOR SIGNAGE			●			●	
BARRICADE GRAPHICS							COORDINATE WITH MALL MANAGER
EXIT SIGN(S)		●				●	
SIGN PERMIT AND APPLICATION							BY TENANT'S SIGN CONTRACTOR

NOTE:

THE RESPONSIBILITY SCHEDULE IS PROVIDED TO ASSIST THE GENERAL CONTRACTOR IN CONSTRUCTION PROCESS. THE CONSTRUCTION DOCUMENTS WILL SUPERSEDE THE RESPONSIBILITY SCHEDULE AND IF A CONFLICT EXISTS BETWEEN THIS SCHEDULE AND CONSTRUCTION DOCUMENTS, THE GENERAL CONTRACTOR SHALL CONTACT THE ARCHITECT IMMEDIATELY FOR CLARIFICATION. REFER TO PLANS FOR ITEMS 'EXISTING TO REMAIN'. REFER TO SCHEDULE FOR ANY EXISTING ITEMS THAT MUST BE REPLACED.

RESPONSIBILITY SCHEDULE - CONTINUED

ITEM	FURNISHED: LANDLORD	FURNISHED: TENANT	FURNISHED: G.C.	INSTALLED: LANDLORD	INSTALLED: TENANT	INSTALLED: G.C.	REMARKS
MECHANICAL							
HVAC UNIT		●			●		REFER TO SHEET M1.1
ROOF CURB WORK		●			●		COORDINATE WITH MALL MANAGER
SUPPLY AND RETURN AIR DUCTWORK		●			●		
DEMOLISH AND/OR MODIFY EXIST. SUPPLY AND RETURN AIR DUCTWORK/DEVICES		●			●		
ALL DIFFUSERS/GRILLES		●			●		
THERMOSTATS		●			●		
FIRE DAMPERS		●			●		
TOILET ROOM EXHAUST FAN		●				●	
AIR BALANCE REPORT BY INDEPENDENT CONTRACTOR			●				REQUIRED FOR FINAL RETENTION
PLUMBING/TOILETS							
MODIFY WASTE/VENT LINES WITHIN SPACE			●			●	
MODIFY WATER LINES WITHIN SPACE			●			●	
WASTE STUB-UP	●						G.C. TO VERIFY LOCATION
WATER CLOSET AND LAVATORY			●			●	
MOP SINK			●			●	
DRINKING FOUNTAIN(S)			●			●	
FLOOR DRAIN/TRAP PRIMER			●			●	
WATER HEATERS			●			●	
TOILET PAPER / TOWEL DISPENSER			●			●	
GRAB BARS			●			●	
MIRRORS			●			●	
F.R.P. PANELS AND TRIM			●			●	
BLOCKING FOR ALL ITEMS LISTED ABOVE			●			●	
ELECTRICAL							
LANDLORD DISTRIBUTION PANEL							VERIFY AVAILABILITY FOR LOAD DEMAND & LOCATION
METER							VERIFY IN FIELD
MAIN DISCONNECT AND FUSES			●			●	
CONDUIT TO SPACE	●			●			G.C. TO UPSIZE IF REQUIRED - VERIFY AT BID
CONDUIT WITHIN SPACE			●			●	
WIRE TO SPACE			●			●	
MAIN CIRCUIT BREAKER			●			●	
PANEL HIGH VOLTAGE			●			●	
TRANSFORMER			●			●	
PANEL LOW VOLTAGE			●			●	
TIME CLOCKS AND WIRING			●			●	
HOMERUNS/CONDUITS/WIRES			●			●	
LIGHTING CONTROLS: SWITCHES/CONTACTORS			●			●	
TELEPHONE CONDUIT TO SPACE			●			●	G.C. TO EXTEND AS REQUIRED - VERIFY
TELEPHONE TERMINAL BOARD/ PLYWOOD/OUTLET			●			●	
PHONE AND DATA CABLE		●			●		SEE SCHEMATIC 'US EDGE' TO INSTALL
PHONE TERMINATIONS (ALL WIRING TO MARK)		●			●		BY TENANT'S VENDOR
CONDUITS AND POWER FOR P.O.S./PHONE SYSTEM			●			●	
HVAC SYSTEM WIRING (LINE AND LOW VOLTAGE)			●			●	
BUZZER SYSTEM			●			●	
LIGHT FIXTURES		●				●	PROVIDED BY TENANT'S LIGHTING CONTRACTOR
LIGHT FIXTURE SUPPORTS (UNISTRUT/THREAD)			●			●	
TEMPORARY LIGHTING/POWER			●			●	
PROVIDE EQUIPMENT CUTSHEETS TO ARCHITECT			●				
FINAL CONNECTION OF POWER TO SIGNS			●			●	
T-1 LINE TO SPACE		●			●		
MISCELLANEOUS							
PICK UP PERMIT/PAY PERMIT FEES			●			●	
OBTAIN C/O APPROVALS			●				
SPRINKLER SYSTEM PLANS/ PLANS/ PERMIT/FEES			●			●	CHANGE ORDER'S NOT PROCESSED WITHOUT AWA. #'S
MODIFY SPRINKLER SYSTEM			●			●	COORDINATE WITH MALL MANAGER
MALL DEPOSIT/INSURANCE WAIVERS			●				
JANITORIAL SERVICE/FINAL CLEANING			●				TWO CLEANINGS-FIRST AT PUNCHLIST SECOND CLEANING DAY PRIOR TO OPENING
TRASH REMOVAL/DUMPSTER RENTAL			●				
ROOF PENETRATIONS			●			●	COORDINATE WITH MALL MANAGER
DEMOLITION/PERMIT AND FEE'S AS REQUIRED			●				
OBTAIN INSPECTIONS/ PROVIDE STATUS REPORT			●				
PROVIDE AS-BUILT COPY OF JOB SITE PLANS			●				
RECEIVE/UNLOAD ALL TENANT SUPPLIED ITEMS			●				
SUB-CONTRACTOR LIST & WARRANTIES			●				PROVIDE TO TENANT AT TURNOVER
TEMPORARY BARRICADE			●			●	COORDINATE MALL MANAGER
G.C. PROJECT MANAGER SITE VISITS DURING CONSTRUCTION			●				
COMPLIANCE TO TENANT TURNOVER REQUIREMENTS			●				AS REQUIRED: MINIMUM (1) AT FIELD REPORT
AUDIO SYSTEM		●				●	COORDINATE WITH TENANT'S VENDOR FOR INSTALLATION SCOPE
CONDUITS AND PULL STRING POWER FOR AUDIO SYSTEM			●			●	
P.O.S. SYSTEM (DATA AND TELEPHONE EQUIPMENT)		●			●		

ABBREVIATIONS

AB. ANCHOR BOLT
A/C AIR CONDITIONING
ACOUST. ACOUSTIC
ADJ. ADJUSTABLE
A.F.F. ABOVE FINISH FLOOR
A.F.G. ABOVE FINISH GRADE
AHU AIR HANDLING UNIT
ALT. ALTERNATE
ARCH. ARCHITECTURAL
ALUM. ALUMINUM
ANOD. ANODIZED
APP. APPROXIMATE
ATT. ATTENUATION
BD. BOARD
B.F.F. BELOW FINISH FLOOR
BIT. BITUMINOUS
BLDG. BUILDING
BLK. BLOCK
BLKG. BLOCKING
BM. BEAM
B.O. BOTTOM OF
BRG. BEARING
BSMT. BASEMENT
C.F. CUBIC FEET
C.J. CONTROL JOINT
C.L. CENTER LINE
CLG. CEILING
CMU CONCRETE MASONRY UNIT
CNTR. COUNTER
CONC. CONCRETE
CONTR. CONTRACTOR
COL. COLUMN
CONST. CONSTRUCTION
CONT. CONTINUOUS
CT. CERAMIC TILE
CW COLD WATER
CY CUBIC YARD
DBL. DOUBLE
DEMO. DEMOLITION
DF DRINKING FOUNTAIN
D.H. DOUBLE HUNG
DIA. DIAMETER
DIM. DIMENSION
DISP. DISPENSER
D.L. DEAD LOAD
DN. DOWN
DR. DOOR
D.S. DOWN SPOUT
DTL. DETAIL
D.W. DISHWASHER
DWGS. DRAWINGS
DRWR. DRAWER
E. EAST
EA. EACH
E.F. EXHAUST FAN
E.I.F.S. EXTERNAL INSULATION FINISH SYSTEM
E.J. EXPANSION JOINT
ELEC. ELECTRICAL
ELEV. ELEVATION
EQ. EQUAL
EQUIP. EQUIPMENT
E.T.R. EXISTING TO REMAIN
EW EACH WAY
EWC ELECTRIC WATER COOLER
EXH. EXHAUST
EXIST. EXISTING
EXP. EXPANSION
EXT. EXTERIOR
FD. FLOOR DRAIN
FE. FIRE EXTINGUISHER
FEC FIRE EXTINGUISHER CABINET
FIN. FINISH
FIXT. FIXTURE
FL. FLOOR
FLASH. FLASHING
FLR. FLOOR
FLUOR. FLUORESCENT
FRM. FRAME
F.R.P. FIBERGLASS REINFORCED PANEL
F.R.T. FIRE RETARDANT TREATED
FT. FOOT/FEET
FTG. FOOTING
FURR. FURRING
GA. GAUGE
G.B. GRAB BAR
G.C. GENERAL CONTRACTOR
GFI GROUND FAULT INTERRUPTER
GYP. GYPSUM
HGT. HEIGHT
H.C. HOLLOW CORE
HD. HEAD
HDR. HEADER
HDWR. HARDWARE
H.M. HOLLOW METAL
HORIZ. HORIZONTAL
HTG. HEATING
HVAC HEATING, VENTILATION, AND AIR CONDITIONING
HW HOT WATER
I.D. INSIDE DIAMETER
INCAN. INCANDESCENT
INCH
INC. INCORPORATED
INCL. INCLUDED
INSUL. INSULATION
JAN. JANITOR
J.B. JUNCTION BOX
J.B.E. JOIST BEARING ELEVATION
JT. JOINT
K.O. KNOCK OUT
LAM. LAMINATE
LAV. LAVATORY
LB. POUND
L.F. LINEAR FOOT
L.H. LEFT HAND
L.L. LANDLORD
LLH LONG LEG HORIZONTAL
LLV LONG LEG VERTICAL
LT. LIGHT
LTG. LIGHTING
L.V. LOW VOLTAGE
L.W. LIGHTWEIGHT
L.W.C. LIGHTWEIGHT CONCRETE
MATL. MATERIAL
MAX. MAXIMUM
MECH. MECHANICAL
MEZZ. MEZZANINE
MFGR. MANUFACTURER
M.H. MANHOLE
MIN. MINIMUM
MISC. MISCELLANEOUS
M.O. MASONRY OPENING
MTL. METAL
MULL. MULLION
N. NORTH
N.A. NOT APPLICABLE
N.I.C. NOT IN CONTRACT
NO. NUMBER
NOM. NOMINAL
N.T.S. NOT TO SCALE
O.C. ON CENTER
O.C.E.W. ON CENTER EACH WAY
O.D. OUTSIDE DIAMETER
OH OPPOSITE HAND
OPP. OPPOSITE
OSB. ORIENTED STRAND BOARD
PH. PHASE
PL. PLATE
PLYWD. PLYWOOD
PR. PAIR
P.S.F. POUNDS PER SQUARE FOOT
P.S.I. POUNDS PER SQUARE INCH
PT. POINT
PVC POLYVINYL CHLORIDE
PVMT. PAVEMENT
Q.T. QUARRY TILE
QTY. QUANTITY
R.A. RETURN AIR
RAD. RADIUS
R.A.G. RETURN AIR GRILLE
R.B. RESILIENT BASE
R.C.P. REFLECTED CEILING PLAN
R.D. ROOF DRAIN
RE. REFERENCE
RECEP. RECEPTACLE
REF. REFRIGERATOR
REINF. REINFORCE/REINFORCING
REBAR REINFORCING BAR
REV. REVISION
R.H. RIGHT HAND
RM. ROOM
R.O. ROUGH OPENING
R.O.W. RIGHT OF WAY
RPM REVOLUTIONS PER MINUTE
R & S ROD AND SHELF
RTU ROOF TOP UNIT
S. SOUTH
S.C. SOLID CORE
SCHED. SCHEDULE
S.F. SQUARE FEET
SHT. SHEET
SIM. SIMILAR
SPEC. SPECIFICATION
SPKR. SPEAKER
SQ. SQUARE
S.S. STAINLESS STEEL
ST. STREET
STD. STANDARD
STL. STEEL
STOR. STORAGE
STRUCT. STRUCTURAL
SUSP. SUSPENDED
T & B TOP AND BOTTOM
TEL. TELEPHONE
TEMP. TEMPERATURE
T & G TONGUE AND GROOVE
THK. THICK
T.O.B. TOP OF BEAM
T.O.F. TOP OF FOOTING
T.O.S. TOP OF SLAB
T.O.W. TOP OF WALL
XFMR. TRANSFORMER
TSTAT. THERMOSTAT
TYP. TYPICAL
UG UNDERGROUND
U.L. UNDERWRITER'S LABORATORY
U.N.O. UNLESS NOTED OTHERWISE
V. VOLT
V.B. VAPOR BARRIER
VERT. VERTICAL
VOL. VOLUME
V.C.T. VINYL COMPOSITION TILE
V.T.R. VENT THRU ROOF
V.W.C. VINYL WALL COVERING
W. WEST
WC WATER CLOSET
WD. WOOD
W/ WITH
W/O WITHOUT
WP WATERPROOF
WSCT. WAINSCOT
W.W.F. WELDED WIRE FABRIC

JOURNEYS

SPACE # 1540
WESTLAND MALL

HIALEAH, FLORIDA

PROJECT LOCATION



JOURNEYS SPACE #1540

MOZ METAL PANELS - INFORMATION

1. PREP EXISTING PLYWOOD/MDF PANELS TO ACCOMODATE NEW METAL PANEL OVERLAY. REMOVE ALL BOLTS AND/OR SCREWS. FILL ALL HOLES, INDENTATIONS AND FLAWS IN THE WOOD PANELS WITH WOOD PUTTY. SAND SMOOTH ALL HOLES, INDENTATIONS AND FLAWS IN THE WOOD PANELS.
2. DO NOT STACK OR ADD SIGNIFICANT WEIGHT TO THE MATERIAL. OPTIMAL STORAGE CONDITIONS ARE ROOM TEMPERATURE (70°F TO 75°F) AND 50-60% RELATIVE HUMIDITY.
3. CARE SHOULD BE TAKEN WHILE HANDLING THE PRODUCT, EVEN WITH PROTECTIVE MASKING. DO NOT USE MARKERS ON PROTECTIVE MASKING, SOME TYPES OF INKS WILL PERMEATE THE FILM AND MARK THE MATERIAL SURFACE. IT IS RECOMMENDED TO LEAVE THE PROTECTIVE MASK ON THE PRODUCT DURING MACHINING/INSTALLATION.
4. FOR GENERAL CLEANING, USE A DAMP, SOFT CLOTH WITH MILD, NON-ABRASIVE SOAP AND WATER. FOR HEAVY CLEANING AND REMOVAL OF GREASE , USE OIL BASED MINERAL SPIRITS OR NAPHTHA. DO NOT TREAT WITH RUBBING COMPOUNDS OR LACQUER THINNER AS THIS MAY DISSOLVE OR ETCH THE COATING.
5. ALL BLADES MUST BE CLEAN, SHARP, AND PROPERLY MAINTAINED. DULL CUTTERS CREATE EXCESSIVE CHIPPING AND BURRING AND REDUCE THE QUALITY OF CUT. SAND DOWN CUT EDGES WITH 220 GRIT SAND PAPER. FILES MAY ALSO BE USED TO DEBUR SHARP EDGES. ALWAYS FILE DOWN ON THE DECORATIVE SURFACE. BEFORE CUTTING MATERIAL IT IS ALWAYS BEST TO TEST CUT FIRST TO CONFIRM RESULTS.
6. ROUTING: SHARP MULTI-FLUTED CARBIDE CUTTERS ARE NECESSARY WHEN CUTTING ALUMINUM. THE LARGER THE DIAMETER OF THE CUTTER THE BETTER RESULTS. THE SPEEDS RECOMMENDED ARE THE SAME AS THOSE USED IN STANDARD WOODWORKING PRACTICES. IT IS IMPORTANT TO USE A ROUTER HAVING ADEQUATE HORSEPOWER TO MAINTAIN CUTTING SPEEDS. IT IS ALSO IMPORTANT THAT THE CUTTER TRAVEL DIRECTION IS AGAINST THE CUTTER ROTATION. ALWAYS CUT DECORATIVE SIDE UP (INTO THE DECORATIVE FACE). WHEN ROUTING, THE LESS MATERIAL REMOVED THE BETTER. IT IS ALSO IMPORTANT THAT THE FACE OF THE MATERIAL BE PROTECTED FROM THE BASE PLATE OF THE ROUTER. FOR EDGE TRIMMING, HIGH SPEED TRIMMERS SHOULD BE USED (APPROXIMATELY 22,000 RPM) AND WILL PRODUCE SMOOTH BURR-FREE EDGES. WHEN USING A CNC ROUTER TO CUT ALUMINUM IT IS BEST TO USE THE MISTER ADD-ON TO SPRAY VEGETABLE OIL ON THE ROUTER BIT TO AIDE IN CUTTING. REFER TO YOUR CNC MANUAL FOR OPTIMAL SETTINGS WHEN CUTTING ALUMINUM.
7. SAWING: (TABLE AND PAN SAW) ALWAYS USE SHARP CARBIDE TIP BLADES WITH 80 TO 100 TEETH. BLADE SHOULD BE 8" TO 12" IN DIAMETER, AND AT 0 DEGREE RAKE FOR BEST RESULTS. IT IS ALWAYS BEST TO CUT INTO THE DECORATIVE FACE WITH THE BLADE TO MINIMIZE BURRING AND EDGE DISTORTION. DO NOT FORCE MATERIAL THROUGH SAW. A CONSTANT FEED RATE WILL PRODUCE SMOOTHER CUTS. BLADE WAX WILL PROMOTE BETTER CUTS.
8. SHEARING: BLADES MUST BE CLEAN, SHARP AND PROPERLY MAINTAINED. DUE TO PRESSURE, ONE SIDE WILL ALWAYS CHIP. TO AVOID CHIPPING TAKE SPECIAL ATTENTION TO PLACEMENT OF DECORATIVE METAL FACE AS FOLLOWS: FOR CHIP FREE CUT TO MATERIAL ON OPERATOR SIDE FEED THRU DECORATIVE FACE DOWN. FOR CHIP FREE CUT TO MATERIAL ON DROP SIDE FEED THRU DECORATIVE FACE UP. SHEARS USED TO CUT STAINLESS MAY BE DULL AND UNRELIABLE FOR PRECISION CUTTING. ALWAYS SAMPLE CUT FIRST.
9. LASER & WATERJET CUTTING: LASER JET IS NEVER RECOMMENDED ON PAINTED ALUMINUM, AS IT WILL LEAVE BURN MARKS ALONG EDGE OF METAL. WATER JET MAY BE MORE SUCCESSFUL USING A FINE CUT FOR ARCHITECTURAL FINISHES. CNC ROUTERS ARE TYPICALLY PREFERRED. IT IS RECOMMENDED TO SAMPLE TEST FIRST.
10. ADHESIVE SPECIFICATION: DAP WELDWOOD - THE ORIGINAL CONTACT CEMENT. PH. 800-543-3840.
11. GENERAL CONTRACTOR SHALL USE RUBBER 'J' ROLLER TO ROLL FLAT 'MOZ' METAL PANELS.
12. REFER TO 'MOZ' PANEL TECHNICAL MANUAL FOR ADDITIONAL INFORMATION FOR INSTALLATION AND CARE.
13. THIS INFORMATION IS INTENDED TO BE A GENERAL GUIDELINE. FOR FURTHER INFORMATION PLEASE CONTACT:
MOZ DESIGNS
711 KEVIN COURT
OAKLAND, CA. 94621 USA
PHONE: 510-632-0853
FAX: 510-632-0852
www.mozdesigns.com

PROJECT TEAM

GENESCO

GENESCO CONSTRUCTION DIVISION
GENESCO PARK, SUITE 604
P.O. BOX 731
NASHVILLE, TENNESSEE 37202-0731
615-367-7539 FAX: 615-367-7845

Kevin L. Cooper Architect AIA, ncarb
FL LICENSE #AR-0017120
316 South 1st Street
Rogers, Arkansas 72756
(479) 633-8181 fax (479) 633-9204
contactus@resourcedesign.net

JOHN D. FERGUSON, P.E., LEED
1700 W. Industrial Drive, Suite B
Rogers, AR 72756
(479) 986-4400 fax (479) 986-4401

DAVID M. LEIFFER, P.E., LEED
1700 W. Industrial Drive, Suite B
Rogers, AR 72756
(479) 986-4400 fax (479) 986-4401

TENANT COORDINATOR
BRIAN CONSTANTINE
TEL. 216-658-4439
email: brian.constantine@cbre.com

SKY GROUP
1100 SUPERIOR AVENUE
SUITE 600
CLEVELAND, OHIO 44114

VICINITY MAP



PROJECT DATA

JOURNEYS: A RETAIL SHOE STORE
TENANT IMPROVEMENT

ADDRESS:
SPACE #1540 LEVEL 1 OF 1
WESTLAND MALL
1675 WEST 49TH STREET
HIALEAH, FLORIDA 33012

TENANT AREA: 2652 SQ. FT.
NUMBER OF EMPLOYEES: 3/SHIFT (2 SHIFTS/DAY)

CONSTRUCTION TYPE: III-A FULLY SPRINKLERED

OCCUPANCY: GROUP M MERCANTILE
GROUP S-1 STORAGE
NON-SEPARATED MIXED USE

OCCUPANT LOAD:

SALES AREA =	1264 /30	=	42
STOCK ROOM =	1388 /300	=	5
TOTAL =	2652		47

APPLICABLE CODES:
INCLUDING BUT NOT LIMITED TO THE LATEST ADOPTED EDITIONS OF THESE CODES AS AMENDED BY MIAMI DADE COUNTY AND THE STATE OF FLORIDA

FLORIDA BUILDING CODE (2014)
FLORIDA PLUMBING CODE (2014)
FLORIDA MECHANICAL CODE (2014)
NATIONAL ELECTRICAL CODE (2011)
FLORIDA EFFICIENCY CODE (2014)
FLORIDA FIRE PREVENTION CODE (2012)

INDEX OF DRAWINGS

A1.1 COVER SHEET / INFORMATION
A2.1 SCHEDULES / NOTES
A2.1 DEMOLITION PLAN
A3.1 FLOOR PLAN
A3.2 REFLECTED CEILING PLAN
A4.1 FIXTURE PLAN AND DETAILS
A4.2 FIXTURE DETAILS
A5.1 STOREFRONT / INTERIOR ELEVATIONS
A5.2 INTERIOR ELEVATIONS
A5.3 MOZ PANELS
A6.1 WALL SECTIONS AND DETAILS
A7.1 TYPICAL DETAILS
A8.1 FIXTURE DETAILS
A9.1 SPECIFICATIONS

M1.1 MECHANICAL PLAN
M2.1 MECHANICAL AND PLUMBING SPECIFICATIONS

P1.1 PLUMBING AND SPRINKLER PLAN

E1.1 LIGHTING PLAN
E2.1 POWER PLAN
E3.1 ELECTRICAL ONE-LINE AND PANEL SCHEDULES
E4.1 ELECTRICAL SPECIFICATIONS

GJO-16-231
HIALEAH, FLORIDA
WESTLAND MALL
JY-1457
JOURNEYS

Drawing Data:

PROJECT NO.
GJO-16-231

STORE NO.
JY-1457

Drawn By: JTW
Checked By: KLC
Revisions:

Dwg Name: GJO-16-231c.dwg
Issue Date: 09-08-17
Sheet: 1 of 14

A1.1

Copyright©2017

Order Plans @ WWW.LDILine.com