



GENERAL NOTES:

1. ALL LOCATIONS AND DISTANCES ARE APPROXIMATE.
2. VACUUM EQUIPMENT AREA TO BE PROPERLY VENTILATED.
3. CUSTOMER TO VERIFY THE FOLLOWING:
 - A. ALL LOCATIONS,
 - B. ALL DISTANCES,
 - C. FINISHING ELEVATION AND ACCESS,
 - D. LINE SLOPE.
4. VACUUM LINES SHOULD COME UP CENTERED TO PROPOSED PARKING STRIPING. SEE CIVIL ENGINEERING SITE PLANS FOR STRIPING--DETAILS DIMENSIONS.

EUROVAC TO PROVIDE:

1. INSTALL ALL PVC THROUGH POST TO INTERCEPTOR (REFER TO DRAWINGS #1,2&4 ON PAGE 2 OF 3)
2. INSTALL TUBING BETWEEN BLOWER AND SEPARATOR (REFER TO DRAWING #: 6 ON PAGE 3)
3. INSTALL ALL EUROVAC VACUUM EQUIPMENT (REFER TO DRAWINGS #:1-6)

CONTRACTOR TO PROVIDE:

1. ANY WALL, FLOOR OR ROOF PENETRATIONS.
2. UNDERGROUND PVC AND ABOVE GROUND PVC TO CANOPY DROPS
3. ALL ELECTRICAL WIRING TO EUROVAC SYSTEMS

LEGEND:

- ① SINGLE ARCH WITH POST, 12" INTERCEPTOR & GARBAGE CANISTER (TYP.2)
- ② DOUBLE ARCH WITH POST, 12" INTERCEPTOR & GARBAGE CANISTER (TYP.9)
- ③ SINGLE CANOPY DROP (TYP.2)
- ④ DOUBLE CANOPY DROP (TYP.10)
- ⑤ EIII 50HP SYSTEM WITH 42" BAG SEPARATOR 1540 CFM @ 7.0 HG - EXHAUST CAPPED
- ⑥ EIII 50HP SYSTEM WITH 42" BAG SEPARATOR 1720 CFM @ 6.5 HG - EXHAUST CAPPED

Order Plans @

| REV. | DATE: | DESCRIPTION: |
|------|----------|----------------------------|
| 1 | 06/07/17 | LAYOUT BACKGROUND REVISION |
| 2 | | |
| 3 | | |
| 4 | | |
| 5 | | |

EUROVAC
WWW.EUROVAC.COM
TEL: 1-800-265-3878

| | |
|-----------------|----------|
| SCALE: | N.T.S. |
| DATE: | 01.06.17 |
| APPROVED BY: CR | |

SITE PLAN
SAM'S INDIAN TRAIL
PIPING LAYOUT

DRAWN BY:
AR