

1 FOUNDATION PLAN
SCALE: 3/8"=1'-0"

2 FRAMING PLAN
SCALE: 3/8"=1'-0"

FOOTING SCHEDULE (2000 PSF)

MARK	SIZE	THICK	REINFORCING
F30	3'-0"	1'-0"	2" x 2'-6" EACH WAY TOP AND BOTTOM

SOILS LABORATORY SHALL VERIFY SOIL BEARING PRESSURE AT CENTER OF EACH FOOTING PRIOR TO PLACING CONCRETE. STRUCTURAL FILL SUPPORTING SLAB OR FOOTINGS SHALL BE PLACED IN MAXIMUM LIFTS WITH EACH 8" LIFT TESTED BY LABORATORY FOR COMPACTION LISTED IN GENERAL NOTES.


COLUMN	BASE PLATE		GAGE		ANCHOR ROD		
	THICK.	X	Y	Gx	Gy	DIA.	EMBD.
HSS4x4x4	3/4"	10"	10"	7"	7"	3/4"	8"
HSS8x4x4	3/4"	14"	10"	11"	7"	3/4"	8"

4 COLUMN BASE PLATE SCHEDULE
NOT TO SCALE

FOOTING SCHEDULE
SCALE: NOT TO SCALE

Project
Sam's Xpress Car Wash
4965 University Parkway
Winston-Salem, NC 27106

Owner
Sam's Ma...
293 Church Place
Suite 200
Matthews, NC 28105



R4
ARCHITECTURE, P.A.

124 Floyd Smith Dr
Suite 375
Charlotte, NC 28262
Tel - 704 - 688-7500

7301 Rivers Avenue
Suite 188
North Charleston, SC 29406
Tel - 843 - 531-6848

www.R4architecture.com

Revision	Date

Drawn By PJW
Checked By JJM
Issue Date 06.15.17
Project No 170382

Sheet Title
Vacuum/Vending
Enclosure Plans

Sheet Number
S503



WWW.IDDILINE.COM

Order Plans

ALL GEOMETRIC CONCEPTS AND LEGENDS ARE THE PROPERTY OF R4 ARCHITECTURE, P.A. ANY UNAUTHORIZED USE OR REPRODUCTION IS SUBJECT TO LEGAL PROSECUTION. COPYRIGHT 2017.