



REF	PRODUCT	DESCRIPTION	NOTES
CFP	COPY/FAK/PRINTER		
CH-1	DESK CHAIR (LOW, NO ARMS)	ZODY ARMLESS TASK CHAIR	
CH-3	CUSTOMER STOOL (SHORT)	SHORT STOOL WITH WOOD TOP	
CH-4	CUSTOMER STOOL (TALL)	TALL STOOL WITH WOOD TOP	
CH-6	CUSTOMER BENCH	1'-10" X 5'-0"	
CH-7	STACKABLE BREAK ROOM CHAIR	SYSTEMS ARMLESS BREAKROOM CHAIR	
CH-10	CUSTOMER BAR STOOL		
FC-1	FILE CABINET	25" WIDE X 15" DEEP, 3 DRAWER	PROVIDED BY OWNER. HON 500 SERIES
IT/LAN	IT/LAN RACK		RACK PROVIDED AND INSTALLED BY CABLING VENDOR
KIT	FIRST AID KIT		PROVIDED BY OWNER. INSTALLED BY GC
LAD	LADDER	8' FOLDING, FIBERGLAS, 250# CAP. MIN	GC TO PURCHASE AND LEAVE IN STORE. ALLOWANCE TOTAL FOR MICROWAVE AND REFRIGERATOR
MIC	MICROWAVE (1 CUBIC FOOT)	MICROWAVE OVEN (WHITE)	GC TO PURCHASE AND INSTALL. ALLOWANCE TOTAL FOR MICROWAVE AND REFRIGERATOR
REF	REFRIGERATOR	15 CU. FT. REFRIGERATOR	GC TO PURCHASE AND INSTALL. ALLOWANCE TOTAL FOR MICROWAVE AND REFRIGERATOR
SAFE	DROP SAFE	8" X 24" X 24" X 24" H	FS PREVENTION VENDOR TO OBTAIN AND INSTALL SAFE
SC-2	TIME-DELAY INVENTORY CABINET	27" D X 48" L X 24" H, 1900 LBS	W/ 3" X 3" X 3" TO 3" X 3" X 3" WITH 3/8" DIAMETER ANCHOR BOLTS
SH-2	WALL MOUNT SHELF	12" W X 48" L X 30 13/16" H	3" SPACERS, RE: 05/A21
SH-3	SECURITY STORAGE CAGE	27 1/4" D X 62 1/2" L X 66 13/16" H	METRIC W/ K-SLOT SECURITY WITH 3 IN. SHOR SHELVES AND PLASTIC TUBS
STAG	STAGING SHELF		
T-1	MANAGER'S DESK	NATIONAL 10-3060P/46, \$9,511	
T-3	HIGH TABLE		
T-4	CUSTOMER BAR TABLE	24" ROUND BAR TABLE	
TB	TECH BENCH		
VQ	VIRTUAL QUEUE SCREEN		PROVIDED BY OWNER. INSTALLED BY GC

\* NOT ALL ITEMS LISTED ARE USED FOR THIS PROJECT  
\*\* ALL FURNITURE/EQUIPMENT IS PROVIDED BY OWNER OR SEPARATE VENDOR AND ASSEMBLED & INSTALLED BY G.C. UNLESS NOTED OTHERWISE

FIXTURE	DESCRIPTION
001 APC	
037 DIGITAL DISPLAY	
103 4x5' GRAPHIC	
104 4x5' GRAPHIC	
105 4x5' GRAPHIC	
425 CREDENZA	
478 POS	
608 STOREFRONT GRAPHIC	
617 APPLE TABLE	
621 OEM TABLE	
623 ACCESSORY STORY	
624 ACCESSORY STORY	
646 ACCESSORY STORY	

CODE	PRODUCT	MANUFACTURER	STYLE	COLOR	NOTES	FLAME SPREAD RATING
WB-1	WALL BASE					
VB-1	VINYL BASE	JOHNSONITE		#63 BURNT UMBER	4, 7, 11	UL 992. 2.0 [CLASS C] ASTM E-84-769. 200 CLASS C
P-1	PAINT	BENJAMIN MOORE	AURA WATERBORNE INTERIOR, SATIN	DECORATORS WHITE PM-3	1, 4	ASTM E-84. CLASS A
P-2	PAINT	BENJAMIN MOORE	WATERBORNE CEILING, MATTE (S22)	DECORATORS WHITE PM-3	1, 4	ASTM E-84. CLASS A
P-4	PAINT	BENJAMIN MOORE	AURA WATERBORNE INTERIOR, SEMI-GLOSS (S28)	DECORATORS WHITE PM-3	1, 4	ASTM E-84. CLASS A
FRP-1	FIBER REINFORCED PANEL	NUDO	FIBERLITE	WHITE (50)	4, 5	CLASS A/1. FLAME SPREAD 25 PER ASTM E-84-91A
CPT-1	CARPET TILE	SHAW	SCAPE/62YJ9 W/ ECOLOGIX CUSHION	DISTANCE/78597	10	MEETS NFPA CLASS 1 PER ASTM E-648
CPT-2	ENTRY CARPET TILE	SHAW	BON JOUR II/ST032	EBONY/31500	6, 8	ASTM E-648-08. CLASS 1
CS-1	CONCRETE SEALER			CLEAR	4	
VCT-1	VINYL COMPOSITE TILE	ARMSTRONG	IMPERIAL TEXTURE	51915 CHARCOAL	2, 3, 4	ASTM E-648. P 0.45 [CLASS 1]

NOTES:  
1. WALLS (TYP) MATTE. TOILET WALLS SEMI-GLOSS. DOORS AND FRAMES (TYP) SEMI-GLOSS.  
2. SEAL, APPLY 2 COATS OF WAX AND POLISH VCT PER MFG. RECOMMENDATIONS.  
3. INSTALL IN A BASKETWEAVE PATTERN.  
4. MUST MEET OR EXCEED LEED STANDARDS FOR LOW VOC AND LOW EMISSIONS.  
5. PROVIDE FRP PANELS TO 4'-0" A.F.F. IN TOILET ROOMS, AS REQUIRED BY CODE AND AROUND JANITORS SINK.  
6. INSTALL PATTERN PARALLEL TO STOREFRONT.  
7. DO NOT PROVIDE BASE BEHIND FIXTURES ALONG WALLS IN SALES 101. INSTALL BASE BEFORE CARPET  
8. 24" X 24" TILES  
9. INSTALL WITH ARROW POINTING TOWARD BACK OF STORE. SEE PLAN  
10. INSTALL IN A 1/4-TURNED PATTERN  
11. REFER TO DETAIL A13/A21 AT FLAT WIRE CUT-OUTS

FINISH SCHEDULE AND LEGEND	E06
A. G.C. IS TO PROTECT ALL SURFACES BEFORE CONSTRUCTION BEGINS AND RESTORE TO LIKE-NEW CONDITIONS ONCE CONSTRUCTION IS COMPLETED.	H. ALL FLOORING AT ALL FRONT OF THE HOUSE AREAS MUST BE INSTALLED TIGHT TO PARTITION.
B. G.C. TO FURNISH AND INSTALL REDUCING OR TRANSITION STRIP AT ALL VCT FLOORING AND OTHER FLOORING TRANSITIONS BETWEEN FLOORING MATERIALS.	I. FINAL PROFESSIONAL CLEANUP BY G.C.
C. FINISHES CALLED OUT SHALL EXTEND OVER, UNDER, AND/OR BEHIND ANY ITEMS OF BUILT-IN MILLWORK, EQUIPMENT, MIRRORS, ETC. AS INDICATED ON DRAWINGS.	J. G.C. TO PROVIDE 10 PERCENT OF ALL MATERIALS INCLUDING BUT NOT LIMITED TO FLOOR FINISHES, CEILING FINISHES, WALL BASES, ETC. FOR "ATTIC STOCK."
D. COVE BASE TO BE USED IN ALL AREAS INDICATED. USE ROLL GOODS ONLY. NO SEAMS SHALL OCCUR WITHIN 6" OF AN OUTSIDE CORNER.	K. G.C. TO VERIFY CONDITION OF EXISTING FLOOR. EXPOSED CONCRETE TO BE PRESENTABLE, FREE OF GLUE, STAPLES, CRACKING, ETC. FLOOR CONDITION TO BE VERIFIED FOR EVEN LEVEL. G.C. TO REPORT ANY DISCREPANCY & CONDITION TO THE ARCHITECT.
E. BEFORE PROCEEDING WITH PROCUREMENT, THE RESPECTIVE INSTALLER SHALL FIELD VERIFY DIMENSIONS TO ASSURE THAT SUFFICIENT QUANTITIES OF MATERIAL ARE ORDERED TO COMPLETE THE WORK.	L. NO SEALERS OR FINISHES TO BE APPLIED UNTIL FLOORS ARE SWEEPED AND MOPPED CLEAN.
F. UPON RECEIPT FROM THE MANUFACTURER, THE INSTALLER SHALL INSPECT MATERIALS FOR DEFECTS, FLAWS, SHIPPING DAMAGE, CORRECT COLOR AND PATTERN. PRIOR TO BEGINNING WORK, DAMAGED OR WRONG MATERIALS SHALL BE RETURNED TO THE MANUFACTURER FOR IMMEDIATE REPLACEMENT TO PREVENT DELAYS IN THE COMPLETION OF THE WORK.	M. DIMENSIONS ON DRAWINGS ARE FINISH FACE TO FINISH FACE OF PARTITIONS, COLUMNS, ETC., OR WHERE SHOWN, UNLESS OTHERWISE NOTED. DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS TAKE PRECEDENCE OVER GRAPHIC REPRESENTATION. DETAIL DIMENSIONS TAKE PRECEDENCE OVER PLAN DIMENSIONS.
G. COMPLIANCE WITH THE MANUFACTURER'S REQUIREMENTS FOR HANDLING, STORAGE, INSTALLATION, AND PROTECTION IS THE EXCLUSIVE RESPONSIBILITY OF THE G.C. AND THEIR RESPECTIVE INSTALLERS.	

FURNITURE AND EQUIPMENT LEGEND	E21
NOTE: 1. ALL FIXTURES ARE FURNISHED AND INSTALLED BY SPRINT (FIXTURE VENDOR) 2. FIXTURE VENDOR TO PROVIDE FIXTURES WITH BASE APPLIED 3. INSTALL TOP OF GRAPHICS 103-105 AT 8'-6" A.F.F. CENTER GRAPHICS ON LIGHT FIXTURES WHERE POSSIBLE 4. IF SITE CONDITIONS REQUIRE SHIFTING OF FIXTURE LOCATIONS, THE FLOOR/WALL OUTLET LOCATIONS MUST BE COORDINATED AND ADJUSTED ACCORDINGLY. 5. AT APC INSTALL 22X28 POSTER FRAME GRAPHIC CENTERED ABOVE APC OUTLETS, MOUNTED AT 7'-0" A.F.F. TO TOP 6. FIXTURE VENDOR TO PROVIDE CUT OUT IN BASE OF ALL ADJOINING POS FIXTURES AT EXISTING KNOCK-OUT LOCATION TO PROVIDE CLEAN PATHWAY BETWEEN FIXTURES FOR CABLE AND WIRE.	

FINISH GENERAL NOTES	A06
1. A CALCIUM CHLORIDE MOISTURE TEST MUST BE PERFORMED ON ALL NEW CONCRETE FLOOR SLABS. IF HIGHER THAN ALLOWED LEVELS OF MOISTURE ARE PRESENT, CONTRACTOR MUST APPLY MOHAWK'S SEALER PER MANUFACTURER'S INSTRUCTIONS. PROVIDE BID ALTERNATE TO PROVIDE THIS MOISTURE TEST AND SEALER IF REQUIRED.	
2. TRANSITION FROM CARPET TO CONCRETE/TILE. PROVIDE ROPPE SLT-63-B - BURNT UMBER.	
3. CENTER SEAM (OR TILE) ON ENTRANCE DOOR	
4. SEE S22/A21 FOR ATTACHMENT DETAILS	
5. FRP-1 TO 4'-0" HIGH IN ALL WET AREAS INDICATED	
6. GC TO INSTALL BLACKOUT FILM AS INDICATED. PROVIDE 3M PRODUCTS OR APPROVED EQUAL.	
7. PAINT EXISTING STEEL COLUMN P-4.	

FINISH KEY NOTES	E01

FINISH AND FIXTURE PLAN	L01

PROJECT NUMBER	SPR1408
SHEET AUTHOR	CHAD OLSONSON
DATE	SEPTEMBER 26, 2017
SHEET TITLE	FINISH AND FIXTURE PLAN
PROJECT NUMBER	SPR1408
SHEET NUMBER	A13