



- 1 EXISTING WINDOW AND FRAME TO REMAIN
  - 2 REMOVE EXISTING DOOR AND FRAME COMPLETE.
  - 3 PORTION OF EXISTING SOFFIT AND FRAMING TO BE REMOVED. REMOVE PORTION OF SOFFIT/ROOFING STRUCTURE BACK TO EXISTING WALL AS REQUIRED.
  - 4 EXISTING METAL ROOF TO REMAIN.
  - 5 NOT USED.
  - 6 REMOVE EXISTING DOWNSPOUT, GUTTER AND FASCIA BOARD.
  - 7 REMOVE EXISTING PARAPET WALL COMPLETE.
  - 8 REMOVE PORTION OF WALL COMPLETE AS REQUIRED FOR NEW OPENING INTO NEW SEATING ADDITION.
  - 9 REMOVE EXISTING BRICK BACK TO EXISTING WALL SHEATHING.
  - 10 EXISTING WINDOW AND FRAME TO BE SALVAGED AND RE-USE DIN NEW LOCATION.
  - 11 REMOVE EXISTING SIDEWALK, CONCRETE SLAB PATIO, LANDSCAPING AND ANY OTHER ITEMS IN THE AREA OF NEW CONSTRUCTION. G.C. TO COORDINATE WITH OWNER IF ANY ITEMS TO BE REMOVED ARE TO BE SALVAGED FOR REINSTALLATION OR REUSED IN OTHER AREAS NOT MENTIONED IN DRAWINGS.
  - 12 EXISTING EXTERIOR LIGHTING TO REMAIN.
  - 13 REMOVE EXISTING METAL ROOF AND INSULATION COMPLETE.
  - 14 EXISTING LANDSCAPING TO BE REMOVED.
  - 15 REMOVE EXISTING BRICK PILASTER COMPLETE.
  - 16 REMOVE EXISTING BOLLARD AND GATE. G.C. TO COORDINATE WITH OWNER ON RE-USE.
  - 17 EXISTING EXTERIOR LIGHTING TO BE REMOVED AND STORED FOR RE-USE IN NEW LOCATION.
- 3 DEMOLITION ELEVATION KEYNOTES  
 12" = 1'-0"

PERMIT SET	
DRAWN BY	LAJ
CHECKED BY	KRB
DATE	6/22/2017
REV.   DATE	DESCRIPTION

The Construction Documents shall consist of all drawings, specifications, surveys, soils reports, addenda and other documents. It is the responsibility of the contractor to verify the accuracy of all information and drawings. The contractor shall be responsible for reviewing the entire set of Construction Documents to determine their particular scope of work. Any discrepancy between the drawings and specifications shall be interpreted at the sole discretion of the Architect.

SHEET TITLE  
 DEMOLITION  
 ELEVATIONS  
**D2.0**

1 DEMOLITION ELEVATION 1  
 1/4" = 1'-0"

QUALITY CONTROL CHECK: ADA EGRESS SNOW GUARDS SLAB THICKNESS