

- NOTES:
- (1) SUPPLY AND RETURN EXHAUST AIR VALVE OFFSETS SHALL MAINTAIN SPACE PRESSURE RELATIONSHIPS
 - (2) ROOM PRESSURE MONITOR SHALL BE SET TO ALARM AT MINIMUM PRESSURE DIFFERENTIAL OF +0.020" W.C. TAB CONTRACTOR TO SET INITIAL BALANCE FOR +0.30" W.C. COORDINATE WITH TAB CONTRACTOR TO ADJUST AIR BALANCE DIFFERENTIAL AS NECESSARY TO ACHIEVE MINIMUM PRESSURE DIFFERENTIAL. MINIMUM PRESSURE DIFFERENTIAL.
 - (3) ROOM PRESSURE MONITOR SHALL BE SET TO ALARM AT MINIMUM PRESSURE DIFFERENTIAL OF -0.020" W.C. TAB CONTRACTOR TO SET INITIAL BALANCE FOR -0.30" W.C. COORDINATE WITH TAB CONTRACTOR TO ADJUST AIR BALANCE DIFFERENTIAL AS NECESSARY TO ACHIEVE MINIMUM PRESSURE DIFFERENTIAL.
 - (4) ROOM PRESSURE MONITOR SHALL MONITOR PRESSURE DIFFERENTIAL BETWEEN CLEAN ROOM AND ANTE ROOM, AND BETWEEN ANTE ROOM AND PHARMACY.
 - (5) EXHAUST FROM BIOLOGICAL SAFETY CABINET.
 - (6) HEPA CEILING DIFFUSERS.
 - (7) ORIFICE PLATE BALANCING DAMPER.

NEW PHARMACY

Order Plans @

10/02/2017 10:02:48 AM
C:\Users\j...Documents\Rev 2018 Loc...7540.00 - CBV/MC Pharmacy.jgh.rvt

Revisions:	Date:

CONSULTANT


Consultant:

 5802 Research Park Boulevard
 Madison, WI 53719
 608.238.2616
 aeieag.com

ARCHITECT/ENGINEER OF RECORD

A/E:

 LACHIN Architects, APC
 Architecture . Planning . Project Management
 5190 Canal Boulevard, Suite 201
 New Orleans, LA 70124
 (504)835-8013



Office of Construction and Facilities Management

Drawing Title MECHANICAL DIAGRAMS
Phase CONSTRUCTION DOCUMENTS
Approved:

Project Title RENOVATE PHARMACY CLEAN ROOM (USP 797)
Location 510 E. Stoner Ave. Shreveport, LA 71101
Issue Date 10/05/2017
Checked KGF
Drawn JBP

Project Number 667-17-108
Building Number 1
Drawing Number M600