


| DOOR SCHEDULE | | | | | | | | | | | | | | |
|---------------|------------------|------|-------|--------|--------|--------|--------|-------|--------|-------------|----------------------|----------------------|----------|------------------------------------|
| Door Number | Room Name | Door | | | | Frame | | | | Fire Rating | Head | Jamb | Sill | Comments |
| | | Elev | Width | Height | Thk | Mat'l | Finish | Mat'l | Finish | | | | | |
| 101 | LOBBY | F | 6'-0" | 7'-0" | 1 3/4" | ALM/GL | PREFIN | ALM | PREFIN | | F4/AG.02 | A4/AG.02 | F1/AG.02 | INCLUDES TEMPERED GLAZING SIDELITE |
| 102A | CORRIDOR | D | 3'-0" | 7'-0" | 1 3/4" | WD/GL | STN | HMWD | PNT | | D11/AG.01 & D4/AG.01 | A11/AG.01 & A6/AG.01 | AG/AG.01 | |
| 102B | CORRIDOR | G | 6'-0" | 7'-0" | 1 3/4" | ALM/GL | PREFIN | ALM | PREFIN | | F8/AG.02 | A10/AG.02 | F1/AG.02 | |
| 103 | MENS | B | 3'-0" | 7'-0" | 1 3/4" | WD | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 104 | WOMENS | B | 3'-0" | 7'-0" | 1 3/4" | WD | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 105 | JC | B | 3'-0" | 7'-0" | 1 3/4" | WD | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 106 | MEZZ ACCESS | B | 3'-0" | 7'-0" | 1 3/4" | WD | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 110 | CITY CORRIDOR | E | 3'-0" | 7'-0" | 1 3/4" | ALM/GL | PREFIN | ALM | PREFIN | | F10/AG.02 | A10/AG.02 | F1/AG.02 | |
| 111 | OFFICE | A | 3'-0" | 7'-0" | 1 3/4" | WD/GL | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 112 | OFFICE | A | 3'-0" | 7'-0" | 1 3/4" | WD/GL | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 113 | OFFICE | A | 3'-0" | 7'-0" | 1 3/4" | WD/GL | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 114 | CONFERENCE | A | 3'-0" | 7'-0" | 1 3/4" | WD/GL | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 121A | OFFICE | A | 3'-0" | 7'-0" | 1 3/4" | WD/GL | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 121B | OFFICE | C | 6'-0" | 7'-0" | 1 3/4" | WD | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 123A | OFFICE | A | 3'-0" | 7'-0" | 1 3/4" | WD/GL | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 123B | OFFICE | B | 3'-0" | 7'-0" | 1 3/4" | WD | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 124A | BREAK RM | A | 3'-0" | 7'-0" | 1 3/4" | WD/GL | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 124B | BREAK RM | A | 3'-0" | 7'-0" | 1 3/4" | WD/GL | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 130A | TRAINING ROOM #1 | A | 3'-0" | 7'-0" | 1 3/4" | WD/GL | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 130B | TRAINING ROOM #1 | A | 3'-0" | 7'-0" | 1 3/4" | WD/GL | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 131 | AV | B | 3'-0" | 7'-0" | 1 3/4" | WD | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 140A | TRAINING ROOM #2 | A | 3'-0" | 7'-0" | 1 3/4" | WD/GL | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 140B | TRAINING ROOM #2 | A | 3'-0" | 7'-0" | 1 3/4" | WD/GL | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 141 | AV | B | 3'-0" | 7'-0" | 1 3/4" | WD | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |
| 142 | STOR | C | 6'-0" | 7'-0" | 1 3/4" | WD | STN | HMWD | PNT | | D11/AG.01 | A11/AG.01 | | |

DOOR ELEVATIONS
SCALE: 1/4" = 1'-0"



| TYPICAL CONSTRUCTION TYPES | |
|--|---|
| WALL CONSTRUCTION | DOOR CONSTRUCTION |
| TYPICAL BRICK CONSTRUCTION BRICK VENEER CONT BOARD INSULATION CONT AIR + WATER BARRIER | TYPICAL CONCRETE CONSTRUCTION CONCRETE 2" MIN RIGID INSUL. BASE - R-20 MIN MTL STUD FRAMING |
| TYPICAL STACKED STONE WALL CONSTRUCTION DRY STACKED STONE VENEER MORTAR-FILLED CAVITY 1" CONT BOARD INSULATION CONT AIR + WATER BARRIER | TYPICAL GYP BOARD CONSTRUCTION 5/8" GYP BOARD FINISH DRAWINGS FOR WALL FINISH INSULATION - SEE WALL TYPES |
| TYPICAL EPS CONSTRUCTION EPS INSULATION R + WATER BARRIER | TYPICAL MTL STUD FRAMING CONSTRUCTION MTL STUD FRAMING W/ BOX HEADERS & INSULATION @ HEAD, TYP SEALANT, BOTH SIDES WOOD TRIM CASING MOUNTED TO FRAME WOOD BLOCKING HM OR FRAME, WITH NO BACKBEND, ANCHOR INTO FRAMING |


2701 1st Avenue S
Birmingham, AL 35233
T 205.879.4482
GMCNETWORK.COM

| ISSUE DATE | ISSUE | DESCRIPTION |
|----------------------|-------|-------------|
| BID ISSUE 11/30/2017 | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |


DRAWN BY: AJ/STH
CHECKED BY: JEO

Oneonta Community Development
Center
100 1st Ave W.
Oneonta, AL 35121
GMC # ABHM170022


DOOR SCHEDULE,
LEGEND, & DETAILS
A6.01
Sheet of




D4 INT SIDELITE HEAD
SCALE: 3" = 1'-0"




D6 INT SIDELITE MULLION
SCALE: 3" = 1'-0"




D8 INT GYP OPENING HEAD
SCALE: 3" = 1'-0"




D11 INT GYP DOOR HEAD
SCALE: 3" = 1'-0"




A4 INT SIDELITE JAMB
SCALE: 3" = 1'-0"



A6 INT SIDELITE SILL
SCALE: 3" = 1'-0"



A8 INT GYP OPENING JAMB
SCALE: 3" = 1'-0"



A11 INT GYP DOOR JAMB
SCALE: 3" = 1'-0"

Order Plans @

WWW.LDILLINE.COM