


11/28/2017 6:37:05 AM

TREKOR ARCHITECTS
1100 CANADA ROAD, SUITE 210
BIRMINGHAM, ALABAMA 35202
PHONE: 205.878.2600
FAX: 205.878.2606
PROJECT #1711



2701 1st Avenue S
Birmingham, AL 35233
T 205.879.4462
GMCNETWORK.COM

ISSUE DATE	ISSUE
	BID ISSUE 11/30/2017

DRAWN BY: KJA
CHECKED BY: CJS

Oneonta Community Development
Center
100 1st Ave W.
Oneonta, AL
GMC # ABHM170022



FLOOR AND FOUNDATION PLAN,
MEZZANINE AND ROOF FRAMING PLAN
\$2.01
sheet of

FOUNDATION AND FLOOR PLAN

- SCALE: 1/8"=1'-0"
1. FINISH FLOOR (TOP OF SLAB) ELEVATION 0'-0", UNLESS NOTED.
 2. TOP OF FINISH FLOOR ELEVATION (C.O.F.) 2'-0", UNLESS NOTED.
 3. FINISH FLOOR ELEVATION, UNLESS NOTED, SEE GENERAL NOTES AND TYPICAL DETAILS.
 4. GENERAL CONTRACTOR COORDINATE LOCATION OF ALL FOOTING STEPS WITH MECHANICAL, ELECTRICAL, AND PLUMBING DRAWINGS.
 5. GENERAL CONTRACTOR COORDINATE FLOOR DEPRESSION DEPTH, SIZE AND LOCATION WITH ARCHITECTURAL DRAWINGS.
 6. DENOTES SHEAR WALL HOLD-DOWN, SEE TYPICAL DETAIL ON SHEET S1.03.
 7. DENOTES SHEAR WALL LOCATION, SEE TYPICAL DETAIL ON SHEET S1.03.
 8. PROVIDE TRIPLE STUDS WHERE GIRDER AND HIP TRUSS BEARS ON WALL.
 9. HSS4X4X1/4 POST EA SIDE OF OPENING.
 10. FOR EXTENT OF EXTERIOR GRADE HIGHER THAN FINISH FLOOR, SEE CIVIL DWGS. IN NO CASE SHALL THE EXTERIOR GRADE BE HIGHER THAN THE 8" CWL.
 11. HSS 1/2x3 1/2x1/4 POST SUPPORT FOR CANTILEVER WALL, COORDINATE LOCATIONS W/ ARCH DWGS.

MEZZANINE FRAMING PLAN

- SCALE: 1/8"=1'-0"
1. TOP OF MEZZANINE FLOOR FINISH ELEVATION 11'-4", UNLESS NOTED.
 2. MEZZANINE FLOOR FINISH ELEVATION 11'-4", UNLESS NOTED.
 3. FROM FLOOR FINISH TO MEZZANINE FINISH JOIST AT 150 PSF LIVE LOAD.
 4. PROVIDE STEEL FRAMING AS SHOWN INCLUDING OPENINGS WHERE INDICATED ON PLAN.

ROOF FRAMING PLAN

- SCALE: 1/8"=1'-0"
1. TRUSS BEARING ELEVATION 14'-6", UNLESS NOTED.
 2. ROOF SYSTEM: 1 1/2" STEEL ROOF DECK ON LIGHT GAUGE TRUSSES @ 48" MAX, UNLESS NOTED. SEE GENERAL NOTES FOR ROOF DECK ATTACHMENT PATTERN, REQUIREMENTS WITH TRUSS MANUFACTURER.
 3. TRUSS MANUFACTURER TO DESIGN TRUSSES TO RESIST LOADS PROVIDED IN THE GENERAL NOTES AND ANY ADDITIONAL LOADS SHOWN ON THE PLAN OR IN SECTIONS.
 4. TRUSS LAYOUT ON PLAN IS FOR SCHEMATIC PURPOSE ONLY. FINAL LAYOUT IS THE RESPONSIBILITY OF THE TRUSS MANUFACTURER.
 5. PROVIDE TRIPLE STUDS WHERE GIRDER AND HIP TRUSS BEARS ON WALL.
 6. PROVIDE TRIPLE STUDS WHERE GIRDER AND HIP TRUSS BEARS ON WALL.
 7. X X X INDICATE EXTENT OF MEZZANINE FLOOR CONSTRUCTION.