

11/22/2017 10:50:34 AM

G:\TORRID\17127\Academics\17127\Drawings\Work in Progress\17127.044\_R3\_SPEC.rvt

Order Plans @ WWW.TORRID.COM

**10870 STORAGE SHELVING AND WORK COUNTERS**  
 PART 1 - GENERAL  
 A. CONTRACTOR TO ASSEMBLE AND INSTALL SHELVING UNITS AND/OR SURFACE MOUNTED STANDARDS, WITH BRACKETS AND SHELVES.  
 B. PROVIDE COMPLETE SYSTEM, FURRING STRIPS EXCLUDED, WITH BRACKETS, CLIPS, SHELVES, RELATED SCREWS AND ANCHORS.  
 PART 2 - PREPARATION / EXECUTION  
 A. CONTRACTOR TO ASSEMBLE AND SECURE SHELVING UNITS TO FLOOR AND WALLS WITH FASTENERS AS RECOMMENDED BY MANUFACTURER IN LOCATIONS AS SHOWN AND DETAILED IN PLANS.  
 B. CONTRACTOR TO PROVIDE REQUIRED BLOCKING, FURRING STRIPS AND BRACING. REFER SECTION 08114 AND SECTION 05500.  
 C. CONTRACTOR TO PROVIDE WORK COUNTERS AS DESCRIBED IN PLANS AND DETAILS.

**10800 TOILET ROOM ACCESSORIES**  
 PART 1 - GENERAL  
 A. PROVIDE ADA APPROVED TOILET ROOM ACCESSORIES AND GRAB BARS INCLUDING ALL SET SCREWS AND ANCHORS REQUIRED FOR COMPLETE INSTALLATION. REFER TO DRAWINGS.  
 B. MANUFACTURER: "BOBRICK" OR EQUAL.  
 C. PROVIDE ITEMS AND QUANTITIES AS INDICATED ON DRAWINGS.  
 PART 2 - PREPARATION / EXECUTION  
 A. INSTALL TOILET ACCESSORY UNITS ACCORDING TO MANUFACTURER'S INSTRUCTION, USING FASTENERS AND IN-WALL BLOCKING AS RECOMMENDED BY UNIT MANUFACTURER. INSTALL UNITS PLUMB AND LEVEL, FIRMLY ANCHORED IN LOCATIONS & AT HEIGHTS INDICATED, IN A TAMPER PROOF MANNER WITH SPECIAL HANGERS, TOGGLE BOLTS, OR SCREWS.

**DIVISION 11 - EQUIPMENT**  
**11001 GENERAL**  
 A. ALL EQUIPMENT MANUALS, INSTRUCTION BOOKLETS, AND WARRANTY INFORMATION SHALL BE DELIVERED, BOUND AND TURNED OVER TO THE CONSTRUCTION MANAGER PRIOR TO THE TURN-OVER.  
 B. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR BRINE TROOP-UP ALL EQUIPMENT, INCLUDING ALL MECHANICAL, PLUMBING AND ELECTRICAL WORK.  
 C. INSTALLATION OF ALL EQUIPMENT (INCLUDING TENANT FURNISHING) IS TO BE INCLUDED IN GENERAL BID.

**11106 WALL STANDARDS**  
 PART 1 - GENERAL  
 A. SURFACE MOUNTED WALL STANDARDS AS INDICATED ON DRAWINGS.  
 PART 2 - PREPARATION / EXECUTION  
 A. CONTRACTOR TO SET TOP WALL STANDARDS LASER LEVEL AND LOCATED AS DETAILED IN DRAWINGS.  
 B. CONTRACTOR TO ENSURE THAT WALL STANDARDS ARE SET TRUE AND PLUMB AND MAXIMUM OF 24" ON CENTER UNLESS OTHERWISE NOTED.

**11200 AUDIO-VISUAL EQUIPMENT**  
 PART 1 - GENERAL  
 A. COORDINATION WITH RESPONSIBILITY SCHEDULE AND OWNER FOR INSTALLATION.  
 PART 2 - PREPARATION / EXECUTION  
 A. VERIFY ELECTRICAL REQUIREMENTS ARE AVAILABLE AND IN PLACE FOR INSTALLATION.  
 B. INSTALL AS RECOMMENDED BY MANUFACTURER'S INSTRUCTIONS.

**DIVISION 12 - FURNISHINGS**  
 1. FIXTURES, ETC. INDICATED ON THE PLANS ARE FURNISHED BY TENANT. CONTRACTOR TO COORDINATE INSTALLATION AS INDICATED IN DRAWINGS.

**DIVISION 13 - SPECIAL CONSTRUCTION**  
 1. NO WORK UNDER THIS SECTION.

**DIVISION 14 - CONVEYING SYSTEMS**  
 1. NO WORK UNDER THIS SECTION.

**DIVISION 15 - MECHANICAL**  
 1. SEE "R4" SHEET.

**DIVISION 16 - ELECTRICAL**  
 1. SEE "R5" SHEET.



architecture - planning - interior design  
 C.M. ARCHITECTURE, P.A.  
 A PROFESSIONAL ARCHITECTURAL CORPORATION  
 800 WASHINGTON AVENUE, SUITE 208  
 MINNEAPOLIS, MN 55401-4148  
 PHONE: (612) 547-1100  
 FAX: (612) 547-1100  
 CONTACT: KELLY GIVEN  
 korridd@torrid.com

**5677**

CONSULTANTS:  
 MEP ENGINEER:  
 AEDIFICA CASE  
 796 MERUS COURT  
 ST. LOUIS, MO 63026  
 PH: (636) 349-1600

SEAL:

PATRICK G. BLEES, ARCHITECT

SIGNATURE: \_\_\_\_\_  
 DATE ISSUED: 11.2.17  
 REG. NO. 6140

**TORRID**

ACADIANA MALL  
 5725 JOHNSTON STREET  
 LAFAYETTE, LA  
 70503  
 SPACE #B-115  
 NEW MALL A

SHEET TITLE:  
 SPECIFICATIONS

REVISIONS:

NO.	DATE:	BY:

PROJECT NO: 17127.044  
 DRAWN BY: NY

**R3**

COPYRIGHT C.M. ARCHITECTURE, P.A. 2017