

NOTES:
1. 3500 PSI MIN. 28 DAY COMPRESSIVE STRENGTH CONCRETE WITH GRADE 60 REINFORCING STEEL
2. IF WATER IS PRESENT IN HOLE, REMOVE BEFORE POURING CONCRETE.
3. FOUNDATION EXCAVATION SHALL BE BY 24" AUGER IN UNDISTURBED OR PROPERLY COMPACTED FILL PER SPECIFICATIONS.
4. FOUNDATION SHALL HAVE A MINIMUM ALLOWABLE END BEARING OF 2000 PSF.
5. FOUNDATION HAS BEEN DESIGNED FOR A GRANULAR SOIL BASED ON A MINIMUM LATERAL SOIL PRESSURE OF 1000 PSF, UTILIZING AASHTO FIGURE 1.8.2(4) OF "EMBEDMENT OF POSTS WITH OVERTURNING LOADS".
6. DETAIL FOR 56' POLE WITH MAX. FIXTURE EPA 4.6 SQ.FT.
7. ALL LIGHT POLE BASE FOUNDATIONS SHALL BE CAST-IN-PLACE. PRE-CAST LIGHT POLE BASE FOUNDATIONS ARE NOT ACCEPTABLE.

NOTE: FOR INFORMATIONAL PURPOSES ONLY, AND BOHLER ENGINEERING SHALL BE HELD HARMLESS IN THE EVENT OF A STRUCTURAL FAILURE.

TYPICAL LIGHTING POLE BASE DETAIL
N.T.S.

TYPICAL LIGHTING POLE BASE DETAIL	10/02/07

NOTE: FINAL DESIGN TO BE PROVIDED BY STRUCTURAL ENGINEER.


CORNER BARS – SAME SIZE AND SPACING AS HYRIZONTAL BARS
#3 @ 16"OC5 BOND FOR TERMINAL SPECIFICATION
PLAN
CORNER BAR
REFER TO ARCH. PLANS FOR LOCATION
VENTED GRATE FOR THE DRAINAGE BROOM MANHOLE
4" SOLID TRAFFIC YELLOW PAINTED EDGE STRIPE
4" SOLID TRAFFIC YELLOW PAINTED STRIPE WITH 18" SPACING AT 45° ANGLE
STRIPING DETAILS NOT TO BE APPLIED UNTIL FINAL ASPHALT LIFT
N.T.S.
EXTERIOR FACE OF BUILDING WALL
REFER TO ARCH. PLANS FOR OPENING
REFER TO ARCH. PLANS FOR LOCATION
SEE GRADING (REFER CIVIL SITE GRADING PLAN)
NOTE: TOP OF MANHOLE TO BE LEVEL WITH FINISH GRADE UNLESS OTHERWISE NOTED OR DIRECTED BY THE ENGINEER. USE ADJUSTMENT RINGS AS REQUIRED BUT NOT TO EXCEED 12".
RING & VENTED COVER PER SITEWORK SPECIFICATIONS
SEE NOTE "A"
REFER TO ARCH. PLANS
INVERT ELEVATION (REFER TO ARCH./ MOT PLANS)
GROUT BOTTOM TO SLOPE TO OUTLET PIPE
CONCRETE SURROUND
SECTION "A"
"A" SECTION
"A" HEIGHT
PIPE
CONCRETE
WALL THICKNESS
GENERAL NOTES:
1. ALL JOINTING COMPOUND TO HAVE 3/4" DIAMETER.
2. REFER DRAWING PLAN FOR PIPE SIZES, LOCATIONS, AND INVERTS.
3. A SQUARE OR RECTANGULAR MANHOLE MAY BE USED IN LIEU OF A ROUND MANHOLE. PIPES SHALL CONNECT TO THE ENDS OF SIDES OF THE MANHOLE. DEFLECTION SHALL NOT BE MADE AT CORNERS OF MANHOLE.
4. ALL REINFORCING BARS TO BE GRADE 60.
5. ALL REINFORCING BARS TO HAVE 3" COVER.
6. OPENINGS FOR INLET & OUTLET PIPES ARE LOCATED AS REQUIRED PER GRADING
7. A 4'-0" PAINTED STRIPED AREA SHALL BE CENTERED ON THE MANHOLE (REFER TO MARKING DETAIL) TO INDICATE ANY PARKING OR STORING IS TO BE LIMITED ON THE MANHOLE. STRIPING SHALL BE PAINTED WITH 4" SOLID TRAFFIC YELLOW STRIPES SPACED AT 45° ANGLE.
8. PRECAST MANHOLE MAY BE USED UNLESS OTHERWISE NOTED OR DIRECTED BY THE E
PRECAST MANHOLE SPECIFICATIONS:
ASTM C478 – PRECAST REINFORCED CONCRETE MANHOLE SECTIONS
ASTM C913 – PRECAST CONCRETE WATER AND WASTEWATER STRUCTURES
CONCRETE 4000 PSI AT 28(D)
JOINT: MASTIC/BUTYL RUBBER GASKET
REINFORCEMENT SCHEDULE, BASE SECTION
TABLE OF "A" DIMENSIONS
REINFORCEMENT SCHEDULE, WALLS
TABLE OF "A" DIMENSIONS
REINFORCEMENT SCHEDULE, CONE
DIMENSIONS
SPECIAL PATTERN
DIAGONAL @ COVER
DIAGONAL @ CENTER
DIAGONAL @ CENTER
DIAGONAL @ CENT