



- GENERAL DEMOLITION NOTES:**
1. TEMPORARILY SEAL OPENINGS THAT OCCUR DUE TO DEMOLITION.
 2. REMOVE ALL WALLS, DOORS, WINDOWS, ETC. OF EXISTING BUILDING THAT ARE REPRESENTED WITH DASHED LINES.
 3. WHERE WALLS, DOORS, WINDOWS, ETC. ARE REMOVED PREP FOR NEW FINISHES.
 4. DEMOLISH EXISTING FIXTURES, PREP/REPAIR WALLS, FLOORS AND CEILINGS FOR NEW PLUMBING AND ELECTRICAL REPLACEMENT AS REQUIRED.
 5. DEMOLISH EXISTING FIXTURES, AS NEEDED AND PARTITIONS - PREP FOR NEW TOILET AND PARTITION LAYOUTS AS REQUIRED.
 6. DEMOLISH ALL EXISTING DOMESTIC WATER SUPPLY PLUMBING, REPLACE ALL DOMESTIC WATER SUPPLY PIPING FROM METER.
 7. DEMOLISH ALL ELECTRICAL WIRING AND REPLACE/RE-FULL ALL ELECTRICAL WORK, UPDATE PANEL/CONDUIT AND CIRCUITS AS NECESSARY.
 8. ALL SELECTIVE DEMOLITION OF MASONRY WALLS AND CONCRETE FLOORS SHALL BE NEATLY CUT AND REPLACED AS NECESSARY FOR FINISHED SURFACE OR APPLICATION OF SCHEDULED FINISH. TYPICAL. NOTE: SOME AREAS OF MASONRY WALLS AND FLOORS WILL NEED TO BE DEMOLISHED IN ORDER TO GAIN ACCESS ALLOWING NEW ELECTRICAL PLUMBING WORK TO BE INSTALLED. S.C. TO COORDINATE WITH PLUMBING AND ELECTRICAL SUB CONTRACTORS THE AREAS NEEDED AND REPLACE AS REQUIRED TYPICAL.

**POOL HOUSE AREA
DEMOLITION
PLAN
SHEET**
POOL HOUSE & EQUIPMENT
POOL HOUSE ELEVATIONS

**ROYAL GIANTS
PARK - 2017
RENEWAL PROJECT**
200 ROBINSON ROAD
EAST SPENCER, NC 28039

