



- SOUND SYSTEM 1 WIRING CODED NOTES
- 200 4" SQUARE J-BOX WITH COVERPLATE ON UNISTRUT.
 - 201 HOMERUN FROM MANAGER'S DESK OR OTHER LOCATION AS INDICATED ON THE ELECTRICAL DRAWINGS TO SPEAKER J-BOXES AS LOCATED ON THE ELECTRICAL DRAWINGS.
 - 202 VOLUME CONTROL WITH 4" SQUARE BOX WITH SINGLE GANG TRIM RING LOCATED IN MANAGER'S OFFICE.
 - 203 HOMERUN TO MANAGER'S OFFICE. COORDINATE LOCATION OF VOLUME CONTROLS WITH G.C.
 - 204 HOMERUN FROM MAIN EQUIPMENT RACK LOCATION TO TELEPHONE EQUIPMENT BACKBOARD. FIELD VERIFY EXACT LOCATION AND REQUIREMENTS.
 - 205 SPEAKER FURNISHED AND INSTALLED BY PLAY NETWORK.
 - 206 12" X 12" X 6" J-BOX TO RECEIVE CONDUIT.
 - 207 PAINT INSIDE OF JUNCTION BOX BLUE AND HANG 12" FLAG (TYP.).

- SOUND SYSTEM INSTALLATION NOTES
1. SEE SOUND SYSTEM WIRING NOTES FOR FURTHER DETAILS ON INSTALLATION OF SUPPLIES AND CABLE BY ELECTRICAL CONTRACTOR.
 2. MOUNTING HARDWARE, SPEAKERS, AMPLIFIER, INSTALLATION AND FINAL CONNECTION ARE BY "OWNER".
 3. SEE ARCHITECTURAL REFLECTED CEILING PLAN FOR EXACT LOCATIONS OF SPEAKERS. ELECTRICAL CONTRACTOR SHALL NOTE ANY CONFLICTS IN FIELD AND NOTIFY ELECTRICAL ENGINEER OF SAME. CIRCUIT CHANGE MUST BE APPROVED BY ELECTRICAL ENGINEER OR "OWNER".

Order Plans

WWW.LDREVIEWS.COM