



1 DUMPSTER ENCLOSURE - FOUNDATION PLAN 3/8" = 1'-0"

FOUNDATION NOTES:

- ELEV. 40'-0" IS REFERENCE ONLY. SEE CIVIL FOR TRUE NGVD ELEVATION.
- C.J. INDICATES CONTROL JOINT SEE S4.1 FOR DETAILS.
- T.E. INDICATES THICKENED EDGE SEE S4.1 FOR DETAILS.
- VERIFY SLOPES AND STEPS WITH ARCH'L PRIOR TO CONSTRUCTION. SEE TYPICAL STEP DETAIL ON S4.1.
- ALL MASONRY WALLS ARE MW-1 U.N.O., SEE SCHEDULE ON THIS SHEET.
- MF-# DENOTES MONOLITHIC CONCRETE FOOTING, SEE SCHEDULE THIS SHEET.
- INDICATES WALL CONTROL JOINT, SEE DETAIL ON S4.1.
- FLOOR CONSTRUCTION: 6" THICK CONCRETE SLAB ON GRADE W/ #4 AT 12" O.C. E-W, MID-DEPTH, AND 8" THICK CONCRETE SLAB REINF. W/ #5 AT 12" O.C. E-W, MID-DEPTH.
- FOOTING EXCAVATIONS SHALL BE FREE OF WATER BEFORE PLACING CONCRETE.
- CONTRACTOR TO COORDINATE ALL FLOOR DRAINS AND PLUMBING PRIOR TO PLACING CONCRETE FOOTINGS OR SLAB.

| MASONRY WALL SCHEDULE | | |
|-----------------------|-----------|----------------|
| MARK | THICKNESS | REINFORCING |
| MW-1 | 8" CMU | #6 AT 48" O.C. |

| FOOTING SCHEDULE | | |
|------------------|---------------------|-------------------|
| MARK | SIZE | REINFORCING |
| MF36.1B | 3'-6" X 18" X CONT. | (4) #6 CONT. BOTH |

MASONRY WALL NOTES:

- WALL SEGMENTS SHALL BE REINFORCED WITH 9 GA. GALVANIZED LATERAL REINFORCING @ 16" O.C. HORIZ. EXTEND REINFORCING 6" INTO POURED ELEMENTS AND AROUND ENCASED STEEL.
- ADJACENT TO ANY EXTERIOR/INTERIOR WALL OPENING, PLACE VERTICAL IN CELL GROUTED SOLID, FULL HEIGHT.
- ALL MASONRY REINFORCED CELLS SHALL BE FILLED WITH 3000 PSI GROUT MIX.

Order Plans

| NO. | DATE | REMARKS |
|-----|------|---------|
| | | |



BID SET
JANUARY 8, 2018
**7-ELEVEN
STORE #**
5544 RONALD REAGAN PARKWAY
DAVENPORT, FL
33896

PROJECT NO: 2016.0305
DATE: 5-31-2017

S5.1
DUMPSTER ENCLOSURE
AND SECTIONS

CHECKED: BM DRAWN: RED

COPYRIGHT © 2016 INTERPLAN, LLC. REPRODUCING, CHANGES OR ASSIGNMENTS ARE PROHIBITED.