

REFLECTED CEILING PLAN SHEET NOTES

- SEE SHEET A002 FOR WALL TYPES AND HEIGHT OF WALLS ABOVE CEILING.
- SEE FINISH SCHEDULE FOR CEILING TYPES & MATERIALS IN EACH ROOM / AREA.
- PERIMETER TRACK FOR ALL ACoustICAL CEILING GRIDS TO BE 2" WIDE, INSTALLED IN ACCORDANCE WITH IBC AND CISCA GUIDELINES.
- DIMENSIONS ARE TO FACE OF STUD.
- CEILING GRIDS TO BE CENTERED IN ALL ROOMS UNLESS NOTED OTHERWISE. PARTIAL TILES AT ROOM PERIMETERS SHALL NOT BE LESS THAN 6" IN EITHER DIMENSION.
- SEE ELECTRICAL, FIRE ALARM AND FIRE PROTECTION DRAWINGS FOR SPECIAL SYSTEMS, SMOKE DETECTORS, LIGHTING AND WALL MOUNTED FIXTURES NOT SHOWN ON THIS SHEET. COORDINATE LOCATIONS OF ALL FIXTURES NOT INDICATED WITH LAYOUT INDICATED ON THIS SHEET.
- LIGHT FIXTURES AND MECHANICAL DIFFUSERS ARE SHOWN FOR POSITIONING IN FINISH CEILING SYSTEM. COORDINATE WITH MECHANICAL AND ELECTRICAL DRAWINGS FOR FIXTURE TYPES, MECHANICAL DIFFUSERS, WALL MOUNTED FIXTURES AND INSTALLATION OF FIXTURES IN SPACES WITHOUT CEILINGS. LIGHTING AND HVAC DIFFUSERS ARE SHOWN FOR COORDINATION ONLY. SEE MECHANICAL AND ELECTRICAL DRAWINGS FOR SPECIFIC INFORMATION.
- SEE MECHANICAL FLOOR PLANS FOR EXTENT OF EXPOSED DUCTWORK IN EXPOSED STRUCTURE AREAS WITHOUT CEILINGS.
- EXTEND PERIMETER WALLS AND FINISH TO STRUCTURE ABOVE AT EXPOSED STRUCTURE AREAS. PAINT ALL EXPOSED DUCTWORK, PIPING, AND HANGERS TO MATCH CEILING.
- SEE MECHANICAL AND ELECTRICAL DRAWINGS FOR MOUNTING OF STUDS OF WHICH NO CEILING IS INDICATED.
- CENTER LIGHTS, DIFFUSERS, EXIT SIGNS, SMOKE DETECTORS, SPEAKERS, GENERAL ALARM SPEAKERS, STROBES & MISC DEVICES IN CEILING TILES WHERE THEY ARE LOCATED. ALIGN MULTIPLE ITEM CENTER OR EDGES.
- LOCATE MECHANICAL GRILLES AND DIFFUSERS SHOWN IN CORRIDORS OR NEAR WALL TO 12" OFF WALLS, UNO.
- INSTALL ACCESS PANELS IN GYPSUM BOARD CEILINGS AT DUCTWORK LOCATIONS. DUCT MOUNTED SMOKE DETECTORS AND DUCT CONTROLS SHALL BE INSTALLED IN THE CEILING WHERE THEY OCCUR.

WILKES COMMUNITY COLLEGE  
**WILKES COMMUNITY COLLEGE**  
 SC# 220-011A  
 NCCS# 220-011A  
**CULINARY LAB**

LS3P  
 227 WEST TRADE STREET SUITE 700  
 CHARLOTTE, NORTH CAROLINA 28202  
 TEL. 704.333.6686 FAX 704.333.2926  
 WWW.LS3P.COM

LS3 ASSOCIATES LTD.  
 CERT. NO. 50417  
 WILKES COMMUNITY COLLEGE  
 12/18  
 MEMBERS OF THE AMERICAN INSTITUTE OF ARCHITECTS


COPYRIGHT 2018 ALL RIGHTS RESERVED  
 PRINTED OR ELECTRONIC DRAWINGS AND DOCUMENTATION MAY NOT BE REPRODUCED IN ANY FORM WITHOUT WRITTEN PERMISSION FROM LS3P ASSOCIATES LTD.

REVISIONS:


No.	Description	Date

PROJECT: 9202-16979  
 DATE: 12/18  
 DRAWN BY: ZS  
 CHECKED BY: WSB


REFLECTED CEILING PLAN  
**A-121**




E1 CLOUD SECTION DIAGRAM 1  
 1/8" = 1'-0"




E3 CLOUD SECTION DIAGRAM 2  
 1/8" = 1'-0"




E4 LAY-IN CEILING PERIMETER DETAIL  
 6" = 1'-0"




E5 HORIZONTAL RESTRAINT  
 3" = 1'-0"




D1 DINING LAB CLOUD DIAGRAM  
 3/16" = 1'-0"



D3 TYPICAL FLOATING CEILING PANEL  
 1/2" = 1'-0"



D2 CEILING PANEL DETAIL  
 1/2" = 1'-0"



A1 FIRST FLOOR REFLECTED CEILING PLAN  
 3/16" = 1'-0"

P:\\_EDU\2020\9202-16979\Wilkes Community College\_Culinary Lab\2.0 Design\Drawings\WCC\_CULINARY LAB\_16.rvt  
 11/20/18 11:15:00 AM

Order Plans @ [www.lsdline.com](http://www.lsdline.com)