

12/19/2017 1:36:35 PM

P:\01 Projects\2017 Projects\17645 7 Eleven Kissimmee at Carrill 7 Dyer\Drawings\Working Drawings\17645\_7 Eleven Kissimmee R16.rvt



SELECT STRUCTURAL  
12573 New Brittany Blvd  
Fort Myers, Florida 33907  
Phone: (239) 210-5090  
info@selectstructural.com  
Certification Auth. 28357



106 N 37TH STREET, SUITE C  
ROGERS, ARKANSAS 72756  
WWW.BATESSTRUCTS.COM  
TEL: 479.633.8888

CONSTRUCTION MANAGER  
CREIGHTON CONSTRUCTION & MANAGEMENT, LLC  
900 SW PINE ISLAND ROAD, SUITE 202  
CAPE CORAL, FL 33991

TENANT  
7-ELEVEN INC.  
3200 HACKBERRY ROAD,  
IRVING, TX 75063

STRUCTURAL CONSULTANT  
SELECT STRUCTURAL  
15573 NEW BRITANNY BLVD  
FORT MYERS, FL 33907

7-ELEVEN STORE  
SW/O CAROL ST. & DYER BLVD.  
KISSIMMEE, FL 34741  
CREIGHTON CONSTRUCTION & MANAGEMENT, LLC  
900 SW PINE ISLAND ROAD, SUITE 202  
CAPE CORAL, FL 33991

Engineer Name - SHAWN ANDERSON  
Engineer Number - 53515  
THE SEAL AND SIGNATURE APPLY ONLY TO THE DOCUMENT TO WHICH THEY ARE AFFIXED AND WE HEREBY DISCLAIM ANY RESPONSIBILITY FOR ALL OTHER PLANS, SPECIFICATIONS, ESTIMATES, REPORTS OR OTHER DOCUMENTS OR INSTRUMENTS RELATING TO OR INTENDED TO BE USED FOR ANY PARTS OR PARTS OF THE PROJECT.

REVISIONS

NO.	DATE	DESCRIPTION
-----	------	-------------


PROJECT NUMBER: 17111  
RELEASE DATE: 12/19/2017

DETAILS & SECTIONS


S5.1

OPENING WIDTH LINTEL SIZE


W < 6'	8F8
6' ≤ W ≤ 10'	8F16-1B/2T
10' < W < 14'	8F24-1B/2T




1 STEPPED BOND BEAM  
NTS




2 PRECAST LINTEL SCHEDULE  
NTS




3 TYPICAL BOND BEAM CORNER  
NTS




4 JOIST STIFFENER DETAIL  
NTS




5 JOIST TO BOND BEAM CONNECTION  
NTS




6 TYPICAL JOIST BRIDGING AT CMU WALL  
NTS



7 JOIST AT STEEL BEAM  
3/4" = 1'-0"




8 METAL DECK TO BOND BEAM  
NTS



9 ROOF OPENING CURB FRAMING  
NTS


ROOF TOP UNIT FRAME SCHEDULE

UNIT WEIGHT	ANGLE SIZE
0-1000 LBS	L 3x3x1/4"
1001-2500 LBS	L 4x4x1/4"
2501-6000 LBS	L 6x6x3/8"




10 ROOF OPENING FRAMING  
NTS

- LOCATE ANGLE BELOW ALL EQUIP CURBS AND AROUND ALL ROOF OPENINGS. SEE MECH CURB FRAMING DETAIL FOR FRAME SUPPORT ANGLE SIZE.
- CONTRACTOR SHALL VERIFY LOCATIONS AND SIZE OF OPENINGS PRIOR TO STEEL FABRICATION.
- FRAME IS REQ'D FOR OPENINGS 1'-0" AND GREATER.



11 DECK ANGLE SPLICE DETAIL  
NTS



12 MECHANICAL CURB FRAMING  
3/4" = 1'-0"

THIS ITEM HAS BEEN ELECTRONICALLY SIGNED AND SEALED USING A DIGITAL SIGNATURE.  
PRINTED COPIES OF THIS DOCUMENT ARE NOT CONSIDERED SIGNED AND SEALED AND THE SIGNATURE MUST BE VERIFIED ON ANY ELECTRONIC COPIES.