

PERFORMANCE SPECIFICATION - CONT.

SECTION VII ELECTRICAL WORK

PART 1 - GENERAL

- 1.1 SCOPE: THIS SECTION COVERS THE FURNISHING OF ALL LABOR, MATERIALS, SERVICES, EQUIPMENT AND APPLIANCES REQUIRED IN CONJUNCTION WITH OR PROPERLY INCIDENTAL TO THE FURNISHING AND INSTALLATION OF COMPLETE ELECTRICAL WORK INCLUDING:
1.1.1 ELECTRICAL SERVICE AND DISTRIBUTION SYSTEM, INCLUDING CONDUITS, PANEL BOARD OUTLET BOXES, WIRING, SWITCHES, OUTLETS, ETC.
1.1.2 CONDUIT AND WIRING SYSTEM FOR INTERCOM.
1.1.3 WIRING SYSTEM TO SERVE ALL ELECTRIC-USING DEVICES, LIGHTING FIXTURES, PUMPS, CONTROL EQUIPMENT, DISPENSERS, DEVICES AND OTHER CURRENT CONSUMING EQUIPMENT.
1.1.4 POWER AND CONTROL WIRING WITH FINAL CONNECTIONS TO ALL EQUIPMENT.
1.1.5 ALL CONDUITS, CONNECTIONS, WIRE AND STUB-OUTS FOR FASCIA SIGN(S) (WHEN SHOWN), CANOPY LIGHTS, PRICE SIGN(S) AND CANOPY MOUNTED FLOOD LIGHTS.
1.1.6 CONDUITS AS MAY BE SHOWN FOR "FUTURE EQUIPMENT" ON DRAWINGS.
1.1.7 ALL TRENCHING, EXCAVATIONS AND BACK FILL AS REQUIRED IN CONJUNCTION WITH ELECTRICAL WORK.
1.1.8 INCIDENTAL ITEMS NOT INDICATED ON THE DRAWINGS OR MENTIONED IN THE SPECIFICATIONS, BUT WHICH ARE REQUIRED TO PROVIDE COMPLETE ELECTRICAL SYSTEMS IN CONFORMANCE WITH REQUIREMENTS OF LOCAL CODES AND ORDINANCES AND THE NATIONAL ELECTRIC CODE.
1.2 CODES AND REGULATIONS: COMPLY WITH LATEST REQUIREMENTS OF LOCAL UTILITY COMPANY, LOCAL, STATE, OSHA, NATIONAL ELECTRIC CODES, NATIONAL FIRE PROTECTIVE ASSOCIATION AND LOCAL ELECTRICAL INSPECTION AUTHORITY. REPORT TO OWNER IMMEDIATELY ANY DISCREPANCIES BETWEEN DRAWINGS AND CODES. PROVIDE INSTALLATION SUPERIOR TO CODE WHERE SO INDICATED ON DRAWINGS AND SPECIFIED HEREIN.
1.3 PERMITS, FEES, TAXES: ARRANGE AND PAY FOR ALL NECESSARY PERMITS, FEES, AND TAXES.
1.4 PROGRESS OF WORK: SCHEDULE WORK WITH THAT OF OTHER TRADES AND IN RELATION TO ENTIRE INSTALLATION SO THAT THE ENTIRE PROJECT CAN BE COMPLETED PER CONSTRUCTION SCHEDULE.
1.5 CUTTING AND REPAIRING: PROVIDE ALL CUTTING, CHANNELING, PATCHING, ETC. AS NECESSARY FOR ELECTRICAL WORK UNDER DIRECTION OF GENERAL CONTRACTOR. WORK FOUND TO BE DEFECTIVE OR INCORRECTLY INSTALLED IS TO BE CORRECTED AT THE DIRECTION OF THE OWNER AT NO ADDITIONAL COST TO THE OWNER. MAKE REPAIR WORK TO BE DONE BY SKILLED CRAFTSMEN IN TRADES INVOLVED, BUT PAID FOR THE ELECTRICAL SUBCONTRACTOR.

PART 2 - PRODUCTS

- 2.1 IDENTIFICATION OF EQUIPMENT AND WIRING: PROVIDE IDENTIFICATION WITH DYMO TAPE OR EQUAL FOR ALL SERVICE ENTRANCE AND DISTRIBUTION EQUIPMENT INCLUDING MAIN SWITCH GEAR, PANELS, DISCONNECT SWITCHES, CONDUITS, ETC., AND FOR MOTOR FEEDERS INCLUDING SWITCHES, STARTERS AND MOTORS.
2.2 LIGHT FIXTURES: TO BE PROVIDED BY OWNER.
2.3 CONDUITS: PROVIDE THE FOLLOWING TYPES OF RACEWAYS IN ACCORDANCE WITH THE SPECIFIC APPLICATION OF LOCATION INDICATED.
2.3.1 STP POWER CONDUITS MUST BE RUN IN SEPARATE RACEWAY. ENTIRE WIRING RUN MUST BE IN RIGID PVC COATED GALVANIZED STEEL CONDUIT. USE ONLY ROB ROY CONDUIT TYPES "PERMA-COAT", "PLASTI-BOND" OR "KORKAP" ELECTRICAL CONDUITS. NO PVC OR RNC CONDUIT ALLOWED.
USE ONLY ROB ROY CONDUIT TYPES "PERMA-COAT", "PLASTI-BOND" OR "KORKAP" ELECTRICAL CONDUITS AT FIBERGLASS TANK SUMPS OR WHERE BRAVO F-17-RR OR F-10-RR ENTRY FITTINGS ARE CALLED OUT FOR FIRST 10' OF RUN. TRANSITION TO RIGID NONMETALLIC CONDUIT (RNC) WHERE ALLOWED BY JURISDICTION.
RUN PVC COATED GALVANIZED STEEL FOR WIRING RUNS EXPOSED TO THE WEATHER; FOR ENCLOSING MAIN GROUNDING CONDUCTOR, WHERE REQUIRED FOR MECHANICAL PROTECTION OR WHERE SPECIFICALLY INDICATED.
WITH THE EXCEPTION OF THE FIRST 10' AND THE LAST 10' OF THE UNDERGROUND RUN AND ONLY WHERE A.H.U. ALLOWS, RIGID NONMETALLIC CONDUIT (RNC) IS ALLOWED FOR UNDERGROUND RUNS IF CONDUIT IS BURIED AT A MINIMUM OF 2'.
2.3.2 SEAL-OFFS: WHERE CONDUITS EXIT FLOOR OR CONCRETE AT DISPENSERS, AUTO GAUGING, SUBMERSIBLE PUMPS AND N.E.C. CLASSIFIED AREAS (REF G9.1).
2.3.3 N.E.C. APPROVED WEATHER PROOF WIRE PULL BOX.
2.4 CONDUCTORS:
2.4.1 FURNISH AND INSTALL COLOR CODED COPPER CONDUCTORS, 600 VOLT, OF SIZES INDICATED. MINIMUM SIZE #12 EXCEPT FOR SIGNAL AND CONTROL CIRCUITS AND WHERE OTHERWISE NOTED, TYPE TW (60 DEGREES CENTIGRADE) FOR GENERAL BRANCH CIRCUIT WIRING; TYPE THHN (90 DEGREES CENTIGRADE) FOR SUPPLY CONNECTIONS TO LIGHT FIXTURES; AND TYPE CU-AL PER CODE OF NEC.
2.4.2 SHIELDED CABLES: PROVIDE SHIELDED CABLE FOR INTERCOM AS PER MANUFACTURER'S SPECIFICATIONS AND AS REQUIRED ON DRAWINGS.
VARIABLE SPEED PUMP CABLE:
- THWN-2 #12 AWG 4 CONDUCTOR 600V SHIELDED (SOIL RESISTANT).
DATA COMMUNICATION CABLE:
- SHIELDED WIRE MUST NOT BE USED.
- 2 WIRE TWISTED PAIR (UTP) W/ 10 P TWISTS PER FOOT.
- WIRING IS STRANDED ANNEALED COPPER TINNED WITH MINIMUM REQUIRED FOR RUNS UP TO 1000 FEET OR 14 AWG FOR RUNS UP TO 2600 FEET. DO NOT DAISY CHAIN COMMUNICATION WIRING.
- INSTALLATION SPECIFIC TO PVC INSULATION, TYPE TFFN OR MTW, UL APPROVED GASOLINE AND OIL RESISTANT.
2.5 SPLICES AND CONNECTIONS: PROVIDE SPLICES ONLY IN READILY ACCESSIBLE OUTLET BOXES. PROVIDE INSULATED PRESSURE CONNECTORS "SCOTCHLOK" OR "CON-ON" SLEEVES WITH OVERALL NYLON INSULATORS FOR CONDUCTORS. CONNECTORS SHALL BE 3M "SCOTCHLOK" BUCHANAN SLEEVES WITH INSULATED WRAP, OR IDEAL "CRIMP-SLEEVES" WITH SCAP CAP INSULATOR OR EQUIVALENT.
2.6 PANEL BOARD:
2.6.1 BRANCH CIRCUIT PANEL BOARDS: PROVIDE FLUSH-MOUNT CIRCUIT BREAKER TYPE PANEL BOARDS WITH THERMAL MAGNETIC, MOLDED CASE, "SQUARE D" TYPE NLAB OR APPROVED EQUAL, WITH PLUG-IN CIRCUIT BREAKERS, "SQUARE D" TYPE NLTQ. PROVIDE GROUNDING TERMINAL BLOCK IN EACH PANELBOARD. SEE INDIVIDUAL PANEL SCHEDULE ON DRAWINGS.
2.6.2 SUBSTITUTES: DISTRIBUTION EQUIPMENT EQUIVALENT IN TYPE, CLASSIFICATION AND QUALITY IN ACCORDANCE WITH NEMA STANDARDS AS MANUFACTURED BY G.E., CUTLER-HAMMER, FEDERAL PACIFIC, ITE, SQUARE D AND WESTINGHOUSE ARE ACCEPTABLE AS SUBSTITUTES ONLY WHEN APPROVED IN WRITING.

SECTION VII ELECTRICAL WORK - CONTINUED

PART 3 - EXECUTION

- 3.1 GENERAL: COORDINATE TIME SCHEDULES, INSTALLATION, HOOKUPS AND MISCELLANEOUS PROCEDURES WITH ALL OTHER TRADES THAT WILL BE INVOLVED TO EXPEDITE THE COMPLETION OF THE CONTRACT. THE ELECTRICAL SUBCONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE PROPER INSTALLATION OF THE ELECTRICAL WORK.
3.2 CONDUITS: FURNISH AND INSTALL A COMPLETE OVERALL CONDUIT RACEWAY SYSTEM FOR ALL WIRING AND CONDUCTORS. PROVIDE SIZES AND RACEWAYS AS INDICATED ON DRAWINGS OR AS REQUIRED BY NATIONAL ELECTRICAL CODE FOR CONDUCTORS TO BE CONTAINED. ALL RACEWAYS SHALL CONFORM TO THE FOLLOW REQUIREMENTS.
3.2.1 CONCEAL ALL CONDUIT RUNS EXCEPT WHERE EXPOSED RUNS ARE AUTHORIZED BY OWNER'S CONSTRUCTION MANAGER IN WRITING.
3.2.2 ACTUAL CONDUIT RUNS ARE NOT GENERALLY INDICATED. CONDUITS AT TANKS SHALL NOT CROSS OVER TANKS. PLACE CONDUIT THROUGH EACH END OF TANK EXCAVATION AND PLACE FIELDS PARALLEL WITH AXIS OF TANKS.
3.2.3 CLEAN AND DRY ALL RACEWAYS THOROUGHLY BEFORE CONDUCTORS ARE PULLED IN.
3.2.4 FLASH AND COUNTER FLASH CONDUITS WHICH PENETRATE THE CANOPY DECKING.
3.2.5 PROVIDE SEAL-OFF FITTINGS WHERE CONDUIT RUNS ENTER OR LEAVE HAZARDOUS AREAS OF DISSIMILAR CONDITIONS SUCH AS TEMPERATURE, HUMIDITY, ETC.
3.2.6 FURNISH AND INSTALL COMPLETE RACEWAY SYSTEM, INCLUDING CONDUITS AND OUTLETS, AS INDICATED AND AS REQUIRED FOR INTERCOM SYSTEM, GAS PRICE SIGNS, SECURITY LIGHTING AND CANOPY LIGHTING SYSTEM, AND LIGHTED FASCIA SYSTEM WHERE APPLICABLE. CONDUIT AMOUNTS AND SIZES SHALL BE AS SHOWN ON GASOLINE DRAWINGS. ADDITIONAL CONDUITS AND CIRCUITS WILL BE REQUIRED FOR LIGHTED FASCIA SYSTEMS. PROVIDE AS REQUIRED.
3.3 LIGHTING: INSTALL ALL LIGHTING FIXTURES AND LAMPS AS INDICATED ON DRAWINGS. SECURELY MOUNT ALL FIXTURES; PROVIDE ALL ADDITIONAL HANGERS AND SUPPORTS AS NECESSARY TO SECURELY FASTEN AND SUPPORT FIXTURES. CLEAN ALL FIXTURES AND LAMPS UPON COMPLETION OF THE PROJECT. CONTRACTOR SHALL VERIFY AMOUNT AND TYPE OF ISLAND/CANOPY LIGHTING SYSTEMS. SHOULD ADDITIONAL CONDUITS/CIRCUITS BE REQUIRED, VERIFY THROUGH LOCAL CONSTRUCTION OFFICE AND PROVIDE AS REQUIRED.
3.4 SIGNS AND LIGHTED FASCIA: VERIFY FINAL LOCATIONS AND TYPE WITH OWNER. FURNISH AND INSTALL ALL CONDUITS AND WIRES WITH STUB-OUTS AS DIRECTED. MAKE FINAL CONNECTIONS AS REQUIRED.
3.5 OUTLETS: COORDINATE LOCATION OF ALL ELECTRICAL EQUIPMENT, INCLUDING INTERCOM OUTLETS, SWITCHES, RECEPTACLES, CONTROLLERS, PANEL BOARDS, SWITCH GEAR, ETC., TO AVOID INTERFERENCE AND OBSTRUCTIONS WITH EQUIPMENT OF OTHER CRAFTS AND TRADES SO THAT ELECTRICAL EQUIPMENT WILL NOT BE BLOCKED OR MADE INACCESSIBLE OR IMPERMEABLE. PROVIDE WEATHERPROOF OUTLETS WHERE EXPOSED TO THE WEATHER OR MOISTURE.
3.6 ISOLATED GROUND: IT IS MANDATORY THAT GASOLINE EQUIPMENT REQUIRING ISOLATED GROUND SHALL BE PROVIDED WITH SAME. MINIMUM CIRCUITS REQUIRED, BUT NOT LIMITED TO, SHALL BE: INTERCOM, CONSOLE, AND GASOLINE TANK MONITORING SYSTEM.
3.7 EXCAVATION AND BACK FILLING: ALL EXCAVATION AND BACK FILLING NECESSARY FOR THE INSTALLATION OF ELECTRICAL WORK SHALL BE INCLUDED IN THIS SECTION AND COMPLY WITH SECTION VIII, EARTHWORK.
3.8 OPERATING AND ACCEPTANCE TESTS:
3.8.1 CONDUCT OPERATING TEST ON ENTIRE ELECTRICAL INSTALLATION; ALL SYSTEMS MUST BE COMPLETE AND IN GOOD OPERATING ORDER. REFER TO SECTION VIII FOR STARTUP AND FINAL CHECK-OUT OF SYSTEM COVERED ELSEWHERE. DO NOT START OPERATING EQUIPMENT WITHOUT SPECIFIC DIRECTIVES OF OWNER'S SPECIFIED REPRESENTATIVE. ANY DAMAGE TO OWNER'S EQUIPMENT DUE TO DEFECTIVE INSTALLATION AND/OR OPERATIONS SHALL BE THE RESPONSIBILITY OF THAT SUBCONTRACTOR. CORRECTION, REPLACEMENT AND/OR MONETARY COMPENSATION AS REQUIRED.
3.8.2 MAKE INSULATION TESTS ON ALL SERVICE EQUIPMENT AND ALL FEEDERS AND PANELBOARDS.
3.8.3 TEST GROUND RESISTANCE TO GROUND SHALL NOT EXCEED 25 OHMS.
3.8.4 INSPECT ALL PANELBOARDS. ALL CONNECTIONS MUST BE TIGHT AND SECURE.
3.9 "AS-BUILT" DRAWINGS: FURNISH OWNER'S CONSTRUCTION MANAGER WITH ONE SET OF MARKED-UP PRINTS (HARDCOPY) AND ALSO IN AUTO CAD 2004 COMPATIBLE DRAWING FILE FORMAT (.DWG) SHOWING "AS-BUILT" INSTALLATION.
3.10 FINAL ACCEPTANCE: UPON COMPLETION OF WORK, PRESENT CERTIFICATE OF APPROVAL OF LOCATION OR GOVERNING INSPECTION AUTHORITY.
3.11 CLEANUP: CLEAN UP ALL DEBRIS CAUSED BY WORK OF THIS SECTION, KEEPING THE PREMISES CLEAN AND NEAT AT ALL TIMES.

SECTION VIII PAINTING

PART 1 GENERAL

- 1.1 SCOPE: THIS SECTION COVERS THE FURNISHING OF ALL LABOR, MATERIALS, SERVICES, EQUIPMENT AND APPLIANCES IN CONJUNCTION WITH OR PROPERLY INCIDENTAL TO THE COMPLETION OF ALL PAINTING OF SURFACES COMPLETE, INCLUDING PAINTING OF THE FOLLOWING SURFACES:
1.1.1 MISCELLANEOUS METAL, DOWNSPOUTS, COLUMNS, POSTS, ISLAND FORMS, VENT RISERS, MANHOLE COVERS AND ELECTRICAL CONDUITS.
1.2 PAINTING DOES NOT INCLUDE:
1.2.1 PAINTING CANOPY SOFFITS.
1.2.2 PAINTING LIGHT FIXTURES.
1.2.3 PAINTING FUEL EQUIPMENT.
1.3 COLOR SCHEDULE: COLOR OF PAINTS SHALL BE AS LISTED IN THE 7-ELEVEN STORE STANDARDS MANUAL.

SECTION VIII CONTINUED

PART 2 - PRODUCTS

- 2.1 PAINT MANUFACTURERS AND PRODUCTS: PAINTING SYSTEM AS SPECIFIED WITHIN THE 7-ELEVEN STORE STANDARDS MANUAL.
2.2 PAINTING COATS AND PRODUCTS: SUPPLIED BY CONTRACTOR
2.2.1 PAINT ALL MANHOLES COVERS AND 4" SURROUNDING CONCRETE, INSIDE AND OUT, IN ACCORDANCE WITH STANDARD INDUSTRY COLOR CODE AS SHOWN.
API COLOR CODES:
OBSERVATION WELL PROVIDED BY MANUFACTURER
UNLEADED REGULAR WHITE W/BLACK CROSS
UNLEADED PREMIUM RED W/WHITE CROSS
UNLEADED REGULAR W/EXTENDER WHITE W/BLACK CROSS & BLACK BAND
UNLEADED PREMIUM W/EXTENDER WHITE W/WHITE CROSS & WHITE BAND
DIESEL SMOKE YELLOW
VAPOR RECOVERY SOL. ORAN.
KEROSENE SOL. BROWN
INTERSTITIAL BLACK
2.2.2 PAINT FASCIA SIGN FRAMES. PAINT GLOSSY WHITE - 2 COATS.

PART 3 - EXECUTION

- 3.1 PREPARE SURFACES TO BE PAINTED: NO PAINT OR SOLVENT SHALL BE ALLOWED TO COME IN CONTACT WITH CONCRETE SURFACE WHERE IT BECOMES NECESSARY, IN ORDER TO EXECUTE HIS OWN WORK, FOR PAINTER TO REMOVE COVERS, PLATES, ETC., PLACED BY OTHER CONTRACTORS IN ANY BRANCH OF THE WORK. HE SHALL REPLACE SAME IN PROPER POSITION. IN SITUATIONS WHERE SAID COVERINGS, PLATES, ETC., CANNOT BE READILY REMOVED, PAINTER SHALL PROTECT THE WORK IN SOME OTHER SATISFACTORY MANNER. OILY RAGS AND WASTE MUST BE REMOVED EVERY NIGHT. UNDER NO CIRCUMSTANCES SHALL THEY BE ALLOWED TO ACCUMULATE. PAINTING SUBCONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE DONE TO THE WORK OF OTHER SUBCONTRACTORS AND SHALL REPAIR OR REPLACE AS NECESSARY TO THE SATISFACTION OF THE OWNER.
3.2 PREPARE SURFACES TO BE PAINTED: INSPECT ALL SURFACES TO BE PAINTED. REPORT ANY DISCREPANCIES TO THE CONTRACTOR PRIOR TO START OF WORK. STARTING OF PAINT APPLICATION SHALL CONSTITUTE ACCEPTANCE OF SURFACES AS SUITABLE FOR THE RECEPTION OF PAINT APPLICATION. ALL SURFACES SHALL BE CLEAN AND DRY, BETWEEN 50 AND 90 DEGREES FAHRENHEIT AT TIME OF PAINT APPLICATION. CLEAN METAL OF MILL SCALE, RUST, OIL, GREASE AND FOREIGN MATTER. CLEAN GALVANIZED METAL ACCORDING TO SSPC-SP 1-63 SOLVENT CLEANING. PROTECT ADJACENT AND FINISHED WORK FROM PAINT.
3.3 APPLICATION OF PAINT: DO NOT THIN, ADULTERATE OR CHANGE MATERIALS EXCEPT AS RECOMMENDED BY MANUFACTURER. EMPLOY ONLY SKILLED MECHANICS FOR WORK. ALL PAINTING SHALL BE BRUSHED, SPRAYED OR ROLLED EVENLY FOR THOROUGH COATS WITHOUT RUNS, SAGS OR OTHER BLEMISHES. ALLOW EACH COAT TO DRY BEFORE APPLYING SUBSEQUENT COATS. ALL SURFACES TO RECEIVE A MINIMUM OF 2 COATS AS NECESSARY TO ACHIEVE AN APPROVED FINISH. APPLICATION OF PAINT, ETC., SHALL BE IN STRICT COMPLIANCE WITH MANUFACTURER'S DIRECTIONS.
3.4 CLEANUP: CLEAN UP ALL DEBRIS CAUSED BY THE WORK OF THIS SECTION, KEEPING THE PREMISES CLEAN AND NEAT AT ALL TIMES.

SECTION IX CANOPIES

PART 1 - GENERAL

- 1.1 SCOPE: THIS SECTION COVERS THE FURNISHING AND INSTALLATION OF ALL ITEMS FOR THE INSTALLATION OF A COMPLETE GASOLINE CANOPY INCLUDING:
1.1.1 COMPLETE FABRICATION DRAWINGS INCLUDING FOOTINGS DESIGN.
1.1.2 COMPLETE ABOVE GROUND STRUCTURAL SUPPORT SYSTEM.
1.1.3 STEEL ROOF DECK AND GUTTER, 20 GA WHITE EMBOSSED.
1.1.4 ROOF BRACING.
1.1.5 CAP FLASHING.
1.1.6 DOWN SPOUTS - INTERNAL INSIDE COLUMNS.
1.1.7 PERMITS AND INSPECTIONS DONE BY OTHERS.
1.1.8 INSTALLATION AND FRAMING FOR OWNER SUPPLIED FASCIA SIGNS (ELECTRICAL BY OTHERS).
1.1.9 INSTALLATION AND FRAMING FOR FASCIA MATERIAL AS PER OWNER SPECIFICATIONS.

PART 2 - PRODUCTS

- 2.1 EMBOSSED ROOF STEEL DECK: ROOF STEEL DECK SHALL BE 2 1/4" MINIMUM DEEP, 20 GAUGE HIGH REFLECTIVE WHITE STEEL WITH MINIMUM SECTION MODULES OF 0.25 IN 1/4 3 MOMENT OF INERTIA OF 0.030 IN 1/4 4. IN CERTAIN AREAS, ROOF DECK WILL BE ALUMINUM. VERIFY WITH LOCAL CONSTRUCTION MANAGER.
2.2 STRUCTURAL STEEL:
2.2.1 ALL STRUCTURAL STEEL TO BE A.S.T.M. A-36 AND SHALL COMPLY WITH THE STANDARD SPECIFICATIONS FOR STRUCTURAL STEEL FOR BUILDINGS OF A.I.S.C. AND WITH THE A.I.S.C. CODE OF STANDARD PRACTICE (LATEST EDITION).
2.2.2 STRUCTURAL BOLTS SHALL CONFORM TO THE STANDARD SPECIFICATION A.S.T.M. A-307 AND SHALL BE PROVIDED WITH WASHERS UNDER THE NUTS.
2.2.3 ALL OTHER BOLTS SHALL BE A-307 AND SHALL CONFORM TO A.S.T.M. STANDARDS, WITH WASHER REQUIRED.
2.2.4 ALL HIGH STRENGTH BOLTS SHALL BE TORQUED TO PROVIDE A MINIMUM TENSION IN BOLT OF 90% OF MINIMUM PROOF LOAD OF THE BOLT.
2.2.5 TUBE COLUMNS SHALL COMPLY WITH A-500, GRADE B.
2.2.6 ALL TUBE COLUMNS SHALL BE 46 KSI STEEL. 2.2.7 ALL WELDING SHALL BE WITH E70XX ELECTRODES AND BE ACCOMPLISHED BY CERTIFIED WELDERS.

PRINTED BY: CSUBLE DRAWING NAME: 3027 - 6160 FUELING SPECIFICATIONS.DWG PRINT DATE: Dec 19, 2017 - 12:07pm

Order Plans @ 7-Eleven.com

7-ELEVEN, INC. 3200 HACKBERRY ROAD, IRVING TEXAS 75063 7-ELEVEN #38227 SMC W CARROLL ST & DYER BLVD KISSIMMEE, FL 34741 FUELING SPECIFICATIONS
Job#: SEI-20880.521 Scale: AS NOTED Date: 12/19/17 Drawn By: RMK Checked By: KMS
SHEET: G16.0 FUELING - USA