RESPONSIBILITY MATRIX PB/GC

	POTTERYBARN PB VENDOR		GENERAL CONTRACTOR		
	FURNISH	INSTALL	FURNISH	INSTALL	REMARKS
GENERAL					
LOCK KEYS AND NEW STORE CORES	●			●	BEST CORES; PERMANENT CORES INSTALLED AT TURNOVER – SEE DOOR SCHEDULE CONSTRUCTION CORES BY GC
HVAC TESTING AND BALANCING/REPORT	●	●			GC TO F&I, IF NEEDED FOR INSPECTION
INTERIOR/SALES					
CASEWORK/STORE FIXTURES	●	●			INSTALL BY FIXTURE INSTALLER
CASHWRAP/BACKWRAP	●	●			INSTALL BY FIXTURE INSTALLER
DESIGN CONSULT TABLE	●	●			INSTALL BY FIXTURE INSTALLER
LOOSE FIXTURES/ACCESSORIES	●	●			FIXTURE INSTALLER TO RECEIVE, UNWRAP, INVENTORY & ASSEMBLE
CHAIRS @ DESIGN CONSULTATION	●	●			
WATERFALL SHELVES AND SUPPORT SYSTEM	●	●			INSTALL BY FIXTURE INSTALLER
STONE COUNTERS	●	●			
PAINTED WOOD BASE			●	●	
WOOD FLOORING	●			●	3/4" PLYWOOD SUBFLOOR BY GC
ANTI FATIGUE MAT AT CASH WRAP	●			●	
FIRE EXTINGUISHERS			●	●	
WOOD CLADDING FOR B-LINE	●	●			INSTALL BY FIXTURE INSTALLER
CORNER GUARDS (SALES FLOOR)	●			●	
BACK OF HOUSE					
BULK AND STOCK SHELVING	●	●		●	RACKS & SHELVING PROVIDED AND INSTALLED BY PB VENDOR -DEFERRED PERMIT & SIGN OFF BY GC -GC TO PROVIDE 2 DAYS LABOR @ FIRST 2 DAYS & @ TURNOVER
TRILOGY LOCKS			●	●	
EMPLOYEE BREAK COUNTER/TABLE/SHELVING/HARDWARE	●	●			BLOCKING/BACKING INSTALL BY GC
S&R DESK/GIFT WRAP TABLE/SHELVING/HARDWARE	●	●			BLOCKING/BACKING INSTALL BY GC
EMPLOYEE LOCKERS (SIX TIER)	●	●			BLOCKING/BACKING BY GC
REFRIGERATOR	●			●	
MICROWAVE	●			●	
COAT RACK AND HOOKS	●			●	BLOCKING BY GC
MOP SHELF	●	●			BY FIXTURE INSTALLER
CORNER GUARDS (STOCKROOM)			●	●	
MANAGER'S COUNTER/SHELVING/HARDWARE	●	●			CONDUIT & PULL STRINGS BY GC
SAFE	●			●	GC TO BOLT TO FLOOR AS REQUIRED
TOILET ROOMS					
LAVATORY	●			●	
FAUCET			●	●	
ADA SIGNAGE	●	●			SEE SIGN PACKAGE
TOILET ACCESSORIES			●	●	
TILE FLOORING/TILE WAINSCOT AND COVE			●	●	
LIGHT FIXTURES	●			●	
MIRROR	●			●	
ELECTRICAL/LOW VOLTAGE					
PLUG MOLD FOR "LIGHTING GALLERY" BAYS	●	●			
TRACK LIGHT FOR "LIGHTING GALLERY" BAYS	●			●	GC TO INSTALL TRACK LIGHT RUNS – (3) RUNS TOTAL LENGTH OF LIGHTING GALLERY FIXTURE. INSTALL AFTER FIXTURE INSTALL. COORDINATE COMPONENTS AND INSTALL WITH FIXTURE VENDOR DRAWINGS
SECURITY SYSTEM	●	●			CONDUIT/PRE-WIRE BY GC/OUTLET BY GC
SECURITY PHONE JACK	●	●			CONDUIT/PULL WIRE BY GC
PHONE EQUIPMENT AND WIRING	●	●			
STEREO SYSTEM: SPEAKERS AND CABINET	●			●	SEE ELECTRICAL
STEREO SYSTEM: RACK AND SUPPORTS COMPONENTS	●	●			
LIGHTING CONTROLS	●			●	SHIPS WITH LIGHT PACKAGE
CURRENT LIMITER PANEL	●			●	
LIGHT FIXTURES AND LAMPS	●			●	
FINAL CONNECTION ON EXTERIOR SIGNS			●	●	
POS CONDUITS/PULL STRINGS			●	●	
POS EQUIPMENT SETUP AND WIRING	●	●			CONDUIT/PRE-WIRE BY GC
TRACK LIGHT	●			●	GC TO INSTALL TRACK LIGHT RUNS
DECORATIVE PENDANTS	●			●	CONDUIT/PRE-WIRE BY GC GC TO PROVIDE (15) ADDITIONAL PIECES OF UNISTRUT IN 10' LENGTHS. INSTALL UNISTRUT ON B-LINE AND MOUNT APPROXIMATELY (15) PENDANTS AT TURNOVER. LOCATIONS TBD BY WSI.
WIRELESS ACCESS POINTS	●	●			CONDUIT/PRE-WIRE BY GC
"SHOPPER TRAK" SYSTEM	●	●			CONDUIT/PRE-WIRE BY GC
LIGHTING (B-LINE)				●	THREADED ROD SUPPORTS BY GC
SIGNS AND GRAPHICS					
STOREFRONT SIGNAGE: INCLUDES WINDOW & STOREFRONT & BLADE SIGNS	●	●			GC TO PROVIDE BLOCKING AS REQUIRED, GC TO INSTALL CONDUIT & CONNECTION VENDOR TO PROVIDE & INSTALL SIGNS
[illegible]	※	※			
TEMPORARY WINDOW GRAPHICS	●	●			
VINYL LETTERS AND STORE HOURS GRAPHICS	●	●			
INTERIOR SIGNAGE/TEMP GRAPHICS	●	●			
STRUCTURAL			●	●	
ELECTRICAL			●	●	ALL FINAL ELECTRICAL CONNECTIONS BY GC.
HVAC			●	●	
PLUMBING			●	●	

RESPONSIBILITY MATRIX WS/GC

	WILLIAMS SONOMA WS VENDOR		GENERAL CONTRACTOR		
	FURNISH	INSTALL	FURNISH	INSTALL	REMARKS
GENERAL					
LOCK KEYS AND NEW STORE CORES	●			●	BEST CORES; PERMANENT CORES INSTALLED AT TURNOVER – SEE DOOR SCHEDULE CONSTRUCTION CORES BY GC
HVAC TESTING AND BALANCING/REPORT	●	●			GC TO F&I, IF NEEDED FOR INSPECTION
INTERIOR/SALES					
CASEWORK/STORE FIXTURES	●	●			BY FIXTURE INSTALLER
CASHWRAP/BACKWRAP	●	●			BY FIXTURE INSTALLER
LOOSE FIXTURES/ACCESSORIES	●	●			FIXTURE INSTALLER TO RECEIVE, UNWRAP, INVENTORY & ASSEMBLE
FIXTURE COUNTERTOPS AT COFFEE/ELECTRICS, CUTLERY, DEMO ISLAND AND CASHWRAP	●	●			
CHAIRS AT DEMO ISLAND	●	●			
PAINTED WOOD BASE			●	●	
NAIL DOWN WOOD FLOORING	●			●	GC TO SUPPLY SUBSTRATE AND ATTACHMENT PER SPEC
TILE FLOORING AT SALES AREA	●			●	
ANTI FATIGUE MAT AT CASH WRAP	●			●	
FIRE EXTINGUISHERS			●	●	
COVED SHEET METAL BASE	●	●			BY FIXTURE INSTALLER
CORNER GUARDS (SALES FLOOR)	●			●	
BACK OF HOUSE					
BULK AND STOCK SHELVING	●	●		●	RACKS & SHELVING PROVIDED AND INSTALLED BY WS VENDOR; GC TO SET ALL SHELVES @ RIVETEERS ONLY -DEFERRED PERMIT & SIGN OFF BY GC -GC TO PROVIDE 2 DAYS LABOR @ FIRST 2 DAYS @ TURNOVER
TRILOGY LOCKS			●	●	
EMPLOYEE BREAK COUNTER/TABLE/SHELVING/HARDWARE	●	●			BLOCKING/BACKING INSTALL BY GC
S&R DESK/GIFT WRAP TABLE/SHELVING/HARDWARE	●	●			BLOCKING/BACKING INSTALL BY GC
EMPLOYEE LOCKERS (SIX TIER)	●	●			BLOCKING/BACKING BY GC
REFRIGERATOR	●			●	
MICROWAVE	●			●	
COAT RACK AND HOOKS	●			●	BLOCKING BY GC
MOP SHELF	●	●			BY FIXTURE INSTALLER
CORNER GUARDS (STOCKROOM)			●	●	
MANAGER'S COUNTER/SHELVING/HARDWARE	●	●			CONDUIT & PULL STRINGS BY GC
SAFE	●			●	GC TO BOLT TO FLOOR AS REQUIRED
ICE MAKER	●			●	
REFRIGERATOR (SCULLERY)	●			●	
SCULLERY SHELVES	●			●	
PLUMBING					
DEMO ISLAND / COFFEE & ELECTRICS			●	●	
SCULLERY FAUCETS + SINKS			●	●	
ELECTRICAL/LOW VOLTAGE					
[illegible]	※	※			[illegible]
SECURITY SYSTEM	●	●			CONDUIT/PRE-WIRE BY GC/OUTLET BY GC
SECURITY PHONE JACK	●	●			CONDUIT/PULL WIRE BY GC
PHONE EQUIPMENT AND WIRING	●	●			
STEREO SYSTEM: SPEAKERS AND CABINET	●			●	SEE ELECTRICAL
STEREO SYSTEM: RACK AND SUPPORTS COMPONENTS	●	●			
LIGHTING CONTROLS	●			●	SHIPS WITH LIGHT PACKAGE
CURRENT LIMITER PANEL	●			●	
LIGHT FIXTURES AND LAMPS	●			●	
FINAL CONNECTION ON EXTERIOR SIGNS			●	●	
POS CONDUITS/PULL STRINGS			●	●	
POS EQUIPMENT SETUP AND WIRING	●	●			CONDUIT/PRE-WIRE BY GC
TRACK LIGHT	●			●	GC TO INSTALL TRACK LIGHT RUNS
DECORATIVE PENDANTS	●			●	CONDUIT/PRE-WIRE BY GC GC TO PROVIDE (15) ADDITIONAL PIECES OF UNISTRUT IN 10' LENGTHS. INSTALL UNISTRUT ON B-LINE AND MOUNT APPROXIMATELY (15) PENDANTS AT TURNOVER. LOCATIONS TBD BY WSI.
WIRELESS ACCESS POINTS	●	●			CONDUIT/PRE-WIRE BY GC
"SHOPPER TRAK" SYSTEM	●	●			CONDUIT/PRE-WIRE BY GC
LIGHTING (B-LINE)			●	●	THREADED ROD SUPPORTS BY GC
SIGNS AND GRAPHICS					
STOREFRONT SIGNAGE: INCLUDES WINDOW & STOREFRONT & BLADE SIGNS	●	●			GC TO PROVIDE BLOCKING AS REQUIRED, GC TO INSTALL CONDUIT & CONNECTION VENDOR TO PROVIDE & INSTALL SIGNS
[illegible]	※	※			
TEMPORARY WINDOW GRAPHICS	●	●			
VINYL LETTERS AND STORE HOURS GRAPHICS	●	●			
INTERIOR SIGNAGE/TEMP GRAPHICS	●	●			
STRUCTURAL			●	●	
ELECTRICAL			●	●	
HVAC			●	●	
PLUMBING			●	●	

PB & WS NOTES

**ALL FINAL ELECTRICAL CONNECTIONS BY GC

GC IS REQUIRED TO USE WSI PREFERRED VENDORS

ALL OTHER ITEMS TO BE FURNISHED BY GC

PLAN SYMBOLS

FIRE-RATED WALLS OR PARTITIONS

(NON-RATED)

(1 HOUR ASSEMBLY)

(2 HOUR ASSEMBLY)

(3 HOUR ASSEMBLY)

EXISTING CONSTRUCTION

CONSTRUCTION TO BE DEMOLISHED

DISPLAY FIXTURES BY CASEWORK CONTRACTOR

PB DISPLAY BAYS

B — WS DISPLAY BAYS

STOCK SHELVING BY SHELVING CONTRACTOR

24x48x96 — STOCK SHELVING

13X8X12 — BULK STOCK

VARIOUS SYMBOLS

(E) STRUCTURAL

CORNER GUARD BACK-OF-HOUSE

FOR SALES AREA LOCATIONS, SEE E3 A-803

RAISED PLATFORM AREA

FOR BACK OF HOUSE LOCATIONS, SEE E5 A-803

COAT RACK WITH FRT BACKING

FD — FLOOR DRAIN

FCO — FLOOR CLEAN OUT

J — J BOX

WALL RECEPTACLE

RECESSED DUPLEX FLOOR OUTLET

F — FIRE EXTINGUISHER– INSTALL TOP OF EXTINGUISHER 5'-0" AFF

REFLECTED CEILING PLAN SYMBOLS

FLUORESCENT LIGHT FIXTURE – SURFACE MOUNTED

4' FLUORESCENT STRIP LIGHT

8' FLUORESCENT STRIP LIGHT

STRUT SYSTEM WITH BLANK ON BOTTOM

STRUT SYSTEM WITH LIGHT TRACK ON BOTTOM

TRACK LIGHT HEADS – SEE REFLECTED CEILING PLAN

RECESSED 3-LAMP RECTANGULAR LUMINAIRE

RECESSED DOWNLIGHT

PENDANT LIGHT FIXTURE

LARGE DECORATIVE PENDANT

SMALL DECORATIVE PENDANT

SCONCE – STOREFRONT – 42"

WAP — WIRELESS ACCESS POINT

CEILING-MOUNTED SECURITY CAMERA

EMERGENCY EGRESS LIGHTING WITH BATTERY BACKUP

RECESSED LIGHT FIXTURE

SW — SUB WOOFER

C — Co2 SENSOR

T — THERMOSTAT

PB SPEAKER, COORDINATE WITH SOUND SYSTEM CONTRACTOR

SP — WS SPEAKER, COORDINATE WITH SOUND SYSTEM CONTRACTOR

CEILING RECEPTACLE

CONCEALED CEILING EMERGENCY LIGHT

EXIT SIGN

FIRE SPRINKLER HEAD, SEE FIRE PROTECTION DRAWINGS AND REFLECTED CEILING PLAN (WHITE RECESSED HEAD)

FIRE SPRINKLER HEAD, SEE FIRE PROTECTION DRAWINGS AND REFLECTED CEILING PLAN (UPRIGHT HEAD)

GYPSUM BOARD CEILING

WOOD PLANK CEILING

RETURN AIR REGISTER

CEILING SUPPLY AIR DIFFUSER

RETURN AIR DIFFUSER

VERTICAL SUPPLY AIR DIFFUSER

ACCESS PANEL,

SYMBOLS

SYMBOL AND DESCRIPTION

BUILDING SECTION INDICATOR (XX / A-XXX)

WALL SECTION INDICATOR (XX / A-XXX)

SMALL CONDITION DETAIL INDICATOR (XX / X-XXX)

MATCHLINE INDICATOR (MATCH LINE XX/A-XXX)

DATUM INDICATOR

KEYNOTE (X.X)

CIRCULAR DETAIL INDICATOR (XX / A-XXX)

SECTION DETAIL INDICATOR (XX / A-XXX)

REVISION INDICATOR (X)

DOOR NUMBER (XXXX)

FINISH INDICATOR (F XXXX)

RECTANGULAR DETAIL INDICATOR (XX / A-XXX)

EXTERIOR ELEVATION INDICATOR (XX / X-XXX)

INTERIOR ELEVATION INDICATOR (XX / X-XXX) OR (XX / A-XXX)

COLUMN GRID INDICATOR AND GRID LINES (X.X)

WALL/PARTITION TYPE INDICATOR (XX XX)

SPOT ELEVATION (EL X'-XX")

PLAN SYMBOLS

ACOUS ACOUSTICAL	FIN FINISH, FINISHED	PBD PARTICLEBOARD
ACT ACOUSTICAL CEILING TILE	FLASH FLASHING	PC PRECAST
AD AREA DRAIN	FLEX FLEXIBLE	PERP PERPENDICULAR
ADJ ADJUSTABLE	FLR FLOOR	PLAM PLASTIC LAMINATE
AFF ABOVE FINISHED FLOOR	FLUOR FLUORESCENT	PLAS PLASTER
AGGR AGGREGATE	FO FACE OF, FINISHED OPENING	PLYWD PLYWOOD
ALT ALTERNATE	FOIC FURNISHED BY OWNER/ INSTALLED BY CONTRACTOR	PNL PANEL
ALUM ALUMINUM	FP FIRE PROTECTION	PL PROPERTY LINE
APPROX APPROXIMATE	FR FRAME, FIRE RATED	PR PAIR
ARCH ARCHITECT, ARCHITECTURAL	FRPF FIREPROOF, FIREPROOFING	PROP PROPERTY
ASB ASBESTOS	FRT FIRE RETARDANT TREATED	PT PAINT, POINT, PRESSURE TREATED
AUTO AUTOMATIC	FS FLOOR SINK	PTD PAPER TOWEL DISPENSER
AV AUDIO VISUAL	FT FOOT, FEET	PTN PARTITION
	FTG FOOTING	PTR PAPER TOWEL RECEPTACLE
BB BULLETIN BOARD	FURR FURRING	
BD BOARD	FUT FUTURE	QT QUARRY TILE
BITUM BITUMINOUS		
BLDG BUILDING	GA GAUGE	RCP REFLECTED CEILING PLAN
BLKG BLOCKING	GALV GALVANIZED	RD ROOF DRAIN, ROAD
BM BEAM	GB GRAB BAR	REF REFER TO, REFERENCE
BO BOTTOM OF	GEN GENERAL, GENERATOR	REFR REFRIGERATOR
BOT BOTTOM	GFRC GLASS-FIBER REINFORCED	REINF REINFORCED, REINFORCING
BRZ BRONZE	GFRG GLASS-FIBER REINFORCED GYPSUM	REQD REQUIRED
BSMT BASEMENT	GFRP GLASS-FIBER REINFORCED PLASTIC	RESIL RESILIENT
	GL GLASS	REV REVISED, REVISION
CAB CABINET	GND GROUND	RGTR REGISTER
CB CATCH BASIN	GRADE	RM ROOM
CEM CEMENT, CEMENTITIOUS	GYPSUM	RO ROUGH OPENING
CER CERAMIC	GWB GYPSUM WALL BOARD	RWD REDWOOD
CG CORNER GUARD		
CH COAT HOOK	HB HOSE BIBB	S SOUTH
CI CAST IRON	HC HOLLOW CORE	SC SOLID CORE
CIP CAST-IN-PLACE	HDBD HARDBOARD	SCD SEAT COVER DISPENSER
CL CENTERLINE	HDW HARDWARE	SCHED SCHEDULE
CLG CEILING	HDWD HARDWOOD	SCW SOLID CORE WOOD
CLKG CAULKING	HM HOLLOW METAL	SD SOAP DISPENSER
CLOS CLOSET	HORIZ HORIZONTAL	SECT SECTION
CMU CONCRETE MASONRY UNIT	HR HOUR	SGL SINGLE
CN COUNTER	HT HEIGHT	SH SHELF
CO CASH OUT, CASED OPENING	HVAC HEATING, VENTILATING AND AIR CONDITIONING	SHR SHOWER
COL COLUMN		SHT SHEET
COMM COMMUNICATION		SIM SIMILAR
CONC CONCRETE		SND SANITARY NAPKIN DISPENSER
CONN CONNECTION, CONNECT		SNR SANITARY NAPKIN RECEPTACLE
CONSTR CONSTRUCTION		SPEC SPECIFICATION
CONT CONTINUOUS, CONTINUE	ID INSIDE DIAMETER	SPKLR SPRINKLER
CORR CORRIDOR	INCL INCLUDE, INCLUDING	SPKR SPEAKER
CPT CARPET	INFO INFORMATION	SQ SQUARE
CSWK CASEWORK	INSUL INSULATE, INSULATION	SS SERVICE SINK
CT CERAMIC TILE	INT INTERIOR	SST STAINLESS STEEL
CTR CENTER		STA STANDARD
CTSK COUNTERSUNK	JAN JANITOR	STD STATION
	JT JOINT	STL STEEL
DBL DOUBLE		STOR STORAGE
DEMO DEMOLISH, DEMOLITION	KIT KITCHEN	STRUCT STRUCTURAL
DEPT DEPARTMENT		SUSP SUSPENDED
DET DETAIL	LAB LABORATORY	SYM SYMMETRICAL
DF DRINKING FOUNTAIN	LAM LAMINATE, LAMINATED	
DIA DIAMETER	LAV LAVATORY	T TREAD
DIAG DIAGONAL, DIAGRAM	LKR LOCKER	T&G TONGUE AND GROOVE
DIM DIMENSION	LT LIGHT	TB TOWEL BAR
DISP DISPENSER		TEL TELEPHONE
DIV DIVIDE, DIVISION	MATL MATERIAL	TEMP TEMPERATURE, TEMPORARY
DN DOWN	MAX MAXIMUM	TER TERRAZZO
DO DOOR OPENING	MC MEDICINE CABINET	THK THICK, THICKNESS
DR DOOR, DRESSING ROOM	MECH MECHANICAL	TO TOP OF
DS DOWNSPOUT	MED MEDIUM	TPD TOILET PAPER DISPENSER
DWG DRAWING	MEMB MEMBRANE	TV TELEVISION
DWR DRAWER	MEZZ MEZZANINE	TYP TYPICAL
	MGR MANAGER	
E EAST	MGT MANAGEMENT	UGND UNDERGROUND
EA EACH	MFR MANUFACTURE, MANUFACTURE	UNFIN UNFINISHED
EIFS EXTERIOR INSULATION AND FINISH SYSTEM	MIN MINIMUM, MINUTE	UON UNLESS OTHERWISE NOTED
EJ EXPANSION JOINT	MIR MIRROR	UR URINAL
EL ELEVATION	MISC MISCELLANEOUS	
ELEC ELECTRIC, ELECTRICAL	MO MASONRY OPENING	VERT VERTICAL
ELEV ELEVATOR	MS MOP SINK	VEST VESTIBULE
EMER EMERGENCY	MTD MOUNTED	VIF VERIFY IN FIELD
ENCL ENCLOSE, ENCLOSURE	MTL METAL	VNR VENEER
EP ELECTRIC PANEL	MUL MULLION	VWC VINYL WALLCOVERING
EQ EQUAL	N NORTH	
EQUIP EQUIPMENT	NIC NOT IN CONTRACT	W WEST, WIDE
EXP EXPANSION, EXPOSED	NO NUMBER	W/ WITH
EXIST EXISTING	NOM NOMINAL	W/O WITHOUT
EXT EXTERIOR	NTS NOT TO SCALE	WC WATER CLOSET, WALLCOVERING
		WD WOOD
FA FIRE ALARM	OA OVER ALL	WP WEATHERPROOF, WATERPROOF, WATERPROOFING, WORK POINT
FCO FLOOR CLEAN OUT	OBS OBSCURE	WR WATER RESISTANT
FD FLOOR DRAIN	OC ON CENTER	WS WILLIAMS-SONOMA
FDC FIRE DEPARTMENT CONNECTION	OFF OFFICE	WSI WILLIAMS-SONOMA, INC.
FDTN FOUNDATION	OH OVERHEAD	WSCT WAINSCOT
FE FIRE EXTINGUISHER	OD OUTSIDE DIAMETER	WT WEIGHT
FEC FIRE EXTINGUISHER CABINET	OPNG OPENING	
	OPP OPPOSITE	YD YARD
	OTS OPEN TO STRUCTURE ABOVE	

Order Plans @ WWW.CADLine.com

OWNER:
WILLIAMS-SONOMA, INC.
3250 Van Ness Avenue
San Francisco, CA 94109
T 415 616 8602
F 415 439 8164
www.williams-sonomainc.com

CALLISON RTKL™
A DESIGN CONSULTANCY OF ARCADIS
CALLISONRTKL INC.
www.callisonrtkl.com

POTTERY BARN
WILLIAMS-SONOMA
Town Center Virginia Beach
173/177 Central Park Avenue
Virginia Beach, VA 23462

PROJECT #006-151817.00/#006-151412.00

ISSUED / REVISED	DATE
FEASIBILITY SET	08/10/17
PRELIMINARY SET	09/28/17
LL CD SET	11/30/17
PERMIT SET	12/18/17
BID SET	01/04/18

RESPONSIBILITY MATRIX, SYMBOLS & ABBREVIATIONS

A-001

COPYRIGHT © 2017 CALLISON, LLC