

WS SUBMITTAL SCHEDULE

Status <small>drop down menu</small>	Item	Specification	Required Approvals			
			GC	Engineer	Architect	WSI
Physical Samples			Simultaneously send 3 copies to WSI + 1 copy to Architect			
Finishes						
	Wood Flooring	24x24" sample board with finish applied	X	X	X	X
	Focal Tile + Grout	Standard color chart with specified color indicated	X	X	X	X
	Grout Demo Island Floor Tile	Samples of each color and type	X	X	X	X
	Resilient Floor at Scullery	Samples of each color and type	X	X	X	X
	Walk-off Mat	Minimum 6"x6" sample	X	X	X	X
	Wood Base	6" sample painted wood	X	X	X	X
Shop Drawings and Specifications			Email to Architect			
MEP						
	Air Diffusers / Grilles		X	X	X	X
	HVAC Equipment		X	X	X	X
	HVAC Ductwork		X	X	X	X
	HVAC Controls		X	X	X	X
	Plumbing Fixtures		X	X	X	X
	Electrical Switchgear		X	X	X	X
	Light Fixtures		X	X	X	X
	Lighting Contactors		X	X	X	X
	B-Line System	Cut sheets on Materials and Connections	X	X	X	X
	Sprinkler Shop Drawings		X	X	X	X
	Fire Alarm Shop Drawings		X	X	X	X
Metal Fabrications						
	Door Hardware Schedule		X	X		
Miscellaneous						
	Wood Flooring Moisture Test		X	X		
	Countertop Shop Drawings		X	X	X	X
	GC-provided Coffee Bar Equipment		X	X	X	X
	Toilet Room Accessories	Cut sheets for all accessories	X	X	X	X
	Stockroom Shelving	Reviewed by Architect and WSI first then copied to GC when approved	X	X	X	X
	Signage	Reviewed by Architect and WSI first then copied to GC when approved	X	X	X	X
Mockups						
All submittals are to be clearly marked to include the Project Name, General Contractor Name and Subcontractor Information. Samples are to be clearly labelled to reference the material callout from the Finish Schedule or to the applicable specification section.						

WS FINISH AND MATERIALS SCHEDULE

ITEM	CODE	MATERIAL	MANUFACTURER	TYPE	REMARKS
WALL	WS1	PAINT	CREATIVE PAINTS	"SCP INT MAIN WALL" 549-1X, FLAT SHEEN (CUSTOM COLOR)	INTERIOR WALLS, SALES FLOOR, GWB CEILING AT SALES AREA
	WS3	PAINT	CREATIVE PAINTS	"SCP WHITE TRIM" (CUSTOM COLOR)	DOORS, DOOR CASINGS AND INTERIOR TRIM, SEMI-GLOSS
	WSS-ES	PAINT	BENJAMIN MOORE	ATRIUM WHITE, PM-13, IN REGAL EGGSHELL SHEEN	AT MANAGER'S OFFICE, SCULLERY, EMPLOYEE BREAK AREA WALLS + CEILINGS
	WSBC	BARRICADE PAINT	BENJAMIN MOORE	ATRIUM WHITE, ECO, LATEX, SEMI-GLOSS SHEEN, REGAL AQUAVELVET, 319-79	AT BARRICADES ONLY
	WSSR	FIRE TAPE + PRIME	BY GC	FIRE TAPE AND PRIME AT GYP WALLS ONLY, NEW AND EXISTING	STOCK ROOM AND BACK OF HOUSE AREAS ONLY.
FLOOR	WSCPT-1	CARPET	MOHAWK	ACCOUNTABLE II TILE IN 7719 CARBON CHAR	MANAGER'S OFFICE, ASTM E84 FLAME SPREAD 75 OR LESS, ASTM E662 SMOKE DENSITY RATING 450 OR LESS IN TESTING METHOD
	WSCPT-2	ENTRY MAT	IMPACT SPECIALTIES	COCOMAT, NATURAL MODEL EM-300, 3/4" THICK, IN NATURAL	3/4" THICK VINYL-BACKED NATURAL COCOA MAT ON SELF-LEVELING CEMENTITIOUS UNDERLAYMENT. CONTACT: JEN DAVIS 619-481-9588 JDAVIS@IMPACTSPECIALTIES.COM
	FLR-1	WOOD FLOOR	VINTAGE LUMBER	WHITE SOLID OAK, LIGHT RUSTIC 3/4" x 3", 4", 5" AND 6" WIDTHS	3 COATS BONA NATURALE, NO SEALER. GC TO PROVIDE 3/4" SUB-FLOOR AND MATERIALS FOR NAIL DOWN.
	RF-1	RESILIENT FLOOR	GERFLOR	"MIPOLAM SYMBIOZ" IN 6008 CALICO	SHEET PRODUCT TO TURN UP WALL FOR 6" INTEGRAL COVE
CEILING	ACP-1	ACOUSTIC CEILING PANEL	ARMSTRONG	ULTIMA HEALTH ZONE 1935, SQUARE LAY IN, W/ 15/16" PRELUDE SUSPENSION SYSTEM, 2X2 PANEL, COLOR: WHITE, TEXTURE: FINE	AT SCULLERY
	WSC-DF	PAINT	CREATIVE PAINTS	WS DRYFALL 395-1X	ALL SALES AREA OTS CEILINGS
TILE	WST-1	FLOOR TILE	DALTILE	50% FIRST SNOW ALS HONED, 50% BLACK MARQUINA LS HONED, 8"x8"x3/8" TILES INSTALLED ON POINT, WITH 1/16" GROUT JOINT	AT DEMO ISLAND, GREEN. LATICRETE 91 SLATE GRAY SANDED SEALANT/SEALER'S CHOICE GOLD RAPID-DRY
	WST-7	BACKSPLASH/ WALL TILE	DALTILE	3X6 CERAMIC FIELD TILES IN RITTENHOUSE, 0190 ARCTIC WHITE WITH 1/8" GROUT JOINT	GROUT: LATICRETE, BRIGHT WHITE, #44 SANDED, SEALANT: SEALERS CHOICE, GOLD-RAPID DRY BACKSPLASH LOCATIONS AT COFFEE/ELECTRICS FOCAL
BASE	MB-1	METAL BASE	BY FIXTURE VENDOR	4" BRAKE-FORMER BLACKENED STEEL WITH #4 DIRECTIONAL FINISH, NO EXPOSED FABRICATORS, 3/8" RADIUS COVER	BASE AT CASH WRAP & DEMO KITCHEN FIXTURES
	RB-1	RUBBER BASE	BURKE FLOORING	4" RUBBER COVER, BASE IN #701, "BLACK"	SEE DETAIL C9/A-802
	WSWB-1	WOOD BASE	BY GC	3/4" x 4" PAINT GRADE, SOLID WOOD BASE	GC TO PAINT WS3
WAINSCOT	WC-1	FRP WAINSCOT	MARLITE	P-100 WHITE, 4" AFF	WAINSCOT AT MOP SINK UP TO +48" AFF, WAINSCOT AT SCULLERY UP TO 96" AFF
THRESHOLD					
METAL FABRICATIONS					
STONE FABRICATIONS	ST-1	STONE COUNTER	BY VENDOR	3 CM CALACUTTA CLASSIC HONED MARBLE (COUNTERTOP)	SALES FLOOR FIXTURES, LOOSE FIXTURES. PROVIDED BY VENDOR, INSTALL BY GC. GC TO COORDINATE WITH WSI-APPROVED FIXTURE SHOP DRAWINGS. CONTINUOUS VEINING SEAMS TO BE APPROVED BY WSI THROUGH SHOP DRAWINGS.
STOREFRONT FINISH					
STOREFRONT GLAZING					

WS INTERIOR FINISH SCHEDULE

SPACE	FLOOR	BASE	WALL	CEILING	REMARKS
SALES AREA	(F) FLR-1	(F) WSWB-1	(F) WS1	(F) WSC-DF	(F) WSC-DF AT EXPOSED PIPING. DO NOT PAINT ALUMINUM DUCTWORK. ALL B-LINE AT SALES FLOOR TO REMAIN FACTORY FINISH. NO PAINT.
COFFEE & ELECTRICS	(F) FLR-1	(F) MB-1	(F) WS1 (F) WST-7	(F) WS1	(F) WST-7 TILE BACKSPLASH AT COFFEE/ELECTRICS FOCAL, SEE INTERIOR ELEVS D7/A-804 ALL B-LINE AT SALES FLOOR TO REMAIN FACTORY FINISH. NO PAINT.
CASHWRAP	(F) WST-1	(F) MB-1	(F) WS1	(F) WS1	ALL B-LINE AT SALES FLOOR TO REMAIN FACTORY FINISH. NO PAINT.
DEMO ISLAND	(F) WST-1	(F) MB-1	--	(F) WS1	ALL B-LINE AT SALES FLOOR TO REMAIN FACTORY FINISH. NO PAINT.
MANAGER'S OFFICE	(F) WSCPT-1	(F) WSRB-1	(F) WSS-ES	(F) WSS-ES	
SHIPPING AND RECEIVING	(F) WSCF-2	(F) WSRB-1	(F) WSSR	--	
SCULLERY	(F) RF-1	(F) RF-1	(F) WC-1	(F) WSS-ES	(F) RF-1 TO WRAP UP WALLS 6" TO PROVIDE INTEGRAL COVERED BASE
STOCKROOM	(F) WSCF-2	(F) WSRB-1	(F) WSSR	--	
EMPLOYEE BREAK AREA	(F) WSCF-2	(F) WSRB-1	(F) WSS-ES	--	(F) WSS-ES UP TO 10'-0" A.F.F. AT BREAK AREA WALLS
ELECTRICAL	(F) WSCF-2	(F) WSRB-1	(F) WSSR	--	

Order Plans @

PAINT CONTACT:
 AT ALL SALES AREA WALLS, SOFFITS, CEILINGS & TOILET ROOMS UNLESS USING SPECIALTY FOCAL COLOR.
 NICK WATERS
 (415) 666-3380
 nickw@mycreativepaint.com

ISSUED / REVISED	DATE
FEASIBILITY SET	08/10/17
PRELIMINARY SET	09/28/17
LL CD SET	11/30/17
PERMIT SET	12/18/17
BID SET	01/04/18

WS FINISH SCHEDULE, FINISH & MATERIAL LEGEND

A-002

OWNER: WILLIAMS-SONOMA, INC.
 3250 Van Ness Avenue
 San Francisco, CA 94109
 T 415 616 8602
 F 415 439 8164
 www.williams-sonoma.com

CALLISONRTKL
 A DESIGN CONSULTANCY OF ARCADIS
 CALLISONRTKL INC.
 www.callisonrtkl.com

POTTERY BARN
 WILLIAMS-SONOMA
 Town Center Virginia Beach
 173/177 Central Park Avenue
 Virginia Beach, VA 23462
 PROJECT #006-151817-00/#006-151412-00