

**GENERAL NOTES**

1. CONTRACTOR TO VERIFY ALL EXISTING CONDITIONS PRIOR TO BID.
2. ALL THERMOSTATS AND SENSORS SHOWN IN APPROXIMATE LOCATIONS. COORDINATE THE EXACT LOCATIONS WITH ARCHITECT.
3. KEEP ALL DUCTWORK AS TIGHT TO STRUCTURE AS POSSIBLE. NOTIFY ARCHITECT IF ANY DISCREPANCIES ARE FOUND.
4. DASHED LINE AROUND HVAC EQUIPMENT REPRESENTS MANUFACTURER'S RECOMMENDED CLEARANCES FOR EQUIPMENT MAINTENANCE. IT IS THE MECHANICAL CONTRACTOR'S RESPONSIBILITY TO MAINTAIN SERVICE CLEARANCES THE FULL HEIGHT OF THE USED IN THIS AREA AND TO PROVIDE ACCESS TO THESE AREAS SUBJECT TO G.C.'S APPROVAL. SHOULD FREE AREA NOT BE AVAILABLE, CONSULT PROJECT MANAGER FOR FURTHER INSTALLATION REQUIREMENTS.

**KEYED NOTES**

REMOVE TEMPERATURE SENSOR PROVIDED BY OWNER WITH LEAD PACKAGE. THE MOUNTING HEIGHT SHALL BE 18" A.F.F. CENTERED ON COLUMN. CONFIRM EXACT LOCATION WITH G.C. PRIOR TO ROUGH-IN. INSTALL CONTROL WIRING IN CONDUIT.

2. INCLUDE IN BID, ADD ALTERNATE FOR USING 45° HARD OVAL WYE BRANCH AND (2) 45° 1.5X RADIUS ELBOWS.

OWNER:  
**WILLIAMS-SONOMA, INC.**  
 3250 Van Ness Avenue  
 San Francisco, CA 94109  
 T 415 616 8602  
 F 415 439 8164  
 www.williams-sonoma.com



EEA Consulting Engineers  
 6615 Vaught Ranch Road, Suite 100  
 Austin, Texas 78730-2314 USA  
 512.744.4400 main 512.744.4444 fax  
 www.eeace.com

State of Registration VIRGINIA  
 Firm Registration No. 0407 004734  
 EEA Project No. 20166524


DRAWN BY: SN  
 CHECKED BY: WKK

**BID DOCUMENT ONLY**

Not Intended for Construction or Permit  
 This document is released under the authority of:

Registrant's Name: MICHAEL N. HART  
 Serial No. 0402-030922

**NOTE:**  
 ALL RIGID ROUND AND FLAT OVAL DUCT SHALL BE SPIRAL WOUND, TYPICAL.



SCALE: 1/4" = 1'-0" @ FULL SIZE

KEYPLAN  
 N.T.S.

**P O T T E R Y B A R R I**  
**WILLIAMS-SONOMA**  
 Town Center Virginia Beach  
 173/177 Central Park Avenue  
 Virginia Beach, VA 23462  
 PROJECT #006-151817-00/#006-151412-00

ISSUED / REVISED	DATE
FEASIBILITY SET	08/10/17
PRELIMINARY SET	09/28/17
LL CD SET	11/30/17
PERMIT SET	12/18/17
BID SET	01/04/18

PARTIAL  
 HVAC PLAN

**M-113**

PARTIAL HVAC PLAN