

OWNER:  
**WILLIAMS-SONOMA, INC.**  
 3250 Van Ness Avenue  
 San Francisco, CA 94109  
 T 415 616 8602  
 F 415 439 8164  
 www.williams-sonoma.com



EEA Consulting Engineers  
 6615 Vaught Ranch Road, Suite 100  
 Austin, Texas 78730-2314 USA  
 512.744.4400 main 512.744.4444 fax  
 www.eeace.com

State of Registration VIRGINIA  
 Firm Registration No. 0407 004734  
 EEA Project No. 20166524

DRAWN BY: SRC  
 CHECKED BY: WKK

**BID DOCUMENT ONLY**

Not Intended for Construction or Permit. This document is released under the authority of:

Registrant's Name: MICHAEL N. HART  
 Serial No. 0402-030922

Order Plans @

WILLIAMS-SONOMA.com

**PLUMBING SCHEDULE**

MARK	OFCI	DESCRIPTION	FIXTURE	CONNECTIONS				NOTES
				WASTE	VENT	CW	HW (MAX F)	
P-1		WATER CLOSET (ADA)	KOHLER HIGHLINE CLASS FIVE MODEL #K-3999 (1.28 GPF) ELONGATED BOWL, COLOR - WHITE. TRIP LEVER ON "OPEN" SIDE. PER ACCESSIBILITY CODE.	4"	2"	3/4"		1,2,6,7
P-2	X (SINK STAND ONLY)	LAVATORY (ADA)	LACAVA S213-001-01 w/ CUSTOM STAINLESS 5460L-21 (CUSTOM OPERATOR STAND FROM JUSTIN BERKOWSKY (773) 637-8600) w/ MAC FAUCETS #400-1100 - OPTIC OIL RUBBED BRONZE FAC 110V ADAPTER, 0.5GPM AERATOR.	1-1/2"	1-1/2"	1/2"	1/2"	2,3,4,5,7,11,14,18 (110°F)
P-3		MOP SINK	FLORESTONE #MS-2424; FLORESTONE #MT-371 FAUCET W/ INTEGRAL CHECK VALVE AND VACUUM BREAKER. GC TO PROVIDE 3/4", 4' GREEN HOSE.	3"	2"	3/4"	3/4"	2,3,8 (110°F)
P-4		DRINKING FOUNTAIN (ADA)	HAWES MODEL #1011MS WITH 1920 BOTTLE FILLER, BP32 BACK PLATE, MTGFR.DF2 MOUNTING FRAME, 6700.4L MOUNTING PLATE, 6.26 WATER FILTER, HOR8 REMOTE CHILLER (115V/60Hz/5.0A). MOUNT PER ADA REQUIREMENTS.	1-1/2"	1-1/2"	1/2"		2,3,4,5,20
P-6		SCULLERY HAND SINK	ADVANCE TABCO 93-63-54-24RL WALL TYPE, STAINLESS STEEL WITH LEVER OPERATED DRAIN (K-26), STAINLESS STEEL BACKPLATE (K-26), FAUCET (K-59) (1.0 GPM).	1-1/2"	1-1/2"	1/2"	1/2"	2,3,4,5,9,10,18 (110°F)
P-7	X (FAUCET ONLY)	DEMO ISLAND HAND SINK	JUST LUNA (COUNTER TYPE, STAINLESS STEEL, UNDER COUNTER TYPE W/ GRID DRAIN.) W/ POTTERY BARN EXTON WIDESPREAD BATHROOM FAUCET-ANTIQUE BRONZE FINISH (1.5 GPM) (FAUCET HOLES CUT IN COUNTER BY G.C.)	1-1/2"	1-1/2"	1/2"	1/2"	2,3,9,17,18 (110°F)
P-8	X (FAUCET ONLY)	COFFEE MAKING SINK	ELKAY ELUH1212PD (COUNTER TYPE, STAINLESS STEEL, UNDER COUNTER TYPE W/ GRID DRAIN.) W/ POTTERY BARN EXTON WIDESPREAD BATHROOM FAUCET-ANTIQUE BRONZE FINISH (1.5 GPM) (FAUCET HOLE CUT IN COUNTER BY G.C.), PROVIDE WITH GREEN TURTLE GT 0060 MICROCEPTOR.	1-1/2"	1-1/2"	1/2"	1/2"	2,3,9,15,17,18 (110°F)
P-9		SOAP SINK	ADVANCE TABCO 93-63-54-24RL SINK, SIDE SPLASH BOTH SIDES (3-COMPARTMENT STAINLESS STEEL, SIDE BOARDS, S.S. LEGS.) W/ CHICAGO FAUCET #445-DJ18E35ABCP (1.5 GPM).	2"		1/2"	1/2"	2,9 (140°F)
P-11		PREP SINK	ADVANCE TABCO 93-61-18-24R SINK, SIDE SPLASH ONE SIDE (1-COMPARTMENT STAINLESS STEEL, 1-SIDE BOARD, S.S. LEGS.) W/ CHICAGO FAUCET #445-L12E35ABCP (1.5 GPM).	1-1/2"		1/2"	1/2"	2,3,9,16 (140°F)
P-12		ICE MAKER	MANITOWOC UD-0190A w/ 3-YR P&L COMM. WARRANTY, 5-YR P&L COMM. WARRANTY ON EVAPORATOR, 5-YR PARTS & 3-YR LABOR COMM. WARRANTY ON COMPRESSOR, (-161) 115V/60/1PH, 5.5A, 6FT. CORD WITH NEMA 5-15P, AR-10000 PRIMARY FILTER, K-00153 FLANGED FOOT. GC TO FURNISH & INSTALL WATTS SERIES 007 BACK FLOW PREVENTER PER CODE.	1/2"		3/8"		14,16
WH-A		WATER HAMMER ARRESTOR	ZURN SHOKTROL					
FD		FLOOR DRAIN	ZURN ZN-415-6S (4" OUTLET, CAST IRON, 6" SQ NIKALOY, FLANGE & MEM. CLAMP). FURNISH WITH TRAP GUARD. EQUALS BY WADE OR J.R. SMITH.	4"				
FS		FLOOR SINK	ZURN ZN-1900 (4" OUTLET, CAST IRON, PORC. ENAM. INTER. NIKALOY HALF GRATE, FLANGE & MEM. CLAMP). FURNISH WITH TRAP GUARD. EQUALS BY WADE OR J.R. SMITH.	4"				
WCO		WALL CLEAN OUT	CAST IRON CLEAN OUT TEE WITH BRONZE THREADED CLEAN OUT PLUG. PLUG TO BE GAS AND WATER TIGHT. WALL ACCESS PANEL - ZURN #2ANB-1460-9, 9" X 9" WALL ACCESS PANEL AND FRAME; SMOOTH NICKEL BRONZE SECURING LUGS. ACCEPTABLE ALTERNATES, WADE OR SMITH.					
DCV		BACKFLOW PREVENTER DOUBLE CHECK VALVE	WATTS LF007			1/2"		
RPZ		BACKFLOW PREVENTER REDUCED PRESS. ZONE ASSY.	WATTS LF919T-S, PROVIDE w/ VENT FUNNEL & 3/4" DRAIN TO INDIRECT WASTE TO MOP SINK TERMINATED WITH AIR GAP 1-1/2" ABV. MOP SINK	3/4"		1/2"		19
WM		WATER METER	WATER METER TO BE PURCHASED FROM LANDLORD'S PREFERRED WATER METER COMPANY. COORDIANTE WITH LL REP.			PER PLAN		

NOTES:

- FURNISH & INSTALL FIXTURE WITH KOHLER K-4650 TOILET SEAT.
- FURNISH & INSTALL STOPS.
- FURNISH & INSTALL "P" TRAP.
- SEE ARCHITECTURAL PLANS FOR INSTALLATION HEIGHT.
- FURNISH & INSTALL HANGERS / CARRIER FOR WALL INSTALLATION.
- PROVIDE WATER CLOSET TRIP LEVER ON THE OPEN SIDE OF WATER CLOSET.
- ALTERNATE MANUFACTURERS - AMERICAN STANDARD OR CRANE
- ALTERNATE MANUFACTURERS - FIAT OR WILLIAMS.
- BUILT TO NSF STANDARD.
- MANUFACTURER'S PHONE NUMBERS: ADVANCED - (800)832-1218 BERLIN FOOD EQ. CO.(GMN)
- INSULATE P-TRAP AND SUPPLY LINES PER ADA. SEE SPECS. FOR ADDITIONAL INFORMATION.
- INSTALLATION BY CONTRACTOR.
- PROVIDE AND INSTALL GREEN TURTLE MICROCEPTOR PER MANUFACTURER'S RECOMMENDATIONS.
- INDIRECT WASTE TO FLOOR SINK.
- FURNISH SINK WITH HAND SOAP DISPENSER, AVOLA B01KBLCOX8 ORB-026. SOAP DISPENSER TO BE INSTALLED IN COUNTER.
- PROVIDE WITH MIXING VALVE, WATTS LFMV-M1. MAXIMUM TEMPERATURE SET POINT SHALL NOT BE GREATER THAN 110°F.
- MOUNT VALVE BRACKETED TO WALL AT 72" A.F.F., LOCATE ABOVE MOP SINK AND COORDINATE WITH G.C.
- INSTALL REMOTE CHILLER, PER MANUFACTURER'S RECOMMENDATIONS, AT LOCATION SHOWN ON PLANS. COORDINATE EXACT LOCATION WITH G.C. AND ARCHITECT.

**ELECTRIC WATER HEATER SCHEDULE**

Tag	TANK SIZE GALLONS	INPUT BTU/H	MANUFACTURER	MODEL	ELECTRICAL			NOTES
					VOLTAGE	PHASE	AMP	
WH-1	6	1500 W	A.O. SMITH	DEL-6	120	1		1,2
WH-2,3	4160 W	10,000 W	CHRONOMITE	SR-20L-208	208	1	20	1
WH-4	50	10,000 W	A.O. SMITH	DEL-50	480	3		1,2

NOTES:

- PROVIDE THE MAKE AND MODEL SPECIFIED OR AN ENGINEER APPROVED EQUAL.
- PROVIDE AND INSTALL WITH EXPANSION TANK, AMTROL THERM-X-TROL MODEL ST. SIZE/INSTALL PER MFR.

**P O T T E R Y B A R R I**  
**WILLIAMS-SONOMA**  
 Town Center Virginia Beach  
 173/177 Central Park Avenue  
 Virginia Beach, VA 23462  
 PROJECT #006-151817-00/#006-151412-00

ISSUED / REVISED	DATE
FEASIBILITY SET	08/10/17
PRELIMINARY SET	09/28/17
LL CD SET	11/30/17
PERMIT SET	12/18/17
BID SET	01/04/18

SCHEDULES  
 PLUMBING

**P-002**