

**LIGHTING CONTROL SYSTEM NOTES:**

**1. SYSTEM OVERVIEW:**

- A. SYSTEM SHALL BE AN LCD GR2400 SERIES PRE-MANUFACTURED LIGHTING CONTROL PANEL, PRE-WIRED AT FACTORY AND FACTORY PRE-PROGRAMMED.
- B. LIGHTING CONTROL PANEL, CONTROL SWITCHES, AND PHOTOCELL SHALL BE FURNISHED BY THE OWNER FOR THE COMPLETE INSTALLATION BY THE ELECTRICAL SUB-CONTRACTOR
- C. ELECTRICAL SUB-CONTRACTOR SHALL PROVIDE THE INSTALLATION, COMMISSIONING, LCD CHECKOUT, DEMONSTRATION, AND TRAINING FOR THE LIGHTING CONTROL SYSTEM.

**2. INSTALLATION AND COORDINATION:**

A. THE ELECTRICAL SUB-CONTRACTOR SHALL PROVIDE A COMPLETE INSTALLATION OF THE LIGHTING CONTROL SYSTEM IN ACCORDANCE WITH THE PLANS AND THE MANUFACTURER'S REQUIREMENTS. THE INSTALLATION SHALL INCLUDE, BUT IS NOT LIMITED TO THE FOLLOWING:

- MOUNT THE LIGHTING CONTROL PANEL(S) AT LOCATIONS INDICATED ON THE PLANS.
- INSTALL THE REMOTE WALL MOUNT CONTROL SWITCH(ES) AT LOCATIONS INDICATED ON THE PLANS
- PROVIDE THE CATEGORY 5e CABLING (IN CONDUIT) FROM THE CONTROL PANEL TO THE REMOTE WALL MOUNT CONTROL SWITCHES. CATEGORY 5e CABLING AND CONDUIT SHALL BE PROVIDED BY THE ELECTRICAL SUB-CONTRACTOR.
- PROVIDE THE OUTLET BOX AND RACEWAY FOR THE INSTALLATION OF THE TELEPHONE LINE AT THE LIGHTING CONTROL PANEL - TELEPHONE CABLE AND JACK SHALL BE INSTALLED BY THE OWNER'S TELEPHONE CABLING VENDOR.
- PROVIDE 120VAC CONNECTION TO POWER THE LIGHTING CONTROL PANEL.
- PROVIDE COMPLETE DEMONSTRATION AND TRAINING FOR SYSTEM OPERATION.
- PROVIDE ALL CONTACT AND COORDINATION WITH LCD FOR REMOTE PROGRAMMING OF THE SYSTEM. CONFIRM THE FINAL PROGRAMMING IS IN ACCORDANCE WITH THE ELECTRICAL RECORD SET OF PLANS.
- PROVIDE TECHNICAL SUPPORT FOR 1 YEAR FROM STORE OPENING. THIS SHALL INCLUDE TROUBLESHOOTING AND REPAIR AND RE-PROGRAMMING.

**3. COMMISSIONING:**

A. THE ELECTRICAL SUB-CONTRACTOR SHALL BE RESPONSIBLE FOR START-UP AND COMMISSIONING OF THE LIGHTING CONTROL SYSTEM AND SHALL COMPLETE THE FOLLOWING COMMISSIONING CHECKLIST:

LIGHTING CONTROL COMMISSIONING CHECKLIST (TO BE PERFORMED BY THE E.C.)	DATE COMPLETE
<input type="checkbox"/> CONTROL PANEL, REMOTE SWITCHES, AND CATEGORY 5e CABLING INSTALLED	
<input type="checkbox"/> 120 VAC POWER PROVIDED AT PANEL	
<input type="checkbox"/> LIGHTING BRANCH CIRCUITS INSTALLED AND TESTED	
<input type="checkbox"/> TELEPHONE LINE INSTALLED AT CONTROL PANEL, CONNECTED TO CONTROL PANEL AND PHONE NUMBER ASSIGNED AND LIVE. COORDINATE WITH WSI FOR PHONE NUMBER.	
<input type="checkbox"/> CONTACT LCD AND PROVIDE THEM WITH THE TELEPHONE NUMBER OF THE LINE TO THE CONTROL PANEL	
<input type="checkbox"/> COORDINATE WITH LCD TO REMOTELY CONFIRM THE CONTROL PANEL IS OPERATING PROPERLY.	
<input type="checkbox"/> HAVE LCD REMOTELY CONTROL EACH LIGHTING ZONE AND CONFIRM THE ASSIGNED LIGHT FIXTURES GROUPS ARE OPERATING PROPERLY. IF NOT, ADJUST THE BRANCH WIRING TO THE CONTROL RELAYS AS REQUIRED FOR PROPER ZONE CONTROL.	
<input type="checkbox"/> ONE WEEK PRIOR TO STORE OPENING, REVISIT STORE TO CONFIRM LIGHTING CONTROL SYSTEM IS OPERATING PROPERLY. HAVE LCD CALLUP CONTROL PANEL AND REMOTELY CONFIRM THE CONTROL AND TIME SCHEDULE FOR EACH ZONE. WITNESS EACH ZONE OPERATION	
<input type="checkbox"/> PROVIDE WRITTEN DOCUMENTATION TO GENERAL CONTRACTOR THAT COMMISSIONING AND CORRECTIVE ACTION IS COMPLETE.	

**4. DEMONSTRATION:**

- A. PRIOR TO TURNOVER, ELECTRICAL SUB-CONTRACTOR SHALL SCHEDULE A TIME WITH THE GENERAL CONTRACTOR AND WSI TO DEMONSTRATE THE LIGHTING CONTROL SYSTEM OPERATION.
- B. ELECTRICAL SUB-CONTRACTOR SHALL DEMONSTRATE THE ENTIRE SYSTEM FOR THE GENERAL CONTRACTOR AND WSI. THIS SHALL INCLUDE CONTACTING LCD TO DEMONSTRATE THE REMOTE OPERATION OF THE LIGHTING ZONES. OBTAIN SIGNATURES CONFIRMING DEMONSTRATION HAS OCCURED:

G.C. SIGNATURE/DATE	_____
WSI SIGNATURE/DATE	_____

**5. TRAINING:**

- A. PRIOR TO STORE OPENING, ELECTRICAL SUB-CONTRACTOR SHALL SCHEDULE A TIME WITH WSI TO PROVIDE TRAINING FOR THE WSI STAFF. PROVIDE A COMPLETE OVERVIEW OF THE LIGHTING CONTROL SYSTEM INCLUDING THE FOLLOWING:
  - LOCATION OF THE CONTROL PANEL, CONTROL SWITCHES, AND PHONE LINE
  - ILLUSTRATE HOW TO MANUALLY CONTROL THE STORE LIGHTING AT THE CONTROL PANEL AND THE REMOTE SWITCHES.
  - INSTRUCT HOW TO CALL LCD AND REMOTELY OPERATE THE LIGHTING ZONES, MODIFY THE LIGHTING ON/OFF CONTROL TIMES, AND HAVE LCD CHECK FOR PROPER SYSTEM OPERATION.

B. OBTAIN WSI SIGNATURE THAT SYSTEM TRAINING IS COMPLETE:

WSI SIGNATURE/DATE	_____
--------------------	-------

**GENERAL NOTES:**

- A. ELECTRICAL CONTRACTOR TO PROVIDE AND TERMINATE ALL LOW VOLTAGE CABLING, SWITCH WIRING AND PHOTO SENSOR WIRE.
- B. ELECTRICAL CONTRACTOR TO CONNECT RELAY PANELS ( IF MULTIPLE PANELS REQUIRED) WITH CAT 5 DATA CABLE IN A DAISY CHAIN, STARTING WITH THE MASTER PANEL THEN TO NEXT NEAREST PANEL AND SO ON.
- C. REFER TO ALL WIRING AND INSTALLATION DETAILS AND DIAGRAM PROVIDED.
- D. BIDDERS CONTACT THE FOLLOWING FOR TECHNICAL ASSISTANCE. INFORMATION: LIGHTING CONTROL AND DESIGN (LCD). PHONE: (800) 345-4448.

LCD TELEPHONE NUMBER FOR REMOTE PROGRAMMING:
(800) 345-4448

OWNER:  
**WILLIAMS-SONOMA, INC.**  
 3250 Van Ness Avenue  
 San Francisco, CA 94109  
 T 415 616 8602  
 F 415 439 8164  
 www.williams-sonomainc.com

**EEA**  
 EEA Consulting Engineers  
 6615 Vaught Ranch Road, Suite 100  
 Austin, Texas 78730-2314 USA  
 512.744.4400 main 512.744.4444 fax  
 www.eeace.com  
 State of Registration VIRGINIA  
 Firm Registration No. 0407 004734  
 EEA Project No. 20166524

DRAWN BY: BMW  
 CHECKED BY: SAH

**BID DOCUMENT ONLY**  
 Not Intended for Construction or Permit  
 This document is released under the authority of:  
 Registrant's Name: SARA A. HAMILL  
 Serial No. 0402052431

**P O T T E R Y B I R D I I**  
**WILLIAMS-SONOMA**  
 Town Center Virginia Beach  
 173/177 Central Park Avenue  
 Virginia Beach, VA 23462  
 PROJECT #006-151817-00/#006-151412-00

ISSUED / REVISED	DATE
FEASIBILITY SET	08/10/17
PRELIMINARY SET	09/28/17
LL CD SET	11/30/17
PERMIT SET	12/18/17
BID SET	01/04/18

LIGHTING CONTROLS  
**E-004**

OrderPlans@www.edonline.com

www.edonline.com