

SYMBOL	MARK	DESCRIPTION
	EX1	WALL MOUNTED EXIT LIGHT PER CODE
	H	2X4 LED FLAT PANEL LIGHTING
	HE	2X4 LED FLAT PANEL LIGHTING WITH EMERGENCY BATTERY PACK
		CEILING-MOUNTED WIRELESS ACCESS POINT (MODEL 205) BY SPRINT VENDOR. RE: KEY NOTE 7
		CEILING-MOUNTED WIRELESS ACCESS POINT (MODEL 225) BY SPRINT VENDOR. RE: KEY NOTE 7
		CEILING-MOUNTED DATA BOX
		OPEN-ENDED DATA CABLE ABOVE CEILING
		CEILING-MOUNTED DUPLEX OUTLET
		JUNCTION BOX ABOVE CEILING

- CONNECT EMERGENCY LIGHTS, EXIT SIGNS, AND NIGHT LIGHTS TO A CONSTANT HOT PHASE CONDUCTOR, DO NOT SWITCH.
- ALL LIGHTS AND OTHER CEILING MOUNTED ITEMS TO BE CENTERED IN GRID UNLESS NOTED OTHERWISE.
- COORDINATE INSTALLATION OF ALL SECURITY CAMERAS AND MONITORING SYSTEMS WITH SPRINT PM

**CEILING PLAN LEGEND R23**

CLG-X ← CEILING TYPE  
 X'-X" ← CEILING HEIGHT ABOVE FINISHED FLOOR


CLG-1 24" x 48" LAY-IN CEILING: STANDARD COMMERCIAL GRADE ACOUSTICAL TILE LAY-IN TILE GRID: STANDARD COMMERCIAL GRADE 15/16" CEILING GRID LOCATION: REFER TO REFLECTED CEILING PLAN FIRE RATING: MEETS PER: ASTM E84, BS476 PARTS 6 & 7, DIN 4102, NFP 92-501 & NFP 92-510 COLOR: WHITE 010

CLG-2 24" x 48" LAY-IN CEILING: ARMSTRONG, SERIES: DUNE 1776, ANGLED TEGULAR, WHITE LAY-IN TILE GRID: ARMSTRONG, SERIES: PRELUDE ML 15/16" EXPOSED TEE, WHITE LOCATION: REFER TO REFLECTED CEILING PLAN FIRE RATING: MEETS PER: ASTM E84, BS476 PARTS 6 & 7, DIN 4102, NFP 92-501 & NFP 92-510

**CEILING FINISH SCHEDULE L23**

- PROVIDE ACCESSIBLE JUNCTION BOX FOR EXTERIOR SIGNAGE. RE: ELECTRICAL
- PROVIDE EMERGENCY EXIT SIGNS AS REQUIRED BY CODE. RE: ELECTRICAL
- PROVIDE OUTLET FLUSH-MOUNTED IN CEILING. OUTLET AND COVER TO BE WHITE
- NIGHT LIGHTS TO REMAIN ON 24/7 - DO NOT SWITCH
- CABLE VENDOR TO PROVIDE PLENUM RATED CAT 5e CABLE LABELED "SHOPPERTRAK" AT LAN RACK END. RUN CABLE ABOVE CEILING FROM DATA RACK TO PLENUM ABOVE FRONT DOOR. TIE OFF ADDITIONAL 15" OF CABLE AT APPROXIMATE "SHOPPERTRAK" LOCATION SHOWN. VERIFY ROUTE AND LOCATION WITH GC. SUPPORT CABLE FROM STRUCTURE USING APPROVED HANGERS - DO NOT LAY ON CEILING TILE.
- CABLE VENDOR TO PROVIDE PLENUM RATED CAT 5e CABLE FOR CONNECTION TO WIRELESS DEVICE. RUN CABLE ABOVE CEILING FROM DATA RACK TO A JUNCTION BOX IN PLENUM AT LOCATIONS SHOWN. VERIFY ROUTE AND LOCATION WITH GC. SUPPORT CABLE FROM STRUCTURE USING APPROVED HANGERS - DO NOT LAY ON CEILING TILE.
- PAINT EXPOSED GYP BOARD SOFFITS/HEADERS P-2.
- START CEILING GRID AT THIS POINT OFF CENTERLINE OF STORE AND/OR EDGE OF EXISTING WALL.
- POWER AND DATA OUTLET IN CEILING FOR NSC DEVICE. RE: ELECTRICAL. CABLE VENDOR TO PROVIDE PLENUM RATED CAT 5e CABLE FOR CONNECTION TO DEVICE. RUN CABLE ABOVE CEILING FROM DATA RACK TO A CEILING MOUNTED JUNCTION BOX WITH BRUSH-STYLE COVER PLATE. VERIFY ROUTE AND LOCATION WITH GC. SUPPORT CABLE FROM STRUCTURE USING APPROVED HANGERS - DO NOT LAY ON CEILING TILE.
- CEILING IS OPEN TO STRUCTURE. NO FINISHES REQUIRED

**CEILING PLAN KEY NOTES A13**



2000 SHAWNEE MISSION PARKWAY  
 STE 100 MISSION WOODS, KS 66205  
 TEL 816 502 1500 FAX 816 842 1878

**Sprint**

#1641 WHITEHAVEN PLAZA  
 4088 ELVIS PRESLEY BLVD.  
 SUITE 104  
 MEMPHIS, TENNESSEE 38116

MATTHEW MASLONS - ARCHITECT  
 TENNESSEE # 102603

I have prepared the drawings and assume responsibility for the sheets numbered with an "A" prefix for the project named below.  
 Other drawings and specifications attached for the above-mentioned project have been by and are the responsibility of the licensed engineer whose stamp and firm appear on that sheet.  
 The architect is not responsible for the design of the mechanical, electrical, plumbing, civil, landscaping, structural, signage (not specified), fire sprinkler or fire suppression systems, and does not take responsibility for the compliance of these areas with the laws of the above governmental entities. The architect is not responsible for materials, components or equipment, as well as the method in which they are installed on the project by others. The architect is not held or responsible for certification, during construction or upon completion of construction. The architect is not responsible for improper operation due to faulty installation or product failure during construction or after completion of construction when operation has begun by the landlord or tenant.  
 The licensed professional whose stamp appears on sheets other than those specifically noted above shall be responsible for those items in paragraph three.

DATE	DESCRIPTION

SHEET TITLE:  
**REFLECTED CEILING PLAN**

PROJECT NUMBER:  
 2017014066  
 SHEET AUTHOR:  
 RM  
 CHECKED BY:  
 RB  
 DATE:  
 JANUARY 5, 2017

SHEET NUMBER:  
**A12**  
 RMTA.BIZ

Order Plans

**REFLECTED CEILING PLAN A01**

