



① PLUMBING PLAN
1/4"=1'-0"

NOTE:
G.C. TO VERIFY EXISTING STUB-INS AND ADJUST BIDS ACCORDINGLY.

PLUMBING FIXTURE SCHEDULE

MARK	FIXTURE	DESCRIPTION	WASH (IN.)	VENT (IN.)	CW (IN.)	HW (IN.)
SS-1	SHAMPOO SINK	SHAMPOO SINK WITH FAUCET AND INTEGRAL VACUUM BREAKER AND ALL ASSOCIATED HARDWARE/ACCESSORIES TO BE SUPPLIED BY OWNER AND INSTALLED BY TENANT'S CONTRACTOR. HAIR INTERCEPTOR - 1 1/2" CATCHER - TRAP BY CARPENTRY MANUFACTURING CORP - SUPPLIED BY TENANT AND INSTALLED BY TENANT'S CONTRACTOR (SUPPLIED BY TENANT AND INSTALLED BY TENANT'S CONTRACTOR)	1-1/2	1-1/2	3/4	3/4
DS-1	DISPENSARY SINK	ACCESSIBLE STAINLESS STEEL SINK IN 18" BAY WITH FAUCET, BY REGIS FIXTURE COMPANY (SUPPLIED BY TENANT AND INSTALLED BY TENANT'S CONTRACTOR)	1-1/2	1-1/2	1/2	1/2

◆ PLUMBING PLAN KEY NOTES

- ◆ CONNECT NEW DISPENSARY TO EXISTING CW, HW & WASTE STUB OUTS AND SHUT-OFF-VALVES BY LANDLORD.
- ◆ CONNECT NEW SHAMPOO SINKS TO EXISTING CW, HW & WASTE STUB OUTS BY LANDLORD.
- ◆ LANDLORD TO PROVIDE WATER AND SANITARY STUB-IN LOCATIONS AT WASHER WITH SHUT-OFF VALVES.
- ◆ EXISTING WALL CLEAN-OUT. G.C TO VERIFY.
- ◆ LANDLORD TO PROVIDE WATER AND SANITARY STUB-IN LOCATIONS AT MCP SINK WITH SHUT-OFF VALVES.

PLUMBING LEGEND

- COLD WATER
- HOT WATER
- - - V - - - VENT PIPE
- ABOVE GROUND SANITARY
- BELOW GROUND SANITARY
- ⊖ FLOOR DRAIN
- ⊖ FLOOR DRAIN WITH FUNNEL
- ⊖ WATER METER

PLUMBING NOTES

1. ALL UNDERGROUND SOIL PIPING TO BE 3" MINIMUM.
2. ALL FLOOR DRAINS AND FLOOR CLEAN-OUTS ARE TO BE FLUSH WITH FLOOR TILE. DO NOT SLOPE FLOOR TO DRAIN.
3. NO EXPOSED PVC OR COPPER PIPING ALLOWED AT SHAMPOO SINKS OR LAVS.
4. WALL CLEANOUTS WITH ROUND STAINLESS STEEL FINISHED COVER PLATES MUST BE FLUSH WITH WALL.
5. ALL NEW PIPING (EXCEPT WASTE) MUST RUN THROUGH WALLS. DO NOT STUB PIPING THROUGH FLOOR OR RUN PIPING THROUGH FIXTURES.
6. ROOF PENETRATIONS TO BE MADE BY LL'S ROOFING CONTRACTOR.
7. ACCESSIBLE STAINLESS STEEL FINISHED SHUTOFF VALVES FOR BOTH HOT AND COLD WATER SUPPLY AT ALL SHAMPOO BOWLS MUST BE INSTALLED ON THE FRONT OF THE SHAMPOO FIXTURE.

12/13/2017

#81973

SUPERCUTS
TENANT BUILD-OUT
LAKESIDE VILLAGE
7582 WINTER GARDEN VINELAND RD
WINDERMERE, FL 34786

PLUMBING PLAN, RISERS AND SCHEDULES

SUPERCUTS

DATE ISSUED
TENANT REVIEW 12.08.17
LANDLORD REVIEW 12.13.17
PERMIT 12.13.17
DRAWN BY DW
CHECKED BY AH
JOB NO. 17-678

P-100

Order Plans @ WWW.LDILine.com