HOOD SCHEDULE

MARK	EXH. CFM	EXH. COLLAR	LENGTH	WIDTH	LOCATION / SERVICE	MODEL (CAPTIVEAIRE)	EPRO#	NOTES
H-3	875	9"x9"	60"	60"	DELI/BAKERY	6024 ND	K-0002299	① ② ③

① HOOD, FANS, AND DUCTS SHALL BE CONSTRUCTED AND INSTALLED IN ACCORDANCE WITH NFPA 96 AND SMACNA GUIDELINES.

② HOODS ARE PROVIDED BY KROGER. CONTRACTOR RESPONSIBLE FOR SCHEDULING, RECEIPT, AND COMPLETE INSTALLATION OF HOODS. ANSUL SYSTEM PROVIDED AND INSTALLED BY KROGER AND GENERAL CONTRACTOR TO COORDINATE.

③ ALL COOKING APPLIANCES VENTED BY TYPE I HOODS TO BE INTERLOCKED SO THAT WHEN THE EXHAUST FAN IS OFF THE COOKING APPLIANCES SHOULD ALSO BE OFF. THE METHOD OF INTERLOCK BETWEEN EXHAUST HOOD AND THE APPLIANCES EQUIPPED WITH STANDING PILOT BURNER IGNITION SYSTEMS SHALL NOT CAUSE SUCH PILOTS TO BE EXTINGUISHED.

FAN SCHEDULE

MARK	CFM	E.S.P. WG	DRIVE	H.P.	TYPE	BASIS OF DESIGN (CAPTIVEAIRE)	EPRO#	LOCATION/SERVICE	AES CURB MODEL#	NOTES
EF-2A	2,250	0.65"	BELT	0.500	CENTRIFUGAL	NCA16FA	K-0002377	EXISTING HOOD 2A	42414	①②
EF-2B	2,100	0.65"	BELT	0.500	CENTRIFUGAL	NCA14FA	K-0002376	EXISTING HOOD 2B	42413	①②
EF-11	875	1.00"	BELT	0.500	CENTRIFUGAL	NCA10FA	K-0002374	NEW HOOD 3	42412	①②

① FANS ARE PROVIDED BY KROGER. CONTRACTOR IS RESPONSIBLE FOR PROVIDING CURBS, SCHEDULING, RECEIPT AND COMPLETE INSTALLATION OF FANS.

② FAN TO BE ON WHEN COOKING EQUIPMENT UNDER THE HOOD IS OPERATING.

AIR DISTRIBUTION SCHEDULE

MARK	TYPE	SIZE IN INCHES		FINISH	O.B.D.	BASIS OF DESIGN (TITUS)	NOTES
		NECK	FACE				
S1	SUPPLY	10"x10"	24"x24"	WHITE	NO	[illegible]	①②③
S2	SUPPLY	8"x8"	16"x16"	④	NO	[illegible]	①②③
R1	EXHAUST	8"x8"	10"x10"	[illegible]	NO	50F	①

① DIFFUSER MOUNTING STYLE SHALL BE CONFIRMED WITH DRAWING AND REFLECTED CEILING PLAN.

② PROVIDE SQUARE TO ROUND TRANSITION WHEN REQUIRED.

③ SEE DRAWINGS FOR DIFFUSER THROW PATTERN. PROVIDE 1 WAY THROW DIFFUSER IF NO DIRECTION ARROWS ARE INDICATED.

④ MATCH FINISH COLOR OF ADJACENT MATERIAL.

Order Plans @ WWW.LDILine.com

ROBERTSON LOIA ROOF
ARCHITECTS & ENGINEERS
3460 Preston Ridge Road , Suite 700 , Alpharetta, Georgia 30005
770-674-[illegible] Fax 770-319-0745

THIS REPRODUCTION IS NOT A CERTIFIED DOCUMENT

Kroger L-407 - Remodel
3101 RICHMOND ROAD
LEXINGTON, KY

FOR:
The Kroger Company
1600 Ormsby Station Court, Louisville, KY 40223

REVISIONS

SHEET TITLE
HVAC SCHEDULES

DATE
01 - 25 - 18

PROJECT NUMBER
17-125

SHEET NUMBER
M6.1