EQUIPMENT SCHEDULE

MARK #		DESCRIPTION	MANUFACTURER	MODEL #	FURNISHED BY	INSTALLED BY
100	1	NITROGEN GENERATOR	PERLICK	7KPH	EQUIPMENT VENDOR	EQUIPMENT VENDOR
100A	1	NITROGEN TANK		BWW SPEC	BWW VENDOR	BWW VENDOR
100B	1	NITROGEN BACKUP CYLINDER		BWW SPEC	BWW VENDOR	BWW VENDOR
100C	1	CO2 BULK TANK WITH CYLINDER		BWW SPEC	BWW VENDOR	BWW VENDOR
100D	1	CO2 BACKUP TANK		BWW SPEC	BWW VENDOR	BWW VENDOR
101SS	1	WALK-IN BEER COOLER	THERMALRITE - IMPERIAL	BWW SPEC	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	CONDENSER	HEATCRAFT	MCH0710X03CBWWF	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	EVAPORATOR	HEATCRAFT	LCE66S6B1B	EQUIPMENT VENDOR	EQUIPMENT VENDOR
102	1	WALK-IN FREEZER	THERMALRITE - IMPERIAL	BWW SPEC	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	CONDENSER	HEATCRAFT	MCH0331L03CBWW	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	EVAPORATOR	HEATCRAFT	LCE612GBCM6CMB-EC	EQUIPMENT VENDOR	EQUIPMENT VENDOR
103	1	WALK-IN MEAT COOLER	THERMALRITE - IMPERIAL	BWW SPEC	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	CONDENSER	HEATCRAFT	MCH0710X03CBWWF	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	EVAPORATOR	HEATCRAFT	LCE67S5BWMC6B-EC	EQUIPMENT VENDOR	EQUIPMENT VENDOR
104	1	WALK-IN PRODUCE COOLER	THERMALRITE - IMPERIAL	BWW SPEC	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	CONDENSER	HEATCRAFT	MCH0710X03CBWWF	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	EVAPORATOR	HEAT CRAFT	LCA6693EWMCBB	EQUIPMENT VENDOR	EQUIPMENT VENDOR
105SS	1	OVERHEAD GLYCOL DELIVERY SYSTEM	PERLICK	4414 WITH DUAL PUMPS	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	BEER POWER RACK SHELF (WALL MOUNTED)	PERLICK	4409SS	EQUIPMENT VENDOR	EQUIPMENT VENDOR
105SC	1	BEER DELIVERY SYSTEM	BWW CUSTOM	BWW SPEC	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	36	TAP FITTINGS	PERLICK		EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	STAINLESS STEEL TAP BOXFACE	BWW CUSTOM		EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	23 x 62.5" S.S. RECESSED DRAIN PAN	BWW CUSTOM	BWW SPEC	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	CO2 BLENDER	MCDANTIN		EQUIPMENT VENDOR	EQUIPMENT VENDOR
106	1	FOUR COMPARTMENT BAR SINK	LACROSSE	SK74CD	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	2	FAUCETS	LACROSSE	3NCLUDED	G.C. PLUMBER	G.C. PLUMBER
106A	1	GLASS RACK STORAGE UNIT	LACROSSE	SK24GR-DB	EQUIPMENT VENDOR	EQUIPMENT VENDOR
106C	1	TUMBLER TABLE	LACROSSE	SK18GR-BWW	EQUIPMENT VENDOR	G.C. PLUMBER
107A	3	HAND SINKS	ADVANCE TABCO	7-BW-23-EC-SP	EQUIPMENT VENDOR	G.C. PLUMBER
-	3	FAUCETS	T & S BRASS	B-1115-B	EQUIPMENT VENDOR	G.C. PLUMBER
-	3	GOOSENECKS	T & S BRASS	TSB132X	EQUIPMENT VENDOR	G.C. PLUMBER
-	3	ADAPTERS	T & S BRASS	TSB344A	EQUIPMENT VENDOR	G.C. PLUMBER
-	3	FAUCET CONTROLS	COMPONENT HARDWARE	K061-0100	EQUIPMENT VENDOR	G.C. PLUMBER
107B	2	DROP IN HAND WASH SINKS	ADVANCE TABCO	DI-1-6-BW	EQUIPMENT VENDOR	G.C. PLUMBER
-	2	FAUCETS	T & S BRASS	B-1110-LN	EQUIPMENT VENDOR	G.C. PLUMBER
-	2	GOOSENECKS	T & S BRASS	TSB132X	EQUIPMENT VENDOR	G.C. PLUMBER
-	2	ADAPTERS	T & S BRASS	TSB344A	EQUIPMENT VENDOR	G.C. PLUMBER
-	2	FAUCET CONTROLS	COMPONENT HARDWARE	K061-0100	EQUIPMENT VENDOR	G.C. PLUMBER
108RB	1	REFRIGERATED BASE - GRILL STAND	SILVER KING	SKRCB60HC1/2	EQUIPMENT VENDOR	EQUIPMENT VENDOR
109ICE	1	LOW WASHER (HIGH TEMP)	HOBART	LXiH	EQUIPMENT VENDOR	EQUIPMENT VENDOR
110A	2	GLASS CHILLERS	PERLICK	BC66LT	EQUIPMENT VENDOR	EQUIPMENT VENDOR
111	2	BAR TABLES	ADVANCE TABCO	KMS-2148-BWC	EQUIPMENT VENDOR	EQUIPMENT VENDOR
111L	2	ICE BINS / BLENDER / DUMP SINK STATION	LACROSSE	SK4-24CD-BWMB	EQUIPMENT VENDOR	EQUIPMENT VENDOR
112R	1	DUMP SINK / HAND WASH SINK STATION	LACROSSE	SK3-H52L	EQUIPMENT VENDOR	EQUIPMENT VENDOR
113S	1	BAR CLASS RACK - 48 x 25	ADVANCE TABCO	GR-BW-48-LR	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	8	GLASS HANGERS	AMERICAN METALCRAFT	WSHGHCR	EQUIPMENT VENDOR	EQUIPMENT VENDOR
114A	4	SPEEDRAILS	LACROSSE	LS90-24GSR	EQUIPMENT VENDOR	EQUIPMENT VENDOR
114B	2	DOUBLE SPEEDRAILS	LACROSSE	LS90-24GSR-2	EQUIPMENT VENDOR	EQUIPMENT VENDOR
114D	2	SPEEDRAILS	LACROSSE	LS90-69GSR	EQUIPMENT VENDOR	EQUIPMENT VENDOR
114F	2	SPEEDRAILS (NOT SHOWN ON PLAN)	LACROSSE	LS90-18GSR	EQUIPMENT VENDOR	EQUIPMENT VENDOR
115	2	BAR BLENDERS	HAMILTON BEACH	TEMPEST HBH850	EQUIPMENT VENDOR	EQUIPMENT VENDOR
117SU	1	PASS THRU GLASS DOOR COOLER	PERLICK	PT1R4	EQUIPMENT VENDOR	EQUIPMENT VENDOR
118	1	EXHAUST HOOD W/ FRONT MAKE UP AIR PLENUM	ACCUTREX PROXIMITY	BWW SPEC	BWW VENDOR	G.C. MECHANICAL
119R	1	GAS FRYERS 4-BANK	PITCO	4-SSH/60C-S/FD	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	2	GAS CONNECTOR KITS	DORMONT	53-S035E-48	EQUIPMENT VENDOR	G.C. PLUMBER
-	1	FRYER BUMPERS	ADVANCE TABCO	BG-BW	EQUIPMENT VENDOR	G.C.
119C	1	FRYER STAND	METRO	BW1424FSRY	EQUIPMENT VENDOR	EQUIPMENT VENDOR
120	1	GAS FRYERS, 3-PAN	PITCO	3-SSH/60C-S/FD	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	GAS CONNECTOR KIT	DORMONT	53-S035-48	EQUIPMENT VENDOR	G.C. PLUMBER
-	1	FRYER BUMPERS	ADVANCE TABCO	BG-BW	EQUIPMENT VENDOR	G.C.
121	1	HOT WELL	APW-WYOTT	CW-3A	EQUIPMENT VENDOR	EQUIPMENT VENDOR
122A	1	COUNTERTOP GRIDDLE	MAGIC KITCHEN	MKG481E	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	GAS CONNECTOR KIT	DORMONT	43-S0356-48	G.C. PLUMBER	G.C. PLUMBER
123OE	2	SERVICE TABLES (6')	ADVANCE TABCO	KMS-3042-SW-R	EQUIPMENT VENDOR	EQUIPMENT VENDOR
123T	1	PASS THROUGH STATION (R) - 186"	ADVANCE TABCO	PA-30186-BW-R	EQUIPMENT VENDOR	EQUIPMENT VENDOR
123S	2	SERVICE TABLES	ADVANCE TABCO	KMS-2772-SW	EQUIPMENT VENDOR	EQUIPMENT VENDOR
123SW	1	EXPO AREA STAINLESS STEEL WRAP	ADVANCE TABCO	WF-1068W	EQUIPMENT VENDOR	EQUIPMENT VENDOR
123T	3	TICKET RAILS	AMERICAN METALCRAFT	TR36	EQUIPMENT VENDOR	EQUIPMENT VENDOR
124TA	1	REFRIGERATED PREP TABLE	SILVER KING	SKF27/2D2/C8-BWW	EQUIPMENT VENDOR	EQUIPMENT VENDOR
125TA	1	REFRIGERATED PREP TABLE	SILVER KING	SKF27/2D2/C8-BWW	EQUIPMENT VENDOR	EQUIPMENT VENDOR
126A	1	FREEZER PREP TABLE - APPETIZER	SILVER KING	SKF27/2D2C10-BWW	EQUIPMENT VENDOR	EQUIPMENT VENDOR
127F	1	UNDERCOUNTER FREEZER W/DRAWERS	SILVER KING	SKF-D2-1-BK1	EQUIPMENT VENDOR	EQUIPMENT VENDOR
127RS	2	UNDERCOUNTER REFRIGERATORS	SILVER KING	SKR27A	EQUIPMENT VENDOR	EQUIPMENT VENDOR
127S	1	DRAIN BIN	LACROSSE	SKP24-BWW	EQUIPMENT VENDOR	EQUIPMENT VENDOR
128	1	REFRIGERATED PREP COUNTER	SILVER KING	SKR27B	EQUIPMENT VENDOR	EQUIPMENT VENDOR
129	3	MICROWAVE OVENS	AMANA	RC22S2	EQUIPMENT VENDOR	EQUIPMENT VENDOR
131A	2	WARMING DRAWERS	HATCO	HDW-1X1	EQUIPMENT VENDOR	EQUIPMENT VENDOR
131S	1	WARMING DRAWER	HATCO	HDW93-00539-BWW	EQUIPMENT VENDOR	EQUIPMENT VENDOR
132	1	FRIED FOOD HOLDING STATION	PITCO	PCC-2S	EQUIPMENT VENDOR	EQUIPMENT VENDOR
133	1	MACHO NACHO	HATCO	FST-1-MN	EQUIPMENT VENDOR	EQUIPMENT VENDOR
134	1	EXHAUST HOOD W/ FRONT MAKE UP AIR PLENUM	ACCUREX	HOOD - BWW SPEC	BWW VENDOR	G.C. MECHANICAL
135	3	BUN PAN RACKS	METRO	RT183N	EQUIPMENT VENDOR	EQUIPMENT VENDOR
136	FT	TRASH RECEPTACLES	RUBBERMAID	354000 GRAY	EQUIPMENT VENDOR	EQUIPMENT VENDOR
137	1	POT AND PAN SINK W/ DRAINBOARDS	ADVANCE TABCO	FC-BWW-3	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	SWING NOZZLE	T & S BRASS	B-WW-0604	EQUIPMENT VENDOR	G.C. PLUMBER
-	1	PRE-RINSE UNIT	T & S BRASS	B-0133-B	EQUIPMENT VENDOR	G.C. PLUMBER
-	1	FAUCET	T & S BRASS	B-0155-LN	EQUIPMENT VENDOR	G.C. PLUMBER
-	3	WASTE VALVE	T & S BRASS	B-3950	EQUIPMENT VENDOR	G.C. PLUMBER
138R	1	PRODUCE PREP SINK W/DRAINBOARD (R)	ADVANCE TABCO	FC-BWW-1-R	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	SWING NOZZLE	T & S BRASS	BWW-0604	EQUIPMENT VENDOR	G.C. PLUMBER
-	1	PRE-RINSE UNIT	T & S BRASS	B-0133-B	EQUIPMENT VENDOR	G.C. PLUMBER
-	1	FAUCET	T & S BRASS	B-0155-LN	EQUIPMENT VENDOR	G.C. PLUMBER
-	1	WASTE VALVE	T & S BRASS	B-3950-XS	EQUIPMENT VENDOR	G.C. PLUMBER
139C	1	PREP TABLE 66"	ADVANCE TABCO	KMS-2466-BW	EQUIPMENT VENDOR	EQUIPMENT VENDOR
140L	1	CARRY OUT HOT HOLDING CABINET - LEFT HINGE	METRO	BWC5382V-LCWL	EQUIPMENT VENDOR	EQUIPMENT VENDOR
141A	2	HEAT LAMPS - 86" DOUBLE	HATCO	GRAH-66DJ	EQUIPMENT VENDOR	EQUIPMENT VENDOR
141B	2	HEAT LAMPS - 86" SINGLE	HATCO	GRAH-66	EQUIPMENT VENDOR	EQUIPMENT VENDOR
143A	1	COFFEE- TEA BREWER	BUNN	ITCB	BWW VENDOR	BWW VENDOR
143AB	2	SHAKE TABLES WITH CANTILEVER SHELVES -102"	ADVANCE TABCO	KMS-305-BW	EQUIPMENT VENDOR	EQUIPMENT VENDOR
143E	1	SHAKE TABLE WITH CANTILEVER SHELVES -32"	ADVANCE TABCO	TKMS-3442-BW	EQUIPMENT VENDOR	EQUIPMENT VENDOR
144	4	SAUCE PUMPS (NOT SHOWN ON PLAN)	SERVER	(2) 80503 (1) 83125 (1) 83126	EQUIPMENT VENDOR	EQUIPMENT VENDOR
152L	2	42" STAINLESS STEEL SHELF WITH WEEP HOLES (L)	ADVANCE TABCO	DT-6R-12-SWL	EQUIPMENT VENDOR	EQUIPMENT VENDOR
152R	2	42" STAINLESS STEEL SHELF WITH WEEP HOLES (R)	ADVANCE TABCO	DT-6R-12-BW-R	EQUIPMENT VENDOR	EQUIPMENT VENDOR
154IBR	1	MICROWAVE SHELF	ADVANCE TABCO	MS-24-42-PBWR	EQUIPMENT VENDOR	EQUIPMENT VENDOR
154OL	1	TOASTER SHELF	ADVANCE TABCO	MS-24-42-TBWL	EQUIPMENT VENDOR	EQUIPMENT VENDOR
155B	4	INVERTED WIRE WALL SHELF - 48"	METRO	BW1848NVSRT	EQUIPMENT VENDOR	EQUIPMENT VENDOR
155C	8	INVERTED WIRE WALL SHELF - 60"	METRO	BW1860NVSRT	EQUIPMENT VENDOR	EQUIPMENT VENDOR
157	5	KEG RACKS	METRO	BWK6GM	EQUIPMENT VENDOR	EQUIPMENT VENDOR
157B	1	BEER COOLER STORAGE 48"	METRO	BW2448S6	EQUIPMENT VENDOR	EQUIPMENT VENDOR
159	1	ICE MACHINE	ICE O MATIC	ICE1806HR	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	PRE CHARGE TUBING KIT	ICE O MATIC	RT340-404	EQUIPMENT VENDOR	EQUIPMENT VENDOR
159A	1	REMOTE CONDENSER	ICE O MATIC	VRC-50618	EQUIPMENT VENDOR	EQUIPMENT VENDOR
159B	1	TRENCH DRAIN			G.C.	
160	1	ICE BIN & CART	FOLLETT	DEV1300SU-48	EQUIPMENT VENDOR	G.C. PLUMBER
161	3	24X36X86 PRODUCE COOLER STORAGE	METRO	8W2436S6PC	EQUIPMENT VENDOR	EQUIPMENT VENDOR
167	2	24X48X74 WIRE COOLER SHELVING UNIT	METRO	BW2474S6R	EQUIPMENT VENDOR	EQUIPMENT VENDOR
174	1	24X36X86 WIRE STORAGE SHELVING UNIT	METRO	BW2436S6R	EQUIPMENT VENDOR	EQUIPMENT VENDOR
174C	1	LOCKABLE CHEMICAL CABINET - 39"	METRO	BWSEC39	EQUIPMENT VENDOR	EQUIPMENT VENDOR
175	2	24X48X86 WIRE STORAGE SHELVING UNIT	METRO	BW2448S6R	EQUIPMENT VENDOR	EQUIPMENT VENDOR
175L	1	LOCKABLE LIQUOR CABINET - 48"	METRO	SEC454C	EQUIPMENT VENDOR	EQUIPMENT VENDOR
180A	2	AIR DRYING UNITS	METRO	BW2436R6CADU	EQUIPMENT VENDOR	EQUIPMENT VENDOR
183	4	PRODUCE COOLER STORAGE	METRO	BW2448S6PCS	EQUIPMENT VENDOR	EQUIPMENT VENDOR
187	2	3 COMP SINK SMART WALL KITS	METRO	8W36-3CDMPSINK	EQUIPMENT VENDOR	EQUIPMENT VENDOR
187A	1	TO GO SMART WALL KIT	METRO	BWTAKEOUT	EQUIPMENT VENDOR	EQUIPMENT VENDOR
188	1	CONVECTION OVEN - GAS	BLODGETT	DFG-50	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	GAS CONNECTOR KIT	DORMONT	43-S0356-48	EQUIPMENT VENDOR	G.C. PLUMBER
188A	1	OVEN STAND	BLODGETT	15150	EQUIPMENT VENDOR	EQUIPMENT VENDOR
190	7	DUNNAGE RACKS 36"	METRO	HP2236PDM8	EQUIPMENT VENDOR	EQUIPMENT VENDOR
190A	3	DUNNAGE RACKS 30"	METRO	HP2230PDM8	EQUIPMENT VENDOR	EQUIPMENT VENDOR
191	2	DUNNAGE RACKS 48"	METRO	HP2248PDM8	EQUIPMENT VENDOR	EQUIPMENT VENDOR
195S	1	PREP SINK SMART WALL KIT - 96"	METRO	BWW1860PREPSINK	EQUIPMENT VENDOR	EQUIPMENT VENDOR
196	1	LABEL HOLDERS (NOT SHOWN ON PLAN)	METRO	BW6999P-180	EQUIPMENT VENDOR	EQUIPMENT VENDOR
197	4	GLASS STORAGE RACKS	VOLLRATH	52712	SMALL WARES VENDOR	EQUIPMENT VENDOR
198	4	GLASS STORAGE RACK DOLLY	VOLLRATH	52717	SMALL WARES VENDOR	EQUIPMENT VENDOR
199	1	DISHMACHINE	HOBART	CUH70-10 2SSN	EQUIPMENT VENDOR	EQUIPMENT VENDOR
199CL	1	SOILED DISHTABLE WITH SCRAPER TROUGH	ADVANCE TABCO	AM18VL-2 (VENTLESS)	EQUIPMENT VENDOR	EQUIPMENT VENDOR
-	1	FAUCET		DTS-S70-604L-BW	EQUIPMENT VENDOR	EQUIPMENT VENDOR
199BR	1	CLEAN DISHTABLE - 82" (R)		B-1116	EQUIPMENT VENDOR	G.C. PLUMBER
375	2	BAG-IN-BOX RACK		DTC-S70-602R-BW	EQUIPMENT VENDOR	EQUIPMENT VENDOR
376	3	CARBONATORS	PEPSI		PEPSI	PEPSI
-	1	SODA DISPENSERS - 6 SHOT	PEPSI		PEPSI	PEPSI
377	1	SODA DISPENSER CABINET	PEPSI		PEPSI	PEPSI
379	6	CO2 LINE	PEPSI		PEPSI	PEPSI
380A	1	WATER FILTER SYSTEM - ICE, COFFEE, TEA	SELECTO SCIENTIFIC	BWW-IM-614	BWW VENDOR	G.C. PLUMBER
380B	1	WATER FILTER SYSTEM - SODA	SELECTO SCIENTIFIC	BWW-IC-614-2	BWW VENDOR	G.C. PLUMBER
380C	2	WATER FILTER SYSTEMS - DISH MACHINES	SELECTO SCIENTIFIC	BWW-IC-620+	BWW VENDOR	G.C. PLUMBER

NOTE:
THE SCHEDULE ABOVE IS EDITED TO CONTAIN ONLY EQUIPMENT THAT IS SPECIFIC TO THIS PARTICULAR PROJECT.

ELECTRICAL REQUIREMENTS

BWW

ITEM NUMBER	DESCRIPTION	VOLTAGE	PHASE	AMPS	DEDICATED	KW	HP	DIRECT	RECEPTACLE	NEMA	HEIGHT (AFF)	EQUIPMENT COMMENTS
100	NITROGEN SYSTEM	120	1	15.0	X				DR	5-15P	80"	
015	WALK-IN BEER COOLER	120	1	20.0	X			X			108"	L.E.D. PRE-WIRED LIGHT FIXTURES BY COOLER MANUFACTURER. CIRCUIT TO INCLUDE LIGHTS, DOOR HEATER, SWITCHES AND ALARMS. ELECTRICAL CONTRACTOR TO VERIFY REQUIREMENTS WITH WALK IN MANUFACTURER.
01A	REMOTE COOLER COMPRESSOR	208-230	3	8.7	X		1-1/2	X		ROOF		COMPRESSOR AND PRE-WIRED TIME CLOCK LOCATED ON ROOF. ELECTRICAL CONTRACTOR TO EXTEND TO DISCONNECT SWITCH ON UNIT.
01B	COOLER EVAPORATOR	208-230	1	11.7	X			X			108"	EVAPORATOR IS POWERED AS PART OF ROOFTOP CONDENSING UNIT. EC TO EXTEND FROM CONDENSER TO EVAPORATOR AS REQUIRED.
01C	DRAIN LINE HEATER	120	1	2.0	X			X			108"	CONNECTION IS ON COMMON CIRCUIT WITH LIGHTS AND SWITCHES - #101 EXTEND POWER TO HEAT TAPE IN COMMON CIRCUIT WITH EVAPORATOR.
102	WALK-IN FREEZER	120	1	20.0	X			X			108"	L.E.D. PRE-WIRED LIGHT FIXTURES BY FREEZER MANUFACTURER. CIRCUIT TO INCLUDE LIGHTS, DOOR HEATER, SWITCHES AND ALARMS. ELECTRICAL CONTRACTOR TO VERIFY REQUIREMENTS WITH WALK IN MANUFACTURER.
02A	REMOTE FREEZER COMPRESSOR	208-230	3	10.7	X		3	X		ROOF		COMPRESSOR AND PRE-WIRED TIME CLOCK LOCATED ON ROOF. ELECTRICAL CONTRACTOR TO EXTEND TO DISCONNECT SWITCH ON UNIT.
02B	FREEZER EVAPORATOR	208-230	1	11.7	X			X			108"	EVAPORATOR IS POWERED AS PART OF ROOFTOP CONDENSING UNIT. EC TO EXTEND FROM CONDENSER TO EVAPORATOR AS REQUIRED.
02C	DRAIN LINE HEATER	120	1	2.0	X			X			108"	CONNECTION IS ON COMMON CIRCUIT WITH LIGHTS AND SWITCHES - #102 EXTEND POWER TO HEAT TAPE IN COMMON CIRCUIT WITH EVAPORATOR.
103	WALK-IN MEAT COOLER	120	1	20.0	X			X			108"	L.E.D. PRE-WIRED LIGHT FIXTURES BY COOLER MANUFACTURER. CIRCUIT TO INCLUDE LIGHTS, DOOR HEATER, SWITCHES AND ALARMS. ELECTRICAL CONTRACTOR TO VERIFY REQUIREMENTS WITH WALK IN MANUFACTURER.
03A	REMOTE COOLER COMPRESSOR	208-230	3	4.2	X		1	X		ROOF		COMPRESSOR AND PRE-WIRED TIME CLOCK LOCATED ON ROOF. ELECTRICAL CONTRACTOR TO EXTEND TO DISCONNECT SWITCH ON UNIT.
03B	COOLER EVAPORATOR	208-230	1	7.8	X			X			108"	EVAPORATOR IS POWERED AS PART OF ROOFTOP CONDENSING UNIT. EC TO EXTEND FROM CONDENSER TO EVAPORATOR AS REQUIRED.
03C	DRAIN LINE HEATER	120	1	2.0	X			X			108"	CONNECTION IS ON COMMON CIRCUIT WITH LIGHTS AND SWITCHES - #103 HEAT TAPE IS COMMON WITH #102C POWER TO SAME SOURCE.
104	WALK-IN PRODUCE COOLER	120	1	20.0	X			X			108"	L.E.D. PRE-WIRED LIGHT FIXTURES BY COOLER MANUFACTURER. CIRCUIT TO INCLUDE LIGHTS, SWITCHES AND ALARMS. ELECTRICAL CONTRACTOR TO VERIFY REQUIREMENTS WITH WALK IN MANUFACTURER.
04A	REMOTE COOLER COMPRESSOR	208-230	3	4.2	X		1	X		ROOF		COMPRESSOR AND PRE-WIRED TIME CLOCK LOCATED ON ROOF. ELECTRICAL CONTRACTOR TO EXTEND TO DISCONNECT SWITCH ON UNIT.
04B	COOLER EVAPORATOR	208-230	1	1.1	X			X			108"	ELECTRICAL CONTRACTOR TO EXTEND AND CONNECT FROM J-BOX MOUNTED ON TOP OF COOLER TO EVAPORATOR. VERIFY WITH M.M.
105	BEER SYSTEM FANS	120	1	15.0	X				DR	5-15P	90"	EC TO MOUNT DR ON UNDERSIDE OF BEER COOLER CEILING
105B	OVERHEAD BEER DELIVERY SYSTEM	120	1	21.0	X		1/2	X			108"	EC TO EXTEND AND CONNECT TO GLYCOL UNIT
106R	REFRIGERATED EQUIPMENT STAND	120	1	3.0	X		1/4		DR	5-15P	18"	
106C	GLASSWASHER (HIGH TEMP)	120-208	1	30.5	X			X			12"	EC TO EXTEND & CONNECT TO GLASSWASHER
110A	2) GLASS CHILLERS	120	1	7.0	X		1/3		DR	5-15P	18"	
115	2) BLENDERS	120	1	9.0	X		1/3		DR	5-15P	12"	
127S	PASS THRU COOLER	120	1	6.3	X		1/3		DR	5-15P	18"	REQUIRES FLOOR STUB-UP AND CONDUIT TO A DEDICATED RECEPTACLE
118												
134	EXHAUST HOOD SYSTEMS											REFER TO ELECTRICAL ENGINEERING DRAWINGS
119R	FRYERS 4-BANK	120	1	10.1	X				DR	5-15P	18"	
120	FRYERS 3-BANK	120	1	8.2	X				DR	5-15P	18"	
121	HOT WELL	120	1	12.5	X	1.5			DR	5-15P	18"	
122A	GRIDDLE	120	1	1.1					DR	5-15P	18"	
147A	REFRIGERATED PREP TABLE	120	1	7.8	X		1/2		DR	5-15P	18"	
127F	REFRIGERATED PREP TABLE	120	1	7.8	X		1/2		DR	5-15P	18"	
126A	FREEZER PREP BASE	120	1	11.2	X		1/2		DR	5-15P	18"	
127U	UNDERCOUNTER FREEZER	120	1	7.8	X		1/2		DR	5-15P	18"	
127RS	2) UNDERCOUNTER REFRIGERATORS	120	1	7.8	X		1/2		DR	5-15P	18"	
128	REFRIGERATED PREP COUNTER	120	1	7.8	X		1/2		DR	5-15P	18"	
129	MICROWAVE OVEN	208	1	16.4	X	3.0			SR	6-20P	18"	
129	2) MICROWAVE OVENS	208	1	16.4	X	3.0			SR	6-20P	90"	PLUGS INTO WIREWAY ON UNDERSIDE OF KITCHEN SOFFIT SEE ELEVATION 2 & 3 ON SHEET K5
131A	2) WARMING DRAWERS	120	1	7.5	X	0.90			DR	5-15P	12"	
131S	WARMING DRAWER	120	1	3.8	X	0.45			DR	5-15P	12"	
132	FRIED FOOD HOLDING STATION	208	1	14.0	X	2.80			SR	6-20P	48"	
133	MACHO NACHO	120	1	10.4	X	1.245			DR	5-15P	48"	
140D	HOT HOLDING CABINET	120	1	16.0	X	2.0			SR	5-20P	24"	
141A	2) HEAT LAMPS	208	1	15.0	X	3.12		X			24"	EC TO EXTEND IN COMMON J-BOX TO SEPARATE CONNECTIONS TO HEAT LAMPS 141A & 141B. WIRE SEPARATE CONTROLLER FOR EACH HEAT LAMP.
141B	2) HEAT LAMPS	208	1	7.5	X	1.56		X			24"	EC TO EXTEND IN COMMON J-BOX TO SEPARATE CONNECTIONS TO HEAT LAMPS 141A & 141B. WIRE SEPARATE CONTROLLER FOR EACH HEAT LAMP
143A	COFFEE- TEA BREWER	120	1	14.0	X	1.70			DR	5-15P	48"	VERIFY REQUIREMENTS WITH VENDOR
150											90"	
156	ICE MACHINE & REMOTE CONDENSER	208-230	1	27.7	X			X			& ROOF	ICE MACHINE & CONDENSER INTERWIRED - SEE DETAIL THIS SHEET. REFERENCE MFR'S SPECS FOR REMOTE REFRIGERATION REQUIREMENTS.
159	CONVECTION OVEN	208	3	30.0				1/3	DR	5-15P	42"	
159B	DISH MACHINE	208-240	3	45.4	X	8.5	2	X			10"	EC TO EXTEND AND CONNECT TO DISHMACHINE UNIT IS WIRED FOR OPTIONAL SINGLE POINT 3 PHASE CONNECTION
160	3) CARBONATORS	120	1	7.2					DR	5-15P	84"	VERIFY REQUIREMENTS WITH VENDOR
376	3) DROP IN SODA DISPENSERS	120	1	5.0					DR	5-15P	18"	SODA DISPENSERS AT REMOTE BEVERAGE STATION TO USE GFI OUTLET. VERIFY REQUIREMENTS WITH VENDOR
377	2) BAR GUNS	120	1	2.0	X				DR	5-15P	12"	

PLUMBING ROUGH-IN REQUIREMENTS

BWW

ITEM NUMBER	DESCRIPTION	PLUMBING: COLD WATER SIZE (IN)	HOT WATER SIZE (IN)	COLD+HOT WATER STUB HEIGHT (AFF)	DIRECT WASTE SIZE (IN)	DIRECT WASTE STUB HEIGHT (AFF)	INDIR WASTE SIZE (IN)	FLOOR DRAIN TYPE	NAT. GAS: GAS SIZE (IN)	BTU / HR	GAS STUB HEIGHT (AFF)	EQUIPMENT COMMENTS
018	BEER COOLER EVAPORATOR						1"	FFD				EXTEND INDIRECT WASTE FROM EVAPORATOR TO FFD
02B	FREEZER EVAPORATOR						1"	FFD				EXTEND INDIRECT WASTE FROM EVAPORATOR TO FFD
03B	MEAT COOLER EVAPORATOR						1"	FFD				EXTEND INDIRECT WASTE FROM EVAPORATOR TO FFD
04B	PRODUCE COOLER EVAPORATOR						1"	FFD				EXTEND INDIRECT WASTE FROM EVAPORATOR TO FFD
105	REMOTE BEER SYSTEM											PROVIDE 21/8" AT CEILING CONDUITS FOR SUPPLY LINES
105D	BEER TAP DRAIN PAN						1"	FS				EXTEND INDIRECT WASTE TO FLOOR SINK
106	FOUR COMPARTMENT BAR SINK	3/4"	3/4"				1-1/2"	FS				P.C. TO PROVIDE WATER TAP W/1/2" NPT & SHUT-OFF VALVE FOR CHEMICALS. CONNECT WATER. EXTEND INDIRECT WASTE TO FS AS REQUIRED
106G	GLASS RACK						1/2"	FS				EXTEND INDIRECT WASTE TO FLOOR SINK
107A	2) HAND SINKS	1/2"		21"	1-1/2"	18"						PC TO EXTEND & CONNECT WATER SUPPLY AND DRAIN
107A	HAND SINK AT BAR	1/2"		18"	1-1/2"							PC TO EXTEND & CONNECT WATER SUPPLY AND DRAIN
107B	2) DROP I