

ROOM FINISH SCHEDULE										
ROOM NO.	ROOM NAME	FLOOR		WALLS				CEILING		COMMENTS
		FLOOR	BASE	N	E	S	W	MATERIAL	FINISH	
BASEMENT										
100	CORRIDOR	VCT-1	RB-1	P-1	P-1	P-1	P-1	GWB	P-2	
101	STAIR	-	-	-	-	-	-	-	-	
102	IT REPAIR	VCT-1	RB-1	P-1	P-1	P-1	P-1	GWB	P-2	
103	IT STORAGE	VCT-1	RB-1	P-1	P-1	P-1	P-1	GWB	P-2	
104	MECH	CONC	RB-1	P-1	P-1	P-1	P-1	GWB	P-2	
105	WOMEN'S	PT-2	PT-1/PTB-1	PT-1	PT-1	PT-1	PT-1	GWB-MR	P-2	PT-1 TO GO DOWN TO FN. FLOOR EXCEPT WHERE NOTED OTHERWISE. PTB-1 ON NORTH WALL.
106	MEN'S	PT-2	PT-1	PT-1	PT-1	PT-1	PT-1	GWB-MR	P-2	PT-1 TO GO DOWN TO FN. FLOOR EXCEPT WHERE NOTED OTHERWISE.
107	ELEC	CONC	RB-1	P-1	P-1	P-1	P-1	GWB	P-2	
108	TELECOM	CONC	RB-1	P-1	P-1	P-1	P-1	GWB	P-2	
109	STORAGE	CONC	RB-1	P-1	P-1	P-1	P-1	GWB	P-2	
110	STORAGE / FUTURE MECHANICAL	CONC	RB-1	P-1	P-1	P-1	P-1	OTS	P-2	EXISTING CEILING TO REMAIN. PAINTED.
111	CORRIDOR	VCT-1	RB-1	P-1	P-1	P-1	P-1	GWB	P-2	
112	FUTURE USE	-	-	-	-	-	-	GWB	-	
113	FUTURE USE	-	-	-	-	-	-	GWB	-	
114	STORAGE	CONC	RB-1	P-1	P-1	P-1	P-1	GWB	P-2	
115	RADIO EQUIP	CONC	RB-1	P-1	P-1	P-1	P-1	GWB	P-2	

NOTE: EXISTING RATED PLASTER CEILING IS BEING REPLACED BY NEW GWB CEILING IN SAME PLACE. CEILING CONDITION IS OPEN TO THIS NEW GWB CEILING ALL AREAS EXCEPT FOR TOILET ROOMS.


FINISH MATERIAL SCHEDULE										
MATERIAL	KEY	DESCRIPTION	MANUFACTURER	PATTERN / ITEM NO.	COLOR	SIZE	FINISH	NOTES		
FLOOR TILE	NCT-1	VINYL COMPOSITION TILE	TBD	TBD	TBD	12" X 12"	-			
GYP-SUM WALL BOARD	GWB-MR	MOISTURE RESISTANT GYPSUM WALL BOARD - PAINTED	-	-	TBD	-	PAINTED			
P-1	-	WALL PAINT COLOR	SHERWIN WILLIAMS	SW9183	CONSERVATIVE GRAY	-	EGGSHELL			
P-2	-	GYPSUM CEILING PAINT COLOR	SHERWIN WILLIAMS	SW7207	CEILING BRIGHT WHITE	-	FLAT			
PT-1	-	PORCELAIN WALL TILE	TBD	TBD	TBD	4" X 4"	-			
PT-2	-	PORCELAIN FLOOR TILE	TBD	TBD	TBD	6" X 6"	-			
PTB-1	-	COVE BASE	TBD	TBD	TBD	4" HIGH	-			
RB-1	-	4" STANDARD COVE WITH TOE	POPPE	700 SERIES	154 BURNT UMBER	4" HIGH	-			
CONC	-	SEALED CONCRETE - SEE PROJECT MANUAL	-	-	TBD	-	TBD			

### FINISH SCHEDULE NOTES

- APPROPRIATE TRANSITION STRIPS ARE TO BE INSTALLED AT ALL CHANGES IN FLOOR FINISH.
- FURNITURE AND EQUIPMENT ARE NOT IN CONTRACT. ITEMS SHOWN ARE FOR COORDINATE PURPOSES ONLY.
- ALL HOLLOW METAL FRAMES TO BE PAINT FINISH TO BE GLOSSY.
- FOR COMPLETE FINISH INFORMATION, CONSULT FINISH SCHEDULES, FINISH PLANS, RCP'S, AND PARTITION SCHEDULE.
- ALL FINISHES BASED ON PROJECT NORTH. ALL FINISHES BASED ON PROJECT NORTH.
- ALL AREAS WITH EXPOSED PAINTED CEILINGS - PAINT WALLS UP TO 9'-0" A.F.F. PAINT UPPER PORTION OF WALL TO MATCH CEILING PAINT AS SCHEDULED UNLESS NOTED OTHERWISE.



1 GROUND FLOOR FINISH PLAN  
1/8" = 1'-0"



KEY PLAN

WESTERN CAROLINA UNIVERSITY  
MOORE HALL GROUND FLOOR RENOVATION  
CULLOWHEE, NC

SHEET	ISSUE	NO.	DATE	DESCRIPTION	BY
1	03/07/18	1	03/07/18	ISSUE FOR BID	AR

PRINCIPAL IN CHARGE: RB  
PROJECT ARCHITECT: LR  
DRAWN BY: AR  
SHEET TITLE: INTERIOR DESIGN FLOOR PLAN

SHEET NO. ID110  
PROJ. NO. 017384  
AGENCY REVIEW ID: 17-1742-01A



WESTERN CAROLINA UNIVERSITY

MOORE HALL GROUND FLOOR RENOVATION

CULLOWHEE, NC

ID110