


**1 FLOOR PLAN**  
A1.1 SCALE: 1/8" = 1'-0"



**GENERAL NOTES**

- (A) REFER TO PROJECT MANUAL FOR ADDITIONAL REQUIREMENTS.
- (B) ALL DIMENSIONS TO ROUGH FACE OF ROUGH FRAMING, CONCRETE, MASONRY OR CENTERLINE OF STRUCTURE, UNLESS OTHERWISE NOTED. COLD FORM METAL STUD INTERIOR PARTITION DIMENSIONS 3-5/8" UNLESS OTHERWISE INDICATED AND NOT SHOWN FOR CLARITY.
- (C) REFER TO EXTERIOR AND INTERIOR FINISH SCHEDULES FOR ADDITIONAL REQUIREMENTS.
- (D) REFER TO PRE-ENGINEERED METAL BUILDING SHOP DRAWINGS FOR ADDITIONAL REQUIREMENTS. NOTE: PERMITTED FINAL DESIGN CONDITIONS DEVIATE SUBSTANTIALLY FROM THOSE INDICATED HEREIN.


**KEY NOTES**

- (1) CONCEALED STEEL COLUMN, REFER TO PRE-ENGINEERED METAL BUILDING SHOP DRAWINGS. PROVIDE SHEET METAL COVER WITH NO EXPOSED HORIZONTAL SEAMS. FINISH TO MATCHING WINDOW FRAMING.
- (2) EXPOSED STEEL COLUMN, REFER TO PRE-ENGINEERED METAL BUILDING SHOP DRAWINGS, (PAINT).
- (3) NOT USED.
- (4) PORTABLE FIRE EXTINGUISHER SURFACE MOUNTED AT 42" A.F.F. TO CENTERLINE OF EXTINGUISHER. FIRE EXTINGUISHERS SHALL BE UL LISTED, ABC TYPE, WITH 10 LBS. CAPACITY.
- (5) SHOWROOM CORNER WALL BOX OUT. INSTALL 5/8" FIRE TREATED PLYWOOD BACKING TO BACK SIDE OF STUD INTERIOR FLANGE ON EACH EXPOSED WALL FACE FROM 8'-0" TO 10'-0" A.F.F. FOR INSTALLATION OF SECURITY MIRRORS. REFER TO 4/A4.2 (TYPICAL).
- (6) TACTILE EXIT SIGN AT EXIT DISCHARGE DOOR STATING "EXIT" WITH BRAILLE LETTERING. SIGN TYPE TO COMPLY WITH ANSI A117.1 AND MOUNTED AT 60" A.F.F. TO CENTERLINE.
- (7) STEEL COLUMN. PROVIDE 7/8" COLD FORM FURRING (20 GA.) OR FIRE TREATED 2X NAILERS AT 24" O.C. WITH 5/8" TYPE 'X' GYPSUM BOARD. HOLD TIGHT AND PLUMB WITH COLUMN.
- (8) KNOX BOX: PROVIDE AN APPROVED KEY BOX PER FIRE DEPARTMENT REQUIREMENTS. THE REQUIRED FORMS AND INSTALLATION INSTRUCTIONS FOR THE KEY BOX CAN BE OBTAINED FROM HANOVER COUNTY FIRE-EMS FIRE MARSHAL'S OFFICE AT (804) 365-6185. LOCATE WHERE SHOWN (VERIFY EXACT LOCATION WITH FIRE DEPARTMENT).
- (9) RESTROOM SIGNAGE EQUAL TO SETON IDENTIFICATION PRODUCTS (800-571-2595) ITEM # 89394 (SHOWING "RESTROOM" AND SYMBOLS FOR MEN, WOMEN AND HANDICAP ACCESSIBILITY). SIGNAGE IS TO BE MOUNTED ON HEADER WALL AS INDICATED ON THE PLAN.

**SPECIAL NOTE:**  
REFER TO PRE-ENGINEERED METAL BUILDING SHOP DRAWINGS FOR LOCATIONS OF INDEPENDENT STRUCTURAL VERTICAL LATERAL BRACING SYSTEMS AND NOTIFY OWNER'S REPRESENTATIVE AND ARCHITECT IF BRACING OCCURS ADJACENT TO RESTROOM PERIMETER WALLS. ENTIRE RESTROOM LAYOUT TO SHIFT 6" AWAY FROM BRACING WALL(S) TO CONCEAL STRUCTURE.

**INTERIOR WALL & CEILING NOTES**

- 1. GENERAL: REFER TO FINISH SCHEDULES FOR ADDITIONAL WALL FINISH MATERIAL APPLICATIONS.
- 2. REFER TO WALL SECTIONS AND DETAILS FOR ADDITIONAL CONDITIONS.
- 2. FRAMING:
  - A. PROVIDE FIRE TREATED 2X BLOCKING AS REQUIRED FOR INSTALLATION OF ACCESSORIES PER MANUFACTURER'S RECOMMENDATIONS.
  - B. PROVIDE DIAGONAL WALL BRACING (3" X 16 GA. FLAT STRIP) AT CORNER FACES OF FREE STANDING PARTITION SYSTEMS.
  - C. WHERE WALL FRAMING EXTENDS TO BOTTOM OF ROOF DECK OR STRUCTURE, PROVIDE DEFLECTION CHANNELS AT TOP TRACK FOR 1 1/2" MINIMUM DEFLECTION.
  - D. REFER TO STRUCTURAL DRAWINGS FOR STRUCTURAL STUD REQUIREMENTS.
  - E. REFER TO WINDOW AND DOOR HEAD, JAMB AND SILL DETAILS FOR ADDITIONAL FRAMING REQUIREMENTS.
  - F. PROVIDE HORIZONTAL STUD BRIDGING AT 4'-0" O.C. VERTICAL.
- 3. GYPSUM AND BACKING BOARD:
  - A. EXPANSION/CONTROL JOINTS: INSTALL EXPANSION/CONTROL JOINTS IN CEILINGS EXCEEDING 2500 SQ. FT. IN AREA AND IN PARTITION WALL LENGTHS EXCEEDING 30 FEET. DO NOT EXCEED A DISTANCE OF 50 FEET IN ANY DIRECTION BETWEEN CEILING JOINTS. INSTALL CONTROL JOINTS WHERE FRAMING OR FURRING CHANGES DIRECTION.
  - B. PROVIDE MOISTURE RESISTANT TYPE "X" GYPSUM BOARD AT ALL WET LOCATIONS (RESTROOMS, WET WALLS, AND JANITOR'S SINK AREAS).
  - C. PROVIDE "J" MOLDING, REGLETS, OR CORNER BEAD AT GYPSUM BOARD PERIMETER CONDITIONS TRANSITIONING TO DISSIMILAR EXPOSED FINISH MATERIALS.
- 4. INSULATION:
  - A. INSULATION SHALL HAVE A FLAME SPREAD RATING OF 0-25 AND A SMOKE DEVELOPMENT RATING OF 0-450.
  - B. PROVIDE SEALANT ON BOTH SIDES OF STUD BOTTOM TRACKS AT ACoustICAL INSULATED WALL LOCATIONS.
- 5. FIRE STOPPING:
  - A. PROVIDE FIRE STOPPING AND FIRE SEALANT MATERIALS AS REQUIRED AT ALL FIRE RATED ASSEMBLY TRANSITIONS, PENETRATIONS, AND PERIMETER CONDITIONS. RATINGS TO BE EQUAL TO RATED ASSEMBLY.



**CRAIG A. SCHNEIDER, AIA**  
ARCHITECT  
1736 East Sunrise, Suite 417  
Springfield, Missouri 65804  
417.862.0188  
417.862.3266  
e-mail: architect@estertyschneider.com

**PROJECT:**  
NEW O'REILLY AUTO PARTS STORE  
SLIDING HILL PLACE  
ASHLAND, VA 42 - ASHLAND MAGISTERIAL DISTRICT  
**FLOOR PLAN**

**O'Reilly AUTO PARTS**  
CORPORATE OFFICES  
535 SOUTH PATTERSON  
SPRINGFIELD, MISSOURI 65802  
(417) 862-2674 TELEPHONE

|          |          |
|----------|----------|
| COMM #   | 3993     |
| DATE:    | 2-24-17  |
| REVISION |          |
| DATE:    | 3-3-17   |
|          | 8-16-17  |
|          | 11-16-17 |
|          | 2-12-18  |