



WWW.LDILine.com

Order Plans @

- DEMOLITION NOTES:**
1. THE CONTRACTOR SHALL PRESERVE BENCHMARKS, REFERENCE POINTS AND STAKES.
 2. IF THE CONTRACTOR, IN THE COURSE OF WORK, FINDS ANY DISCREPANCIES BETWEEN THE PLANS AND THE PHYSICAL CONDITIONS OF THE LOCALITY, OR ANY OMISSIONS IN THE PLANS OR IN THE LAYOUT AS GIVEN BY THE ENGINEER, IT SHALL BE HIS DUTY TO IMMEDIATELY INFORM THE ENGINEER, IN WRITING, AND THE ENGINEER WILL PROMPTLY VERIFY THE SAME. ANY WORK DONE AFTER SUCH DISCOVERY, UNTIL AUTHORIZED, WILL BE AT THE CONTRACTOR'S RISK.
 3. THE PURPOSE OF THIS DRAWING IS TO CONVEY THE OVERALL SCOPE OF WORK AND IT IS NOT INTENDED TO COVER ALL DETAILS OR SPECIFICATIONS REQUIRED TO COMPLY WITH GENERALLY ACCEPTED DEMOLITION PRACTICES. CONTRACTOR SHALL THOROUGHLY FAMILIARIZE HIMSELF WITH THE SITE, SCOPE OF WORK, AND ALL EXISTING CONDITIONS AT THE JOB SITE PRIOR TO BIDDING AND COMMENCING THE WORK. DEMOLITION CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR MEANS, METHODS, TECHNIQUES, AND PROCEDURES USED TO COMPLETE THE WORK IN ACCORDANCE WITH THE CONSTRUCTION DOCUMENTS AND IS LIABLE FOR THE SAFETY OF THE PUBLIC AND CONTRACTOR'S EMPLOYEES DURING THE COURSE OF THE PROJECT.
 4. REMOVE AND LEGALLY DISPOSE OF INDICATED ITEMS OFFSITE, UNLESS OTHERWISE INDICATED.
 5. CONTRACTOR SHALL COMPLY WITH ALL GOVERNING REGULATIONS AND NOTIFICATIONS BEFORE STARTING SELECTIVE DEMOLITION.
 6. CONTRACTOR SHALL ARRANGE DEMOLITION SCHEDULE SO AS NOT TO INTERFERE WITH OWNER'S ON-SITE OPERATIONS.
 7. CONTRACTOR SHALL CONDUCT DEMOLITION OPERATIONS AND REMOVE DEBRIS TO ENSURE MINIMUM INTERFERENCE WITH ROADS, DRIVES, WALKS, AND OTHER ADJACENT OCCUPIED OR USED FACILITIES.
 8. CONTRACTOR SHALL ERECT TEMPORARY PROTECTION, SUCH AS WALLS, WALKS, FENCES, RAILINGS, CANOPIES, AND COVERED PASSAGEWAYS TO SECURE AREAS OF DEMOLITION AND CONSTRUCTION AND TO SEPARATE THOSE ACTIVITIES FROM ALL SCHOOL ACTIVITIES.
 9. PROTECT EXISTING SITE IMPROVEMENTS, APPURTENANCES, AND LANDSCAPING TO REMAIN.
 10. DEMOLISH AND REMOVE EXISTING CONSTRUCTION ONLY TO THE EXTENT REQUIRED BY NEW CONSTRUCTION AND AS INDICATED.
 11. BURNING OF DEMOLITION DEBRIS IS NOT PERMITTED.
 12. ALL AREAS OF CONSTRUCTION, INCLUDING STORAGE AREAS, SHALL BE FENCED AND GATED WITH LOCKABLE GATES. FENCE SHALL BE 6-FT CHAINLINK FENCE.

ASPHALT OR CONCRETE TO BE REMOVED

DEMOLITION PLAN
SCALE - 1" = 10'

Southern A&E architects & engineers
7951 Iron Circle
Austell, Ga. 30168
(770) 819-7777
DATE February 28, 2018
JOB NUMBER 01-647-061
FACILITY CODE NUMBER 66-1050
RENOVATIONS TO
BELWOOD ELEMENTARY SCHOOL
GORDON COUNTY BOARD OF EDUCATION
CALHOUN, GEORGIA
DRAWING NUMBER
C101

