



DEMOLITION NOTES:

REFER ALSO TO SPECIFICATIONS SECTION 02070 SELECTIVE DEMOLITION.
 DEMOLITION WORK IS NOT LIMITED ONLY TO DEMOLITION SHOWN ON THIS PLAN.
 REFER ALSO TO CIVIL, ARCHITECTURAL, STRUCTURAL, PLUMBING, MECHANICAL,
 ELECTRICAL AND KITCHEN DRAWINGS FOR ADDITIONAL DEMOLITION WORK
 NOT SHOWN ON THIS PLAN.

COORDINATE DEMOLITION WORK WITH NEW WORK IN THE AREA.
 UNLESS OTHERWISE NOTED ALL REMOVED MATERIAL AND DEBRIS SHALL BECOME
 THE PROPERTY OF THE CONTRACTOR AND REMOVED FROM THE SITE.

D1. REMOVE EXISTING VCT FLOORING & WALL BASE. AFTER REMOVAL
 OF EXIST. FLOORING & BASE. PREPARE EXISTING SLAB FOR NEW FLOOR
 INSTALLATION PER NEW FLOOR MANUFACTURER'S RECOMMENDATIONS.

D2. REMOVE EXISTING QUARRY TILE FLOORING, GROUT BED.
 PREPARE EXISTING SLAB FOR NEW FLOOR INSTALLATION PER NEW FLOOR
 MANUFACTURER'S RECOMMENDATIONS.

D3. REMOVE EXISTING ACOUSTICAL SUSPENDED CEILING SYSTEM, TILE & GRID
 W/ HANGERS. REFER TO ELECTRICAL & MECHANICAL DRAWINGS FOR EXTENT OF
 REMOVAL OF MECHANICAL DIFFUSERS / RETURNS & LIGHT FIXTURE, ETC.

D4. REMOVE EXISTING DOORS & FRAME.
 D5. REMOVE EXISTING DOORS & FRAMES. PATCH IN MATCHING MASONRY
 TO MAKE SMOOTH TRANSITION WITH EXISTING MASONRY BY SAW-TOOTHING

D6. REMOVE EXISTING WINDOW UNIT & PREPARE
 OPENING FOR NEW ALUMINUM WINDOW. REFER TO
 FLOOR PLAN, NEW WINDOW ELEVATION & SECTION
 FOR WORK REQUIRED.

D7. REMOVE EXISTING MECHANICAL UNIT
 (REFER TO MECHANICAL DRAWINGS FOR FURTHER DETAILS).
 CONTRACTOR IS REQUIRED TO BLOCK-UP EXISTING OPENINGS
 WITH MATCHING BRICK & MASONRY. REFER TO FLOOR PL
 FOR ADDITIONAL DETAILS & DESCRIPTION.

D8. REMOVE EXISTING CARPETING & RUBBER
 BASE. PREPARE EXISTING SLAB & WALL FOR NEW
 FLOOR & WALL BASE MATERIAL.

D9. REMOVE EXISTING MILLWORK (INCLUDE EXIST.
 BASE CABINETS & WALL CABINETS). BASE CABINETS TO
 TO REPLACE WITH NEW CABINETS. NEW WALL CABINETS
 WILL BE INSTALLED. CONTRACTOR IS TO REMOVE TO
 ALL HORIZONTAL SURFACES PRIOR TO REPAIRS.

D10. REMOVE EXISTING WALL MOUNTED TRACK STRIPS ON BOTH SIDES
 OF CORRIDOR.

D11. REMOVE EXISTING CERAMIC TILE FLOORING & GROUT. PREPARE
 EXISTING SLAB FOR NEW FLOOR INSTALLATION PER NEW FLOOR
 MANUFACTURER'S RECOMMENDATIONS.

GENERAL NOTE: REFER TO DOOR SCHEDULE DWGS A601
 FOR REQUIREMENTS OF REPLACING EXISTING DOORS. CONTRACTOR
 TO REMOVE EXIST. DOORS & HARDWARE AS PART OF DEMOLITION.

DEMOLITION LEGEND
 HATCHED AREA INDICATES EXISTING MASONRY
 WALL TO BE REMOVED. CONTRACTOR IS REQUIRED
 TO PATCH ADJACENT EXISTING WALL TO REMAIN
 WITH NEW MATCHING MASONRY SAW-TOOTH INTO
 EXISTING WALL TO MAKE SMOOTH TRANSITION &
 TO MAKE A COMPLETE WALL LOOK.

DEMOLITION PLAN
 SCALE: 1/16" = 1'-0"

Southern A&E 7951 Iron Circle Austell, Ga. 30168 (770) 819-7777 architects & engineers		REVISED DATE February 28, 2018 JOB NUMBER 01-847-061
FACILITY CODE NUMBER: 664-1050 RENOVATIONS TO: BELWOOD ELEMENTARY SCHOOL GORDON COUNTY BOARD OF EDUCATION CALHOUN, GEORGIA		
DRAWING NUMBER A102		