


# MT. HOLLY - HUNTERSVILLE ROAD (VARIABLE WIDTH PUBLIC R/W)



## CHARLOTTE-MECKLENBURG EROSION NOTES

1. ALL EROSION CONTROL MEASURES SHALL CONFORM TO THE STANDARDS SET FORTH IN THE CHARLOTTE LAND DEVELOPMENT STANDARDS MANUAL, STATE OF NORTH CAROLINA EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL, OR THE MORE RESTRICTIVE OF ANY STANDARDS THAT CONFLICT.
2. ALL STORM DRAINAGE DESIGN SHALL CONFORM TO THE STANDARDS AND SPECIFICATIONS AS PROVIDED IN THE CHARLOTTE-MECKLENBURG STORM WATER DESIGN MANUAL, CHARLOTTE LAND DEVELOPMENT STANDARDS MANUAL, OR THE MORE RESTRICTIVE OF ANY STANDARDS THAT CONFLICT.
3. IN AREAS WHERE THE FLOODWAY REGULATIONS ARE APPLICABLE, THE FUTURE CONDITIONS FLOOD FRINGE LINE, FEMA FLOOD FRINGE LINE, COMMUNITY ENCROACHMENT LINE, AND FEMA ENCROACHMENT LINE SHALL BE SHOWN ON THE PRELIMINARY PLAN AND THE FINAL PLAN. AN APPLICATION FOR A FLOODPLAINS DEVELOPMENT PERMIT SHALL BE SUBMITTED TO MECKLENBURG COUNTY ENGINEERING IN ACCORDANCE WITH THE REQUIREMENTS SET FORTH IN THE CITY/COUNTY FLOODWAY REGULATIONS.
4. CITE ALL APPROPRIATE STANDARD DETAIL NUMBERS FOR ANY STRUCTURES OR SPECIFICS USED WITHIN THE PLANS IN REFERENCE TO THE MOST CURRENT COPY OF THE CHARLOTTE LAND DEVELOPMENT STANDARDS MANUAL.

## EROSION AND SEDIMENT CONTROL PLAN NARRATIVE:

1. EXISTING SITE CONDITIONS: PROJECT AREA IS CURRENTLY A PRE-DEVELOPED PARCEL WITHIN THE CITY LIMITS OF CHARLOTTE. THE SITE CURRENTLY EXISTS AS A VACANT LOT PARCEL. THE MAJORITY OF THE SITE CURRENTLY DRAINS OFF-SITE VIA OVERLAND FLOW.
2. PROJECT DESCRIPTION: PROJECT SHALL CONSIST OF CONSTRUCTION OF PROPOSED TACO BELL RESTAURANT ALONG WITH SITE REPAIRS, INFRASTRUCTURE AND LANDSCAPING. THE APPROXIMATED TOTAL DISTURBED AREA = 31,560 SF / 0.725 ACRES.
3. CRITICAL OR SENSITIVE AREAS: THIS SITE DOES NOT CONTAIN ANY CRITICAL OR SENSITIVE AREAS.
4. CONSTRUCTION SCHEDULING: ORDER OF EROSION CONTROL CONSTRUCTION (PRIOR TO LAND DISTURBANCE)
  - A. INSTALL CONSTRUCTION ENTRANCE, AND DESIGNATE EQUIPMENT AND CHEMICAL STORAGE AREAS.
  - B. CONSTRUCT SILT FENCE AND INLET PROTECTION AS INDICATED.
  - C. CONSTRUCT TEMPORARY SEDIMENT TRAPS.
  - D. PERFORM LAND CLEARING AND GRADING, INSTALLING E&S COMPONENTS AT THE EARLIEST POSSIBLE TIME DURING GRADING ACTIVITIES.
  - E. MAINTAIN E&S MEASURES THROUGHOUT THE GRADING PROCESS.
  - F. STABILIZE SURFACES IMMEDIATELY IN AREAS WHERE WORK IS COMPLETED.
  - G. INSTALL PERMANENT STABILIZATION MEASURES, SUCH AS SEEDING AND MULCHING, SOON AFTER THE EARLIEST POSSIBLE TIME.
  - H. FOLLOWING COMPLETION OF GRADING AND CONSTRUCTION ACTIVITIES REMOVE TEMPORARY CONTROLS TO STABILIZE ALL DISTURBED AREAS.
5. INSPECTION AND MAINTENANCE SCHEDULE FOR E&S AND EROSION CONTROL DEVICES: INSPECTIONS SPECIFIC TO ALL EROSION AND SEDIMENT CONTROL DEVICES AND STORMWATER OUTLETS SHALL BE INSPECTED AT LEAST ONCE EVERY 7 DAYS AND WITHIN 24 HOURS AFTER A RAINFALL EVENT OF 1/2" OR GREATER.

## CONSTRUCTION SEQUENCE

1. OBTAIN GRADING/EROSION CONTROL PLAN APPROVAL FROM THE MECKLENBURG COUNTY LUESA.
2. SET UP AN ON-SITE PRE-CONSTRUCTION CONFERENCE WITH THE FOLLOWING DEPARTMENTS: (THE TERRITORY FOR INSPECTORS ARE LISTED BELOW): LUESA EROSION CONTROL INSPECTOR, LAND DEVELOPMENT INSPECTOR AND ZONING INSPECTOR. FAILURE TO SCHEDULE SUCH CONFERENCE 48 HOURS PRIOR TO ANY LAND DISTURBING ACTIVITY IS SUBJECT TO FINE.
3. INSTALL SILT FENCE, INLET PROTECTION, SEDIMENT TRAPS, DIVERSION DITCHES, TREE PROTECTION, AND OTHER MEASURES AS SHOWN ON PLANS, CLEARING ONLY AS NECESSARY TO INSTALL THESE DEVICES.
4. CALL FOR ON-SITE INSPECTION BY INSPECTOR. WHEN APPROVED, INSPECTOR ISSUES THE GRADING PERMIT AND CLEARING AND GRUBBING MAY BEGIN.
5. THE CONTRACTOR SHALL DILIGENTLY AND CONTINUOUSLY MAINTAIN ALL EROSION CONTROL DEVICES AND STRUCTURES.
6. FOR PHASED EROSION CONTROL PLAN, THE CONTRACTOR SHALL MEET WITH EROSION CONTROL INSPECTOR PRIOR TO COMMENCING WITH EACH PHASE OF EROSION CONTROL MEASURES.
7. THE LAND DEVELOPMENT INSPECTOR SHOULD BE CALLED TO CONDUCT INSPECTIONS ON STORM DRAINAGE, SIDEWALKS, DRIVEWAY ON STORM DRAINAGE, SIDEWALKS, DRIVE WAY IMPROVEMENTS, AND ALL ASPECTS OF ROAD CONSTRUCTION.
8. STABILIZE SITE AS AREAS ARE BROUGHT TO FINISHED GRADE.
9. COORDINATE WITH EROSION CONTROL INSPECTOR PRIOR TO REMOVAL OF EROSION CONTROL MEASURE.
10. ALL EROSION CONTROL MEASURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE N. C. EROSION AND SEDIMENT CONTROL PLANNING AND DESIGN MANUAL, U. S. DEPT. OF AGRICULTURE, MECKLENBURG COUNTY EROSION CONTROL ORDINANCE, AND THE CHARLOTTE-MECKLENBURG LAND DEVELOPMENT STANDARDS.
11. CALL THE WATER QUALITY INSPECTOR (NAME) AT (PHONE NUMBER) TO SET UP A BMP PRE-CONSTRUCTION MEETING PRIOR TO STARTING ANY WORK. THIS MEETING SHOULD TAKE PLACE AT LEAST 48 HOURS PRIOR TO STARTING CONSTRUCTION ON ANY BMP. THE INSPECTOR WILL VERIFY THAT THE CONTRIBUTING DRAINAGE AREA IS COMPLETELY STABILIZED AND STORM DRAINAGE PIPES ARE CLEAN BEFORE INSTALLATION OF ANY BMP.

## CLEARING AND SITE PREPARATION NOTES:

1. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROPER INSTALLATION OF THE EROSION CONTROL DEVICES, AS SHOWN ON THE CONSTRUCTION PLANS, PRIOR TO ANY SITE CLEARING AND/OR DEMOLITION. REFER TO THE "EROSION CONTROL NOTES" SECTION CONTAINED HEREIN FOR ADDITIONAL REQUIREMENTS. NOT ALL NOTES MAY BE APPLICABLE.
2. PRIOR TO ANY SITE CLEARING, ALL TREES SHOWN TO REMAIN, AS INDICATED ON THE CONSTRUCTION PLANS, SHALL BE PROTECTED IN ACCORDANCE WITH LOCAL TREE ORDINANCES AND DETAILS CONTAINED IN THESE PLANS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO MAINTAIN THESE TREES IN GOOD CONDITION. NO TREE(S) SHOWN TO REMAIN SHALL BE REMOVED WITHOUT WRITTEN APPROVAL FROM THE OWNER AND THE LOCAL AGENCY HAVING JURISDICTION OVER THESE ACTIVITIES.
3. THE CONTRACTOR SHALL CLEAR AND GRUB ONLY THOSE PORTIONS OF THE SITE NECESSARY FOR CONSTRUCTION. ALL DISTURBED AREAS MUST BE SEED, MULCH, SODDED OR PLANTED WITH OTHER APPROVED LANDSCAPE MATERIAL IMMEDIATELY FOLLOWING CONSTRUCTION.
4. THE TOP 4" TO 6" OF GROUND REMOVED DURING CLEARING AND GRUBBING ACTIVITIES SHALL BE STOCKPILED. TO BE USED FOR LANDSCAPING PURPOSES, UNLESS OTHERWISE DIRECTED BY THE OWNER. REMAINING EARTHWORK THAT RESULTS FROM CLEARING AND GRUBBING OR SITE EXCAVATION IS TO BE UTILIZED ON-SITE, PROVIDED THE MATERIAL EXISTING ABOVE THE OWNER'S SOILS TESTING CATEGORY. EXCESS MATERIAL IS TO EITHER BE STOCKPILED ON-SITE, AS DIRECTED BY THE OWNER OR OWNER'S ENGINEER, OR REMOVED FROM THE SITE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ACQUIRING ANY PERMITS THAT ARE NECESSARY FOR REMOVING ANY EXCESS MATERIAL FROM THE SITE.
5. ALL EXISTING DEBRIS (ABOVE OR BELOW GROUND), CONSTRUCTION DEBRIS AND OTHER WASTE MATERIAL SHALL BE REMOVED FROM THE SITE BY THE CONTRACTOR, IN ACCORDANCE WITH APPLICABLE REGULATORY AGENCY REQUIREMENTS.
6. THE CONTRACTOR IS TO PREPARE THE SITE IN ACCORDANCE WITH THE SOILS REPORT, COPIES OF WHICH ARE AVAILABLE TO THE OWNER OR SOILS TESTING COMPANY DIRECTLY.
7. CONTRACTOR TO BE RESPONSIBLE FOR INSTALLATION OF TEMPORARY CONSTRUCTION FENCE ALONG THE PERIMETER OF PROPERTY. TYPE OF FENCE IS TO BE SUBMITTED BY CONTRACTOR TO ENGINEER FOR APPROVAL.
8. THE CONTRACTOR SHALL REMOVE ALL VEGETATION, SURFACES SOIL, DEMOLITION MATERIALS AND OTHER UNDESIRABLE MATERIALS. SUCH MATERIALS SHALL BE REMOVED FROM THE SITE AND DISPOSED OF IN ACCORDANCE WITH GOVERNING LOCAL AND STATE LAWS.

## EROSION AND SEDIMENT CONTROL:

1. GENERAL: ALL EROSION AND SEDIMENT CONTROL METHODS SHALL BE IMPLEMENTED PRIOR TO THE START OF CONSTRUCTION. DURING CONSTRUCTION, EXPOSED AREAS SHALL BE COVERED BY MULCHES SUCH AS STRAW, HAY, OR OTHER ACCEPTABLE MATERIALS. THE MAJORITY OF THE PROJECT SHALL BE PROTECTED BY SEDIMENT TRAPS OR BALES. THESE SHALL BE MAINTAINED AND MODIFIED DURING THE CONSTRUCTION PROCESS TO MINIMIZE DOWNSTREAM SILTATION. WHEN COMPLETION IS NEAR, EXPOSED AREAS WILL BE REPAIRED. CLEARED OF SILT, MUD AND DEBRIS, AND RE-SODDED TO PROPERLY DEFINE THE INTENDED STORM QUANTITIES.
2. PROTECTION AND STABILIZATION OF ON-SITE SOIL STOCKPILES: FILL MATERIAL SHALL BE PROTECTED BY MULCHES OR COVERED BY CONSTRUCTION DRAINAGE CONTROLS THAT PREVENT EROSION OF THE STOCKPILED MATERIAL. CONTROL OF DUST FROM SUCH STOCKPILES MAY BE REQUIRED, DEPENDING UPON THEIR LOCATION AND THE EXPECTED LENGTH OF TIME THE STOCKPILES WILL BE PRESENT. IN NO CASE SHALL ANY UNSTOCKPILED MATERIAL REMAIN MORE THAN THIRTY (30) CALENDAR DAYS AFTER SUBSTANTIAL PROJECT COMPLETION.
3. PROTECTION OF EXISTING STORM SEWER SYSTEMS: DURING CONSTRUCTION, ALL STORM SEWER INLETS IN THE VICINITY OF THE PROJECT SHALL BE PROTECTED BY SEDIMENT TRAPS SUCH AS SECURED HAY BALES, SOD, STONE, ETC., WHICH SHALL BE MAINTAINED AND MODIFIED AS REQUIRED BY CONSTRUCTION PROGRESS, AND WHICH MUST BE APPROVED BY THE ENGINEER BEFORE INSTALLATION.
4. SEDIMENT BASINS AND SEDIMENT TRAPPING MEASURES: PERIMETER BERMS, SEDIMENT BARRIERS, VEGETATIVE BUFFERS AND OTHER MEASURES INTENDED TO TRAP SEDIMENT AND/OR PREVENT THE TRANSPORT OF SEDIMENT ON ADJACENT PROPERTIES, OR INTO EXISTING BODIES OF WATER, MUST BE INSTALLED, CONSTRUCTED OR, IN THE CASE OF VEGETATIVE BUFFERS, PROTECTED FROM DISTURBANCE AS A FIRST STEP IN THE LAND ALTERATION PROCESS. SUCH SYSTEMS SHALL BE FULLY OPERATIVE BEFORE ANY OTHER DISTURBANCE OF THE SITE BEGINS. EARTHEN STRUCTURES, INCLUDING BUT NOT LIMITED TO BERMS, EARTH FILTERS, DAMS, OR DOWNSLOPES, SHALL BE STABILIZED AND PROTECTED FROM DRAINAGE DAMAGE OR EROSION WITHIN ONE WEEK OF INSTALLATION.
5. SWALES, DITCHES AND CHANNELS: CHANNELS LEADING FROM THE SITE SHALL BE SODDED WITH ARGENTINE BAHIA WITHIN THREE (3) DAYS OF EXCAVATION.
6. UNDERGROUND UTILITY CONSTRUCTION: UNDERGROUND UTILITY LINES AND OTHER STRUCTURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE FOLLOWING STANDARDS:
  - A. NO MORE THAN 500 LINEAR FEET OF TRENCH SHALL BE OPEN AT ANY ONE TIME.
  - B. EXCAVATED MATERIAL SHALL BE CAST TO THE UPHILL SIDE OF TRENCHES AS LONG AS SAFETY AND SPACE CONSIDERATION ALLOW. TRENCH MATERIAL SHALL NOT BE CAST INTO, (OR ONTO) THE SLOPE OF ANY STREAM, CHANNEL, ROAD, DITCH OR WATERWAY.
7. ALL EROSION AND SILTATION CONTROL DEVICES: SHALL BE REGULARLY INSPECTED AND MAINTAINED, (ESPECIALLY AFTER EACH RAINFALL) AND WILL BE CLEANED OUT AND/OR REPAIRED AS REQUIRED.
8. DISTURBED AREAS AND AREAS USED FOR STORAGE OF MATERIALS THAT ARE EXPOSED TO RAIN SHALL BE INSPECTED FOR EVIDENCE OF, OR THE POTENTIAL FOR, POLLUTANTS ENTERING THE STORMWATER SYSTEM.
9. APPLICATION RATES AND METHODS FOR USE OF FERTILIZERS AND PESTICIDES AT THE CONSTRUCTION SITE SHALL CONFORM WITH ALL LOCAL AND STATE ORDINANCES. NUTRIENTS SHALL BE APPLIED ONLY AT RATES NECESSARY TO ESTABLISH AND MAINTAIN VEGETATION SUCH THAT DISCHARGES WILL NOT CAUSE OR CONTRIBUTE TO VIOLATIONS OF STATE SURFACE OR GROUNDWATER QUALITY STANDARDS.
10. OFF-SITE VEHICLE TRACKING OF SEDIMENTS AND THE GENERATION OF DUST SHALL BE MINIMIZED BY CONTRACTOR.

## DEWATERING NOTES:

1. DURING THE EXCAVATION OF THE STORMWATER PONDS, THE CONTRACTOR MUST CONSTRUCT A SEDIMENT BASIN TO PROVIDE A DISCHARGE POINT FOR DEWATERING. THE SEDIMENT BASIN CAN BE A CELL IN THE PROPOSED EXCAVATION AREA OF LAND OR IT CAN BE A TRENCH AREA ABOVE GROUND. ALL DEWATERING MUST BE DONE IN THE SEDIMENT AREA UNTIL THE WATER IS CLEAN SUCH THAT THERE WOULD BE NO TURBID DISCHARGE.
2. DURING EXCAVATION, THE CONTRACTOR SHALL NOT PENETRATE THE EXISTING CLAY LAYER. IF PRESENT, THE CONTRACTOR ENCOUNTERS THE CLAY LAYER, HE/SHE IS TO PLACE A MINIMUM OF 2 FEET OF SANDY MATERIAL OVER THE CLAY AND TERMINATE THE DEPTH OF THE EXCAVATION.
3. THE CONTRACTOR ENCOUNTERS SILTY/CLAY SAND, WHICH CAUSE THE WATER TO BECOME TURBID, HE/SHE SHALL TREAT THE SEDIMENT BASIN WITH A CHEMICAL ADDITIVE SUCH AS ALUM IN ORDER TO PROMOTE THE COAGULATION AND SETTLEMENT OF THE PARTICLES FOR THE WATER TO BECOME LESS TURBID. IF TURBID WATER IS ENCOUNTERED DURING EXCAVATION OF THE POND, THE CONTRACTOR SHALL NOTIFY THE ENGINEER OF RECORD IMMEDIATELY TO DETERMINE THE COURSE OF ACTION THAT IS APPROPRIATE TO ELIMINATE THE TURBIDITY AND ALLOW DISCHARGE THAT MEETS WATER QUALITY STANDARDS.
4. THE CONTRACTOR SHALL FOLLOW THE EXCAVATION OF THE STORMWATER PONDS SUCH THAT A SEDIMENT BASIN WILL BE AVAILABLE AT ALL TIMES. THE SEDIMENT BASIN CAN BE RELOCATED AS NECESSARY TO ENSURE THE WATER WITHIN THE SEDIMENT BASIN BECOMES NON-TURBID AND ACCEPTABLE FOR DISCHARGE OFF-SITE.

## BEST MANAGEMENT PRACTICES:

THIS PLAN HAS BEEN PREPARED TO ENSURE COMPLIANCE WITH APPROPRIATE CONDITIONS OF LOCAL, STATE AND FEDERAL REGULATIONS. THE PLAN ADDRESSES THE FOLLOWING AREAS:

1. GENERAL EROSION CONTROL.
2. PROTECTION OF SURFACE WATER QUALITY DURING AND AFTER CONSTRUCTION.
3. CONTROL OF WIND EROSION.

THE VARIOUS TECHNIQUES OR ACTIONS IDENTIFIED UNDER EACH SECTION INDICATE THE APPROPRIATE SITUATION WHEN THE TECHNIQUES SHOULD BE EMPLOYED. IT SHOULD BE NOTED THAT THE MEASURES IDENTIFIED ON THIS PLAN ARE ONLY SUGGESTED BMP(S). THE CONTRACTOR SHALL

PROVIDE POLLUTION PREVENTION AND EROSION CONTROL MEASURES AS SPECIFIED IN THE CHARLOTTE LAND DEVELOPMENT STANDARDS MANUAL, 3000 SERIES DETAILS AND AS NECESSARY FOR EACH SPECIFIC APPLICATION.

## DEMOLITION NOTES (IF NECESSARY):

1. CONTRACTOR SHALL SUBMIT DEMOLITION SCHEDULE TO OWNER PRIOR TO PROCEEDING WITH DEMOLITION ACTIVITIES.
2. EXTENT OF SITE CLEARING IS SHOWN ON DRAWINGS.
3. SITE DEMOLITION WORK INCLUDES, BUT IS NOT LIMITED TO:
  - A) ROADWAY
  - B) DRAINAGE AREA
  - C) SITE UTILITIES
  - D) LANDSCAPING
4. CONDUCT SITE DEMOLITION OPERATIONS TO ENSURE MINIMUM INTERFERENCE WITH ROADS, STREETS, WALKS, AND OTHER ADJACENT OCCUPIED OR USED FACILITIES. DO NOT CLOSE OR CONSTRUCT STREETS, WALKS OR OTHER OCCUPIED OR USED FACILITIES WITHOUT PERMISSION FROM AUTHORITIES HAVING JURISDICTION.
5. PROVIDE PROTECTION NECESSARY TO PREVENT DAMAGE TO EXISTING IMPROVEMENTS INDICATED ON PLANS. EXISTING TO REMAIN DAMAGED IMPROVEMENTS TO BE RESTORED TO ORIGINAL CONDITION, AS ACCEPTABLE TO PARTIES HAVING JURISDICTION.
6. REMOVE WASTE MATERIALS AND UNSUITABLE TOPSOIL FROM PROPERTY AND DISPOSE OFF-SITE IN A LEGAL MANNER.
7. LAND UNDERGROUND UTILITIES TO REMAIN IN PLACE, PROVIDE ADEQUATE SUPPORT AND PROTECTION DURING DEMOLITION OPERATION.
8. UNWARRANTED, OR INCORRECTLY CHARTED, PIPING OR OTHER UTILITIES BE ENCOUNTERED DURING DEMOLITION, CONSULT PROJECT ENGINEER AND UTILITY OWNER FOR IMMEDIATE ACTION.
9. DEMOLITION AND COMPLETELY REMOVE FROM SITE MATERIAL INDICATED ON PLANS. MATERIAL TO BE REMOVED:
  - A) UNWARRANTED, OR INCORRECTLY CHARTED, PIPING OR OTHER UTILITIES FROM DAMAGE CAUSED BY SETTLEMENT, LATERAL MOVEMENT, CORROSION, WASHOUT, OTHER HAZARDS CREATED BY THE DEMOLITION OPERATION.
10. CONDUCTIVE CLEARING REFER TO LANDSCAPE PLAN.
11. CONTRACTOR SHALL RESTORE ALL DISTURBED AREAS TO EXISTING CONDITIONS, OR BETTER. FURTHERMORE, CONTRACTOR SHALL PROVIDE TO THE ENGINEER A PHOTOGRAPH OF PRE-CONSTRUCTION CONDITIONS AND POST-CONSTRUCTION CONDITIONS AS NOTED ON PLANS.
12. CONTRACTOR SHALL MAINTAIN STORMWATER MANAGEMENT SYSTEM TO INSURE NO DAMAGE TO ADJACENT PROPERTIES OCCURS DURING 100-YEAR STORM EVENTS.

## GENERAL NOTES:

1. SITE DEVELOPER TO PROVIDE GRADING TO 0.1 FT PRIOR TO PAVING.
2. ONCE SITE IS CLEARED, EROSION CONTROL MEASURES (I.E., SEED AND MULCH) WILL BE IMPLEMENTED IN ACCORDANCE WITH THIS PLAN.
3. ALL ROADWAYS SHALL BE MAINTAINED/SWEPT DAILY TO REMOVE ANY DIRT TRANSPORTED ONTO THE EXISTING PAVED ROADWAYS.

## SECTION 1 GENERAL EROSION CONTROL:

- 1.1 GENERAL EROSION CONTROL BEST MANAGEMENT PRACTICES SHALL BE EMPLOYED TO MINIMIZE SOIL EROSION AND POTENTIAL POND SLOPE FAILURES. WHILE THE VARIOUS TECHNIQUES REQUIRED WILL BE SITE SPECIFIC, THEY SHOULD BE EMPLOYED AS SOON AS POSSIBLE DURING CONSTRUCTION ACTIVITIES.
- 1.2 CLEARED SITE DEVELOPMENT AREAS NOT CONTINUALLY USED FOR CONSTRUCTION ACTIVITIES SHALL BE COVERED WITH HAY AND/OR OVER SEEDED AND SUFFICIENTLY WATERED TO STABILIZE THE TEMPORARY GROUND COVER.
- 1.3 BANKS OF RETENTION/DETENTION PONDS SHALL NOT BE CONSTRUCTED STEEPER THAN 4H:1V FROM TOP OF BANK TO TWO FEET BELOW THE CONTROL ELEVATION.
- 1.4 A 1-FOOT WIDE STRIP OF SOD SHALL BE PLACED ALONG ALL CURBING AND AROUND ALL INLETS. SOD SHALL BE PLACED BEFORE SILT BARRIERS ARE REMOVED.
- 1.5 THE CONTRACTOR WILL STABILIZE BY SEED AND MULCH, SOD, OR OTHER APPROVED MATERIALS ANY DISTURBED AREAS WITHIN ONE WEEK FOLLOWING COMPLETION OF THE UTILITY SYSTEMS AND PAVEMENT AREAS. CONTRACTOR SHALL MAINTAIN SUCH AREAS UNTIL FINAL ACCEPTANCE BY THE OWNER. THE CONTRACTOR IS TO COORDINATE WITH THE OWNER REGARDING THE TYPE OF MATERIAL, LANDSCAPING AND IRRIGATION REQUIREMENTS.

## SECTION 2 PROTECTION OF SURFACE WATER QUALITY DURING AND AFTER CONSTRUCTION:

- 2.1 SURFACE WATER QUALITY SHALL BE MAINTAINED BY EMPLOYING THE FOLLOWING BEST MANAGEMENT PRACTICES IN THE CONSTRUCTION PLANNING AND CONSTRUCTION OF ALL IMPROVEMENTS.
- 2.2 WHERE PRACTICAL, STORMWATER SHALL BE CONVEYED BY SWALES.
- 2.3 EROSION CONTROL MEASURES SHALL BE EMPLOYED TO MINIMIZE TURBIDITY OF SURFACE WATERS LOCATED DOWNSTREAM OF ANY CONSTRUCTION ACTIVITY. WHILE THE VARIOUS MEASURES REQUIRED WILL BE SITE SPECIFIC, THEY SHALL BE EMPLOYED AS NEEEDED IN ACCORDANCE WITH THE FOLLOWING:
  - A. IN GENERAL, EROSION SHALL BE CONTROLLED AT THE FURTHEST PRACTICAL UPSTREAM LOCATION.
  - B. STORMWATER INLETS SHALL BE PROTECTED DURING CONSTRUCTION AS INDICATED. PROTECTION MEASURES SHALL BE EMPLOYED AS SOON AS PRACTICAL DURING THE VARIOUS STAGES OF INLET CONSTRUCTION. SILT BARRIERS SHALL REMAIN IN PLACE UNTIL SODDING AROUND INLETS IS COMPLETE.
- 2.4 HEAVY CONSTRUCTION EQUIPMENT PARKING AND MAINTENANCE AREAS SHALL BE DESIGNED TO PREVENT OIL, GREASE, AND LUBRICANTS FROM ENTERING SITE DRAINAGE FEATURES INCLUDING STORMWATER COLLECTION AND TREATMENT SYSTEMS. CONTRACTORS SHALL PROVIDE BROAD DIKES, HAY BALES OR SILT SCREENS AROUND, AND SEDIMENT SUMPS WITHIN SUCH AREAS TO CONTAIN SPILLS OF OIL, GREASE OR LUBRICANTS. CONTRACTORS SHALL HAVE AVAILABLE, AND USE ABSORBENT FILTER PADS TO CLEAN UP SPILLS AS SOON AS POSSIBLE AFTER OCCURRENCE.
- 2.5 SILT BARRIERS: ANY SILT WHICH ACCUMULATES BEHIND THE BARRIERS AND ANY FILL USED TO ANCHOR THE BARRIERS SHALL BE REMOVED PROMPTLY AFTER THE END OF THE MAINTENANCE PERIOD SPECIFIED FOR THE BARRIERS.
- 2.6 PREVENT EROSION FROM SHEET FLOW ACROSS BARE GROUND FROM ENTERING LAKES OR SWALES BY INSTALLING A TEMPORARY SEDIMENT SUMP AS REQUIRED. THE TEMPORARY SEDIMENT SUMP SHALL REMAIN IN PLACE UNTIL VEGETATION IS ESTABLISHED ON THE GROUND DRAINING TO THE SUMP.

## SECTION 3 CONTROL OF WIND EROSION:

- 3.1 WIND EROSION SHALL BE CONTROLLED BY EMPLOYING THE FOLLOWING METHODS AS NECESSARY AND APPROPRIATE:
  - A. BARE EARTH AREAS SHALL BE WATERED DURING CONSTRUCTION AS NECESSARY TO MINIMIZE THE TRANSPORT OF FUGITIVE DUST. IT MAY BE NECESSARY TO LIMIT CONSTRUCTION VEHICLE SPEED IF BARE EARTH HAS NOT BEEN EFFECTIVELY WATERED. IN NO CASE SHALL FUGITIVE DUST BE ALLOWED TO LEAVE THE SITE UNDER CONSTRUCTION.
  - B. AS SOON AS PRACTICAL AFTER COMPLETION OF CONSTRUCTION, BARE EARTH AREAS SHALL BE VEGETATED.
  - C. ANY TIME DURING CONSTRUCTION THAT WATERING AND/OR VEGETATION IS NOT EFFECTIVE IN CONTROLLING WIND EROSION AND/OR THE TRANSPORT OF FUGITIVE DUST, OTHER METHODS AS ARE NECESSARY FOR SUCH CONTROL SHALL BE EMPLOYED. THESE METHODS MAY INCLUDE ERECTION OF DUST CONTROL FENCES.

**CORNELISON ENGINEERING & DESIGN, INC.**  
**CED**  
 © 2017 CORNELISON ENGINEERING & DESIGN, INC.  
 3809 S OLD 5TH AVENUE, FAYETTEVILLE, NC 28404  
 TEL: 815-339-4200 FAX: 815-339-7682  
 WWW.CORNELISON-ENG.COM  
 CERTIFICATE OF AUTHORIZATION 4581

**CORNELISON ENGINEERING & DESIGN, INC.**  
 PROFESSIONAL SEAL  
 037118  
 ENGINEER  
 CRAIG L. CORNELISON  
 2-09-18  
 CRAIG L. CORNELISON, P.E.  
 NORTH CAROLINA LICENSE NUMBER  
 PE037118

REVISIONS:	

CONTRACT DATE: \_\_\_\_\_  
 BUILDING TYPE: MED 54  
 PLAN VERSION: \_\_\_\_\_  
 SITE NUMBER: 311687  
 STORE NUMBER: 436563

**TACO BELL**  
 3923 SHAKEDOWN STREET  
 CHARLOTTE, NC 28216

**LIVE MAS**  
 MEDIUM 54  
**EROSION CONTROL PLAN**  
 C07  
 PLOT DATE: 2-09-18

Drawing name: P:\0901069 - TB Mt Holly Rd, Charlotte, NC\Cadd\Construction\C07 - TB MT HOLLY NC - EROSION PLAN.dwg by Ricardo Ramos Feb 09, 2018 1:12pm

Order Plans @ WVA

AREA OF DISTURBANCE = 0.725 ACRES