



PRIOE A WOOD NAILER TO MATCH THE THICKNESS OF THE WALL FINISH. APRROX. 1" THICK IS TYPICAL BUT MAY VARY. TOP OF WOOD NAILER SHALL BE FLUSH WITH 10P OF WALL FINISH. THE WOOD NAILER SHALL EXTRO AT LEAST 1/2" INCH BEYOND THE LOWER HORIZONTAL EDGE OF THE PARAPET COPING TO ALLOW FOR PROPER FASTENING.

- 2 FASTENERS USED TO ATTACH THE COPING TO WOOD NAILERS, MUST BE SPACED NO GREATER THAN 18 INCHES ON-CENTER.
- ALLOW FOR 1/8 INCH EXPANSION GAP BETWEEN 10-FOOT LENGTHS OF COPING. PROVIDE A COPING JOINT COVERS BETWEEN ENDS OF COPING PIECES AND AT CORNERS. JOINT COVERS SHOULD BE MADE FROM THE SAME MATERIAL AS THE COPING AND SHOULD LAP THE JOINTS A MINIMUM OF 6" ON EITHER SIDE. JOINT COVERS SHALL BE FASTENED THE SAME WAY AS THE COPING.
- 4 PRESSURE TREAT PLYWOOD SLOPED 1/4:12 TOWARDS ROOF
- 5 ROOF MEMBRANE WRAPPED OVER PARAPET UNDER COPING CAP.
- 6 FACTORY PAINTED 24 GAUGE METAL COPING WITH 4" DROP FRONT, BACK AND ENDS (WHERE SHOWN).
- 7 WALL FINISH: 1-1/2' THICK E.I.F.S.
- 8 DOUBLE 2X TOP PLATE
- 9 PLYWOOD SUBSTRATE. SEE SHEET A1.0 & S2.0 FOR ADDITIONAL



NOTE: G.C. TO PROVIDE BLOCKING AND INSTALL THE LADDER. - 1/8" MOLDED POLYURETHANE SAFETY CAPS 2-1/2" ALUMINUM CHANNEL SIDERAIL (6005-T5) 2-1/4" SERRATED ALUMINUM TREAD (6005-T5) AS REQ'D



ROOF LADDER N.T.S.





12144.400

CONTRACT DATE: 10.23.17 BUILDING TYPE: EXP. LITE MED40 PLAN VERSION: DECEMBER 2016 SITE NUMBER 311687 STORE NUMBER: 436563

TACO BELL

3923 SHAKEDOWN ST CHARLOTTE, NC



CONSTRUCTION DETAILS ROOF

A6.0