EQUIPMENT CONNECTION SCHEDULE

ITEM TAG	QTY	VOLTAGE/ PHASE	DESCRIPTION	CIRCUIT	BRANCH CIRCUIT WIRING	DEVICE	REMARKS
B-223	1	120/1	WATER HEATER IGNITION	D-29	2#12,1#12G; 3/4"C	MOTOR RATED SWITCH	
B-381	1	120/1	CO2 SENSOR	A-25	2#12,1#12G; 3/4"C	NEMA 5-20R	
C-026	1	120/1	DUAL VAT FRYER	A-40	2#12,1#12G; 3/4"C	NEMA 5-20R	
C-107	1	120/1	RETHERMALIZER	A-24	2#12,1#12G; 3/4"C	NEMA 5-20R	
C-400	1	120/1	TIMER	A-18	2#12,1#12G,1#12IG; 3/4"C	NEMA 5-20R	
E-107	1	120/1	HOOD FIRE SUPPRESSION SYSTEM	D-28	2#12,1#12G; 3/4"C EA	JUNCTION BOX	
F-040	1	120/1	OFFICE COMPUTER	A-15	2#12,1#12G; 3/4"C	NEMA 5-20R-IG	
F-050	2	120/1	CREDIT CARD ROUTER	A-38	2#12,1#12G; 3/4"C	NEMA 5-20R-IG	
F-080	1	120/1	OFFICE PRINTER/COPIER/ FAX SCANNER	A-14	2#12,1#12G,1#12IG; 3/4"C	NEMA 5-20R-IG	
F-090	4	120/1	UPS EQUIPMENT	A-10 A-16	2#12,1#12G,1#12IG; 3/4"C	NEMA 5-20R-IG	
F-131	1	120/1	MUSIC SYSTEM (MUZAK)	D-8	2#12,1#12G; 3/4"C	NEMA 5-20R-IG	
F-174	1	120/1	SAFE w/TOUCH SCREEN CNTRL	A-6	2#12,1#12G; 3/4"C	NEMA 5-20R	
L-043	1	120/1	DIGITAL MENU BOARD	A-39	2#12,1#12G; 3/4"C	NEMA 5-20R	
N-043	1	208/1	POWER SOAK	D-19/21	2#12,1#12G; 3/4"C	NEMA 6-15R	
N-145	2	120/1	AUTOMATIC FAUCET	A-33	2#12,1#12G; 3/4"C	NEMA 5-20R	
P-417	1	120/1	(8) CHANNEL TIMER	A-18	2#12,1#12G,1#12IG; 3/4"C	NEMA 5-20R	
P-452	2	208/1	HOT WATER DISPENSER	A-9/11 A-35/37	2#10,1#10G; 3/4"C	JUNCTION BOX	
R-009	1	120/1	FULL HEIGHT FREEZER	A-5	2#12,1#12G; 3/4"C	NEMA 5-20R	
S-026	1	120/1	HEATED CABINET	A-41	2#12,1#12G; 3/4"C	NEMA 5-20R	
S-027	1	120/1	HEATED CABINET	A-1	2#12,1#12G; 3/4"C	NEMA 5-20R	
S-204	1	120/1	D/T TIMING SYSTEM	[illegible]	2#12,1#12G; 3/4"C	NEMA 5-20R	
S-240	1	120/1	ORDER CONFIRMATION BRD/SWITCH BOX	A-21	2#12,1#12G; 3/4"C	JUNCTION BOX	REFER TO "HM-10" ON E5.0
S-264	1	120/1	BEVERAGE DISPENSER S/S	A-3	2#12,1#12G, 3/4"C	NEMA 5-20R	
S-285	1	120/1	BEVERAGE DISPENSER D/T	A-1	2#12,1#12G; 3/4"C	NEMA 5-20R	
S-286	1	120/1	WATER FILTER SYSTEM	B-17	2#12,1#12G, 3/4"C	NEMA 5-20R	
S-513	2	120/1	ICE MAKERS S/S & D/T (2)	D-10	2#12,1#12G; 3/4"C	NEMA 5-20R	
S-513	2	208/1	REMOTE CONDENSER S/S REMOTE CONDENSER D/T	D-13/14 D-15/16	2#10,1#10G, 3/4"C 2#10,1#10G; 3/4"C	NEMA L6-30R	
S-540	1	120/1	PEPSI BOOSTER TANK	A-2	2#12,1#12G; 3/4"C	NEMA 5-20R	
S-546	1	120/1	ICE TEA BREWER	A-26	2#12,1#12G; 3/4"C	NEMA 5-20R	
S-547	1	120/1	POD BREWER	A-36	2#12,1#12G; 3/4"C	NEMA 5-20R	
S-739	1	208/3	FROZEN BEV DISPENSER	D-40/42	2#10,1#10G; 3/4"C	NEMA L6-30R	
S-740	1	120/2	FROZEN BEV CONDENSER REMOTE UNIT	D-30/32	2#12,1#12G; 3/4"C	NEMA 5-20R	
U-011	1	120/1	BASE STATION-DT COMM SYSTEM	A-22	2#12,1#12G,1#12IG; 3/4"C	NEMA 5-20R-IG	
U-033	2	120/1	SECURITY SYSTEM	A-17	2#12,1#12G; 3/4"C	NEMA 5-20R	
U-054	1	120/1	CCTV & MONITOR	A-23	2#12,1#12G; 3/4"C	NEMA 5-20R-IG	
U-061	3	120/1	READER (VSAT)	A-10 A-38	2#12,1#12G; 3/4"C	NEMA 5-20R-IG	
U-070	3	120/1	RECEIPT PRINTER	A-4 A-10	2#12,1#12G; 3/4"C	NEMA 5-20R-IG	
U-100	4	120/1	POS ORDER ENTRY	A-4 A-16	2#12,1#12G,1#12IG, 3/4"C	NEMA 5-20R-IG	
U-238	5	120/1	KITCHEN MONITOR	A-32	2#12,1#12G; 3/4"C EA	NEMA 5-20R-IG	(1) MONITOR IS FED FROM CIRCUIT "A-32". (4) MONITORS ARE FED FROM COOKLINE PANEL
W-059-1	1	208/3	WALK-IN COOLER	D-1/3/5	3#12,1#12G; 3/4"C	JUNCTION BOX	REFER TO ROOF PLAN. PROVIDE ALL INTERCONNECTIVE WIRING BETWEEN INDOOR AND OUTDOOR UNIT PER MANUFACTURER'S RECOMMENDATIONS.
W-059-2	1	208/3	WALK-IN FREEZER	D-7/9/11	3#12,1#12G; 3/4"C	JUNCTION BOX	REFER TO ROOF PLAN. PROVIDE ALL INTERCONNECTIVE WIRING BETWEEN INDOOR AND OUTDOOR UNIT PER MANUFACTURER'S RECOMMENDATIONS.

GENERAL NOTE:
COORDINATE ALL RECEPTACLE AND DEVICE TYPES WITH MANUFACTURER RECOMMENDATIONS.

Order Plans @ WWW.LDLine.com

GLMV ARCHITECTURE, PLLC
1525 E. Douglas Wichita, KS 67211
Tel: (316) 265-9387 Fax: (316) 265-5846
www.glmv.com

DEVITA
ATLANTA • CHARLOTTE • GREENVILLE • RICHMOND
877.4.DEVITA • corp@devitainc.com
DeVita & Associates, Inc. Project: 17002-22
Drawn By: RAG Checked By: RAG
NC Firm License # C-0819

SEAL 042553 REGISTERED DIANA A. GRAY

12144.400

CONTRACT DATE: 10.23.17
BUILDING TYPE: EXP. LITE MED40
PLAN VERSION: DECEMBER 2016
SITE NUMBER: 311687
STORE NUMBER: 436563

TACO BELL
3923 SHAKEDOWN ST.
CHARLOTTE, NC

EXPLORER LITE
MEDIUM54

EQUIPMENT SCHEDULES

E2.2