ITEM NO.	QUANTITY	DESCRIPTION OF EQUIPMENT	APPROVED MANUFACTURER	MECHANICAL - ELECTRICAL						MECHANICAL - PLUMBING						ITEM NO.	REMARKS (ALL ITEMS BY CHICK-FIL-A UNLESS OTHERWISE NOTED)
				VOLT	PH	KW	AMP	HP	NEMA-RATING	HW	CW	FW	FW2	IW	ROUGH-IN		
101	1	SERVING COUNTER	CLAYTON FIXTURE													101	PLEASE REFER TO MANUFACTURER SHOP DRAWINGS
105	1	PASS-THRU COUNTER	CLAYTON FIXTURE													105	REFER TO MANUFACTURER SHOP DRAWINGS
105a	11	STAINLESS STEEL BIN HOLDER	CLAYTON FIXTURE MODEL #02099996													105a	LOCATED IN ITEM #105a - NOT SHOWN ON PLAN
105b	22	CONDIMENT BIN	INTERMETRO MODEL #SB91055CAS													105b	LOCATED IN ITEM #105a - NOT SHOWN ON PLAN
110	1	BACK BAR COUNTER	CLAYTON FIXTURE													110	REFER TO MANUFACTURER SHOP DRAWINGS
111	1	STAINLESS STEEL DROP-IN HAND SINK	CLAYTON FIXTURE											1 1/2"		111	PROVIDED IN MILLWORK PACKAGE
115	1	DRIVE-THRU CASH COUNTER	CLAYTON FIXTURE													115	PLEASE REFER TO MANUFACTURER SHOP DRAWINGS
116	1	BEVERAGE COUNTER	CLAYTON FIXTURE													116	PLEASE REFER TO MANUFACTURER SHOP DRAWINGS
117A	1	S/S CUSTOM FABRICATED TEA SHELF	ALL SOUTHERN FABRICATORS #7220													117A	USE (2) 18-8 SS MCMASTER-CARR 92351A552 HEX HEAD LAG SCREWS PER 3/16" PRE-DRILLED HOLE STUD ONLY, MIN 2" APART
119	3	MLOP COUNTER	PROVIDED BY CHI													119	REFER TO MANUFACTURER SHOP DRAWINGS
120	1	HOT HOLDING CENTER LINE TABLE	FRANKE MODEL #18008697	120/208	3	3.2	16		DIRECT CONNECTION							120	60 AMP SERVICE REQUIRED TO POWER TABLE & ADDITIONAL EQUIPMENT EXCEPT POS - ORDER W/ITEM #2780[illegible]
120a	1	COLD CENTER LINE TABLE	FRANKE MODEL #18008872	120/208	3	7.8	6.5		DIRECT CONNECTION							120a	60 AMP SERVICE REQUIRED TO POWER TABLE & ADDITIONAL EQUIPMENT EXCEPT POS - ORDER W/ITEM #27802290
120c	1	TOASTER CENTER LINE TABLE	FRANKE MODEL #18008738	120/208	3				DIRECT CONNECTION							120c	60 AMP SERVICE REQUIRED TO POWER TABLE & ADDITIONAL EQUIPMENT EXCEPT POS - ORDER W/ITEM #27802293
120d	1	CENTERLINE UNDERCOUNTER REFRIGERATOR	FRANKE MODEL #18008870	115	1	.58	5		NEMA 5-15R							120d	LOCATED UNDER ITEM #120a - FRANKE COLD TABLE CIRCUIT #1
121	1	WALL MOUNTED SOUP PACKAGING HOLDER	FRANKE MODEL #27802615													121	
125	1	SAFE COUNTER	CLAYTON FIXTURE													125	REFER TO MANUFACTURER SHOP DRAWINGS
130	1	LOCKABLE CLEANING SUPPLY CABINET	CLAYTON FIXTURE													130	PLEASE REFER TO MANUFACTURER SHOP DRAWINGS
135	1	DESK TOP	CLAYTON FIXTURE													135	REFER TO MANUFACTURER SHOP DRAWINGS
136	1	B.O.G. CABINET	CLAYTON FIXTURE													136	REFER TO MANUFACTURER SHOP DRAWINGS
138	1	COMPUTER NETWORK CABINET	CLAYTON FIXTURE													138	PLEASE REFER TO MANUFACTURER SHOP DRAWINGS
145A	2	CONDIMENT CONTAINER	CLAYTON FIXTURE													145A	PLEASE REFER TO MANUFACTURER SHOP DRAWINGS
145B	1	CONDIMENT CONTAINER	CLAYTON FIXTURE													145B	PLEASE REFER TO MANUFACTURER SHOP DRAWINGS
146	1	TRASH CONTAINER	CLAYTON FIXTURE													146	PLEASE REFER TO MANUFACTURER SHOP DRAWINGS
149	2	SNEAKER KEEPER BENCH	CLAYTON FIXTURE													149	PLEASE REFER TO MANUFACTURER SHOP DRAWINGS
150	3	BREAD RACK	LOCAL SUPPLIER													150	
180	8	ORDER REGISTER		120	1		0.7									180	PROVIDED BY CFA IT
180a	1	LCD ARM	INNOVATIVE													180a	USED TO MOUNT POS MONITORS; PROVIDED BY CFA IT
181	6	CASH DRAWER	APG MODEL #4000													181	PROVIDED BY CFA IT
182	7	RECEIPT PRINTER	EPSON MODEL #TM-T88IV	120	1		0.18									182	PROVIDED BY CFA IT
183	12	ORDER MONITOR	RADIANT KITCHEN PRODUCTION SYSTEM	120	1		0.125		NEMA 5-20R							183	PROVIDED BY CFA IT
183a	8	RADIAL ARM	INNOVATIVE MODEL #7000													183a	USED TO MOUNT ORDER REGISTERS; PROVIDED BY CFA IT
184	3	IPAD	APPLE	120	1	0.12	2.1		NEMA 5-20R							184	PROVIDED BY CFA IT
190	1	DRIVE-THRU VIDEO MONITOR	ACER MODEL #V173DJB	120	1				NEMA 5-20R							190	PROVIDED BY CFA IT
200A	3	SLIM LINE CUSTOM TEA DISPENSER	WILBUR CURTIS MODEL #TCN14040													200A	LOCATED ON ITEM #117A - ORDER (2) #TCN14040-SW [illegible] #TCN14040-[illegible]S
200S	3	SLIM LINE TEA DISPENSER	WILBUR CURTIS MODEL #TCN040													200S	LOCATED ON ITEM #200Sa - ORDER (2) #TCN040-SW [illegible] #TCN040-[illegible]S
200Sa	1	TEA STAND	CLAYTON FIXTURE													200Sa	
201	1	ICE CREAM CONE DISPENSER	PROVIDED BY OWNER													201	PROVIDED BY CFA WAREHOUSE
202	4	SLIM JIM TRASH CAN	RUBBERMAID MODEL #3540													202	PROVIDED BY CFA WAREHOUSE
202A	1	UNDERCOUNTER SLIM JIM TRASH CAN	RUBBERMAID MODEL #1971258													202A	PROVIDED BY CFA WAREHOUSE
205	4	HAND SANITIZER	GOJO MODEL #2730-PL													205	RE: ARCHITECTURAL SHEETS FOR DETAILS ON MOUNTING HEIGHTS AND LOCATIONS
206	4	SOAP DISPENSER	GOJO MODEL #2730-PL													206	RE: ARCHITECTURAL SHEETS FOR DETAILS ON MOUNTING HEIGHTS AND LOCATIONS
210	1	INGREDIENT BIN	RUBBERMAID MODEL #3602-88													210	PROVIDED BY CFA WAREHOUSE
211B	3	FLY SYSTEM	GENUS COBRA MODEL #107000-00	120	1	0.078	0.65		NEMA 5-15R							211B	CLOCK STYLE RECEPTACLE REQUIRED
211C	4	FLY SYSTEM	GENUS DISCREET MODEL #108500-00	120	1	0.03	0.25		NEMA 5-15R							211C	CLOCK STYLE RECEPTACLE REQUIRED
215	1	KEY CABINET	BLOCK & Co. MODEL #101903003													215	PROVIDED BY CFA WAREHOUSE
220	1	COAT RACK	SAFCO MODEL #x700-24in													220	FURNISHED BY OWNER
225	1	FAT VAT	PITCO FRIALATOR MODEL FAT VAT													225	PROVIDED BY CFA WAREHOUSE
230	4	HIGH CHAIR	RUBBERMAID MODEL #FG780508													230	PROVIDED BY CFA WAREHOUSE
240	2	BABY CHANGING STATION	RUBBERMAID MODEL #FG781888													240	PROVIDED BY CFA WAREHOUSE, RE: ARCHITECTURAL SHEETS FOR DETAILS ON MOUNTING HEIGHTS AND LOCATIONS
260	1	42" VENT HOOD + 3" AIR SPACE	HALTON HOODS													260	HOOD SHROUD BY VENT HOOD MANUFACTURER; REFER TO SHOP DRAWINGS
263	1	90" VENT HOOD	HALTON HOODS													263	HOOD SHROUD BY VENT HOOD MANUFACTURER; REFER TO SHOP DRAWINGS
266	1	151" VENT HOOD	HALTON HOODS													266	HOOD SHROUD BY VENT HOOD MANUFACTURER; REFER TO SHOP DRAWINGS
269	1	ANSUL FIRE SUPPRESSION SYSTEM	HALTON HOODS	120	1		VERIFY		DIRECT CONNECTION							269	LOCATED ABOVE HOOD - BEHIND CLOSURE PANEL; REFER TO SHOP DRAWINGS; FED FROM CFA-T500 PANEL
270	1	ANSUL FIRE SUPPRESSION SYSTEM	HALTON HOODS	120	1		VERIFY		DIRECT CONNECTION							270	REFER TO SHOP DRAWINGS; FED FROM CFA-T500 PANEL
300aR	1	MILKSHAKE BASE DISPENSER	EQUIPMENT TO BE REUSED/RELOCATED	120	1		4.0		NEMA 5-20R							300aR	MOUNTED ON ITEM # 300b
300bR	1	MILKSHAKE BASE DISPENSER SHELF	EQUIPMENT TO BE REUSED/RELOCATED													300bR	
300cR	2	SINGLE-SPINDEL MIXER	EQUIPMENT TO BE REUSED/RELOCATED													300cR	
300dR	1	TOPPING DISPENSER/HOLDER	EQUIPMENT TO BE REUSED/RELOCATED													300dR	
300XR	1	DOUBLE BARREL ICE CREAM MACHINE	EQUIPMENT TO BE REUSED/RELOCATED	208	3		19.0 / 15.0	1.5/1.5	VERIFY					1"		300XR	
301C	1	WIREWORKS CUP DISPENSER & LID ORGANIZER	SAN JAMAR MODEL #C8504WF													301C	
305	1	TEA BREWER	WILBUR CURTIS MODEL #TCTT10000	120	1	1.65	13.8		NEMA 5-20R			3/8"			P-24 @ 60" A.F.F.	305	QUICK DISCONNECT HOSES PROVIDED BY OWNER
305R	1	TEA BREWER	EQUIPMENT TO BE REUSED/RELOCATED	120	1	1.65	13.8		NEMA 5-20R			3/8"			P-24 @ 60" A.F.F.	305R	
308a	4	COFFEE WARMER	WILBUR CURTIS MODEL #TFT1G3040													308a	MOUNTED ON ITEM #308b - (2) NOT SHOWN ON DRAWINGS
308b	1	COFFEE WARMER STAND	QUADRA TECH MODEL #CFA3QDT008													308b	
308c	1	SLIM LINE ICED COFFEE DISPENSER	WILBUR CURTIS MODEL #TCN-3-5GAL													308c	
308d	1	DRY & DAIRY DISPENSER	SERVER MODEL #80091	120	1		1.0		NEMA 5-20R							308d	
308e	1	SYRUP RACK	MONIN MODEL #P573													308e	PROVIDED BY CFA WAREHOUSE
308R	1	SINGLE COFFEE MAKER	EQUIPMENT TO BE REUSED/RELOCATED	208	1	4.0	19.2		L14-30P			3/8"			P-24 @ 60" A.F.F.	308R	
309	1	SINGLE JUICE DISPENSER	SCHROEDER MODEL #900-0021	115	1		4.4		5-20P							309	
309R	1	SINGLE JUICE DISPENSER	EQUIPMENT TO BE REUSED/RELOCATED	115	1		4.4		5-20P							309R	
310R	1	DOUBLE JUICE DISPENSER	EQUIPMENT TO BE REUSED/RELOCATED	115	1		8.2		NEMA 5-20R							310R	
315W	4	10 HEAD DRINK TOWER/ICE BIN	LANCER #85-23710-111-07 MODEL 2300	120	1		10		(2)NEMA5-15R					3/4"		315W	PROVIDED WITH (2) CORDS & PLUGS PER TOWER
316	1	CO2 TANK	CHART INDUSTRIES													316	LOCATED IN MECH. ROOM - SECURE TO WALL WITH CHAIN
317	1	BEVERAGE RACK SYSTEM (6 SHELF - 6 WIDE)	PROFITMASTER MODEL #3PMD010													317	
318a	1	8-STOP WATER MANIFOLD PANEL	PB&J MODEL D									3/4"			P-28 @ 118" A.F.F.	318a	INSTALLED BY PLUMBING CONTRACTOR - RE: PLUMBING SHEETS FOR DETAILS
320	4	TURBO CARBONATOR	LANCER MODEL #85-1923-03	120	1		6.2		NEMA 5-20R							320	ORDER (6) #44231, (2) #44233, (6) DR. PEPPER PUMPS, & (2) #T5274SN-01
350	1	WATER FILTER SYSTEM	SELECTO SCIENTIFIC T1 FILTER SYSTEM MODEL #80-6203CFB								1"	3/4"	1/2"		SEE PLUMBING SHEETS	350	RE: PLUMBING SHEETS FOR DETAILS
355F	1	FAUCET FOR DECK MOUNTED HAND SINK	T&S MODEL #B-0328-CR-VF05							1/2"	1/2"				P-6 @ 18" & 19" A.F.F.	355F	INCLUDED IN T&S KIT #B-2495-CFA
359	3	WALL MOUNTED SPLASH GUARD	ATLANTA CUSTOM FABRICATORS #3ACF114													359	RIGHT HAND MOUNT - 12" HIGH x 24" WIDE S/S WALL MOUNTED SIDE SPLASH W/HEMMED EDGE
359L	2	WALL MOUNTED SPLASH GUARD	ATLANTA CUSTOM FABRICATORS #3ACF051													359L	LEFT HAND MOUNT - 12" HIGH x 24" WIDE S/S WALL MOUNTED SIDE SPLASH W/HEMMED EDGE
360	3	HAND SINK	EAGLE MODEL #HSAN-10											1 1/2"		360	WITH SIDE MOUNTING BRACKETS
360F	3	FAUCET FOR WALL MOUNTED HAND SINK	T&S MODEL #B-1146-CFA-VF05							1/2"	1/2"				P-5 @ 24" & 25" A.F.F.	360F	(2) INCLUDED IN T&S KIT #B-2495-CFA
365a	1	4 COMPARTMENT SINK CHEMICAL DISPENSER	SOLIDSENSE													365a	PROVIDED BY OPERATOR
365F	1	FAUCETS FOR UTENSIL SINK	T&S MODEL #B-0152-14-CRBCT; B2299-CR							1/2"	1/2"				P-9 @ 12" A.F.F.	365F	INCLUDED IN T&S KIT #B-2495-CFA, HW (2), CW (2)
365R	1	4 COMPARTMENT UTENSIL SINK	EQUIPMENT TO BE REUSED/RELOCATED											1 1/2"		365R	
367	1	DOUBLE BOWL VEGETABLE PREP SINK	EAGLE GROUP MODEL #YCFA-0039-00											1 1/2"		367	WITH 16" CENTER DRAIN BOARD - PROVIDE (2) FISHER #22209 DRAINS W/FLAT STRAINERS
367a	1	VEGETABLE WASH DISPENSER	ECOLAB													367a	PROVIDED BY OPERATOR
367F	1	FAUCET FOR VEGETABLE PREP SINK	T&S MODEL #B-0154-14-CR-BC							1/2"	1/2"				P-8 @ 12" A.F.F.	367F	INCLUDED IN T&S KIT #B-2495-CFA
367FW	1	FILTERED WATER FAUCET (WALL MOUNTED)	T&S MODEL #B-0236-CR-063X									1/2"			(2) P-30 @ 48" A.F.F.	367FW	(2)FW - INCLUDED IN T&S KIT #B-2495-CFAR
370	1	MOP SINK	BUILT IN BY GC							1/2"	1/2"			3"	(2) P-7 @ 36" A.F.F.	370	SUNKEN 24"x 36" - WALL @ (3) SIDES/STAINLESS STEEL WALL PANEL TO 42" AFF
370a	1	MOP SINK ACCESSORIES	SOLIDSENSE													370a	
380	1	ICE BIN	FOLLETT MODEL #SG[illegible]-60											1"		380	ORDER WITH ITEM #380a
380a	1	ICE BIN SANITATION SYSTEM	BIOZONE MODEL #IZ-X-[illegible]	120	1	0.0096			5-15P							380a	INSTALLED ON WALL ABOVE ITEM #380 ON LEFT - SHARES DUPLEX WITH (1) ITEM #380Z
380Z	2	ICE MACHINE	FOLLETT HORIZON CHEWBLET MODEL #[illegible]50RBT	115	1		6.0		5-15P				1/2"	3/4"	P-23 @ 69" & 85" A.F.F.	380Z	INSTALLED ON ITEM #380 - PROVIDE WITH 35' LINE SETS
380ZC	2	ICE MACHINE REMOTE CONDENSING UNIT	FOLLETT HORIZON CHEWBLET	208	3		21.2		DIRECT CONNECTION							380ZC	AIR COOLED UNIT - G.C. SHALL PLACE & INSTALL CONDENSER ON ROOF - NOT SHOWN ON DRAWINGS
400R	1	SINGLE SECTION REACH-IN FREEZER	EQUIPMENT TO BE REUSED/RELOCATED	115	1		9.4	.5	5-15P							400R	
402	1	FREEZER/WORK TABLE	TRAULSEN MODEL #ULT60-ZCF-[illegible]	120	1		7.3		NEMA L5-20R							402	ELECTRICIAN TO CHANGE PLUG TO TWIST LOCK; ORDER WITH WORKTOP, BACKSPLASH, AND 6" CASTERS
410	1	WALK-IN FREEZER	THERMOKOOL	120	1		3.3		DIRECT CONNECTION							410	REFER TO LIGHTING PLAN
410a	1	WALK-IN FREEZER CONDENSER	THERMOKOOL	208	3		14.38	3	DIRECT CONNECTION							410a	G.C. SHALL INSTALL CONDENSER ON ROOF - NOT SHOWN ON DRAWING
410b	1	WALK-IN FREEZER EVAPORATOR	THERMOKOOL	208	1	.177	1.5		DIRECT CONNECTION					3/4"		410b	POWER FED FROM CONDENSER
420LR	1	SINGLE UNDERCOUNTER REFRIGERATOR	EQUIPMENT TO BE REUSED/RELOCATED	115	1	.564	4.7	.2	5-20P							420LR	
421	1	DOUBLE UNDERCOUNTER REFRIGERATOR	TRAULSEN MODEL #UHT48-ZCF-LR	115	1	.756	6.3	.2	5-20P							421	ORDER ON 4" CASTERS
421R	1	DOUBLE UNDERCOUNTER REFRIGERATOR	EQUIPMENT TO BE REUSED/RELOCATED	115	1	.756	6.3	.2	5-20P							421R	
431	1	DOUBLE REFRIGERATED WORK TABLE	TRAULSEN MODEL #UHT48-ZCF-LR	115	1	.756	6.3	.2	NEMA 5-20R							431	ORDER WITH WORKTOP, BACKSPLASH, AND 6" CASTERS
432	2	DOUBLE REFRIGERATED WORK TABLE	TRAULSEN MODEL #UHT60-ZCF-LR	115	1	0.756	6.3	.2	L5-20P							432	E.C. TO CHANGE PLUG TO TWIST LOCK - ORDER ON 6" CASTERS WITH BACKSPLASH TOP
440R	1	BREADING TABLE	EQUIPMENT TO BE REUSED/RELOCATED	115	1		12.0	.5	L5-20P (BY E.C.)							440R	ELECTRICIAN TO CHANGE PLUG TO TWIST LOCK IF NEEDED - FIELD VERIFY EXISTING PLUG
441	1	[illegible] PREP TABLE	TRAULSEN MODEL #TS090HT-ZCF01	120	1		9.0		NEMA 5-15R							441	PROVIDE WITH TWIST LOCK PLUG; ORDER ON 4" CASTERS WITH PAN PKG.; SESC TO PROVIDE PAN PKG.
444R	2	THAWING CABINET - DOUBLE	EQUIPMENT TO BE REUSED/RELOCATED	115	1		16.0	.5	DIRECT CONNECTION							444R	CONVERT TO DIRECT CONNECT IF NEEDED - GC TO INSTALL LIQUID TIGHT FLEX CONDUIT
444S(r)	1	THAWING CABINET-SINGLE - Right Hand	TRAULSEN MODEL #RET132EWUT-FHS	120	1		16.0		DIRECT CONNECTION							444S(r)	CONVERT TO DIRECT CONNECT IF NEEDED-GC TO INSTALL LIQUID TIGHT FLEX CONDUIT,HINGE RIGHT
449	1	WALK-IN COOLER	THERMOKOOL	120	1		2.4		DIRECT CONNECTION							449	REFER TO LIGHTING PLAN
449a	1	WALK-IN COOLER CONDENSER	THERMOKOOL	208	3		5.75	1	DIRECT CONNECTION							449a	G.C. SHALL INSTALL CONDENSER ON ROOF - NOT SHOWN ON DRAWING
449b	1	WALK-IN COOLER EVAPORATOR	THERMOKOOL	208	1	.118	1.0		DIRECT CONNECTION					3/4"		449b	POWER FED FROM CONDENSER

Order Plans @ WWW.LDILine.com - FOR BID ONLY - FOR BID ONLY - FOR BID ONLY -

Chick-fil-A
5200 Buffington Road
Atlanta, Georgia
30349-2998

TriMark
Foodservice Equipment, Supplies and Design
STRATEGIC

CHICK-FIL-A
SOUTH COBB DRIVE
3100 South Cobb Dr SE, Smyrna GA 30080

FSR# 00810

REVISION SCHEDULE

NO.	DATE	DESCRIPTION

CURRENT TEMPLATE UPDATE APPLIED	SO8-V6
ARCHITECT'S PROJECT #	00810
PRINTED FOR	BID
DATE	02/05/2018
DRAWN BY	

Information contained on this drawing and in all digital files produced for above named project may not be reproduced in any manner without express written or verbal consent from authorized project representatives.

SHEET
EQUIPMENT SCHEDULE

SHEET NUMBER
K-201

BID

2/5/2018 4:30:29 PM