

NOTE:
THIS PLAN IS PART OF AN OVERALL SET OF PLANS. THIS SHEET IS CONSIDERED INVALID UNLESS ACCOMPANIED BY ALL OTHER DRAWINGS IN THE SET OF PLANS ON THE JOB SITE OR FOR BIDDING PURPOSES. THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A COMPLETE SET OF PLANS TO ALL THOSE CONDUCTING WORK ON THIS PROJECT.

- HERNANDO COUNTY UTILITY NOTES:**
1. CONTRACTOR TO SCHEDULE A PRE-CONSTRUCTION MEETING FIVE (5) BUSINESS DAYS PRIOR TO THE START OF OFF-SITE UTILITY CONSTRUCTION. CONTRACTOR MUST PROVIDE ALL UTILITY SUBMITTALS TO THE HCUO INSPECTOR FOR REVIEW AND APPROVAL A MINIMUM OF THREE (3) BUSINESS DAYS PRIOR TO THE PRE-CONSTRUCTION MEETING. HCUO INSPECTOR MUST ATTEND THE PRE-CONSTRUCTION MEETING.
 2. CONTRACTOR TO NOTIFY HCUO INSPECTOR 48 HOURS PRIOR TO UTILITY CONSTRUCTION IN THE COUNTY RIGHT-OF-WAY. HCUO INSPECTOR MUST BE PRESENT FOR ALL WATER AND SEWER CONNECTIONS.
 3. CONSTRUCTION WATER TO BE PROVIDED BY A TEMPORARY CONSTRUCTION WATER METER INSTALLED BY HCUO ON THE CLOSEST FIRE HYDRANT TO THE SITE. CONTRACTOR TO CONTACT HCUO'S COMMERCIAL CUSTOMER SERVICE DIVISION TO SIGN UP FOR SERVICE, IF CONSTRUCTION WATER IS REQUIRED.
 4. ENGINEER/DEVELOPER/CONTRACTOR/OWNER TO COMPLETE AND DEDICATE ALL OFFSITE WATER AND SEWER INFRASTRUCTURE TO HERNANDO COUNTY UTILITIES DEPARTMENT (HCUO). CONTACT HCUO TO OBTAIN THE CONTRIBUTED ASSET FORM.
 5. ALL NEW UTILITY CONSTRUCTION PROCEDURES & MATERIALS SHALL MEET OR EXCEED HERNANDO COUNTY UTILITIES DEPARTMENT POTABLE WATER, RECLAIMED WATER & WASTEWATER CONSTRUCTION SPECIFICATIONS MANUAL, LATEST EDITION AS AVAILABLE ON THE INTERNET @ www.hernandocounty.us/utilities/engineering
 6. HERNANDO COUNTY UTILITIES DEPARTMENT SHALL NOT OWN, OPERATE, OR MAINTAIN ON-SITE WATER AND/OR SEWER UTILITIES LOCATED OUTSIDE OF DEDICATED UTILITY EASEMENTS.
 7. THE HERNANDO COUNTY UTILITY DEPARTMENT (HCUO) IS NOT RESPONSIBLE FOR ON-SITE DAMAGE ASSOCIATED WITH THE MAINTENANCE OR REPAIR OF ANY HCUO OWNED INFRASTRUCTURE. THE OWNER/DEVELOPER IS RESPONSIBLE FOR ALL REPAIRS AND REPLACEMENT TO EXISTING LANDSCAPING, CURBING, ASPHALT, CONCRETE, ETC.
 8. HCUO OWNED INFRASTRUCTURE: HCUO PERSONNEL MUST BE PRESENT TO PHYSICALLY VERIFY THAT THE INSTALLATION OF ALL PIPE FITTINGS HAS BEEN DONE PER PLAN BEFORE BURYING. THESE FITTINGS SHALL INCLUDE BUT NOT LIMITED TO: COUPLING, RESTRAINT, TEE, 90, 45, 22, 11, AIR RELEASE AND ANY DIMENSIONS FROM A STRAIGHT PIPE RUN. THE HOURS FOR THESE INSPECTIONS SHALL BE BETWEEN 9 AM AND 4 PM. IF HCUO HAS NOT INSPECTED THE FITTING BEFORE BURYING THE CONTRACTOR WILL BE RESPONSIBLE FOR UNCOVERING FOR INSPECTION.

NOTE:
WET TAPS, SERVICE LINES, AND WATER METERS SHALL BE INSTALLED BY HCUO

GRADING UTILITIES

- POINT OF CONNECTION
- EXISTING/PROPOSED WATER LINE
- EXISTING/PROPOSED SEWER LINE
- EXISTING/PROPOSED FORCE MAIN
- EXISTING/PROPOSED REUSE
- EXISTING/PROPOSED STORM SEWER LINE
- EXISTING/PROPOSED OVERHEAD UTILITIES
- EXISTING/PROPOSED UNDERGROUND UTILITY LINES
- EXISTING/PROPOSED POWER POLE
- SITE LIGHTS - REFER TO OTHER PLANS FOR SPECIFICATIONS
- EXISTING/PROPOSED FIRE HYDRANT ASSEMBLY
- EXISTING/PROPOSED FIRE DEPARTMENT CONNECTION
- EXISTING/PROPOSED WATER METER
- EXISTING/PROPOSED IRRIGATION METER
- EXISTING/PROPOSED DOUBLE DETECTOR CHECK VALVE ASSEMBLY (DDCVA)
- EXISTING/PROPOSED GATE VALVE
- EXISTING/PROPOSED SANITARY MANHOLE
- EXISTING/PROPOSED SANITARY CLEANOUT
- EXISTING/PROPOSED GRADED INLET - REFER TO GRADING PLAN
- EXISTING/PROPOSED JUNCTION BOX - REFER TO GRADING PLAN
- PROPOSED CURB INLET - REFER TO GRADING PLAN
- EXISTING/PROPOSED MITERED END SECTION - REFER TO GRADING PLAN

Revisions	No.	Date	By
1	02/12/18	AVF	
2		AVF	
3		AVF	
4		AVF	

Project No.	Scale	Date
10/21/17		

CADD Tech	AVF
Designer	AVF
Engineer	SAL

PALMETTO CAPITAL GROUP, INC.
L.A. Civil, Inc.
Certificate of Authorization # 00029995
PO BOX 7649
Clearwater, Florida 33758-7649
Phone: 727-446-9000

DOLLAR GENERAL
SEC US 19 AND PINE FOREST DRIVE
HERNANDO COUNTY, FL

UTILITIES SITE PLAN

PROJECT TITLE

SHEET TITLE

SHEET No.
C5.1

- ITEMS REQUIRED FOR HCUO FINAL INSPECTION APPROVAL (FOR CERTIFICATE OF OCCUPANCY):**
- INSTALLATION AND INSPECTION OF AN HCUO APPROVED REDUCED PRESSURE ZONE BACKFLOW PREVENTION ASSEMBLY (RPZ-BPA) FOR POTABLE AND IRRIGATION SERVICES.
 1. INSTALLED PER CURRENT HCUO BACKFLOW PREVENTION ASSEMBLY DETAIL #8 & TESTED BY A LICENSED PLUMBER / FIRE CONTRACTOR. TEST RESULTS PROVIDED TO HCUO'S BPA COORDINATOR.
 2. CONTACT HCUO'S BPA COORDINATOR AT (352) 254-4802 FOR INSPECTION. THIS INSPECTION IS SEPARATE FROM THE PLUMBING INSPECTION SCHEDULED WITH THE DEVELOPMENT (BUILDING DEPARTMENT).
 - SUBMIT COMPLETE CONTRIBUTED ASSET FORM WITH ITEMIZED MATERIAL COST LIST FOR REVIEW AND APPROVAL.
 - SUBMIT (2) SETS OF 2" RECORD DRAWINGS AND (2) SETS OF AUTOCAD RECORD CO'S. (BUILT DATA MUST BE SHOWN ON THE ORIGINAL UTILITY PLAN SUBMITTED FOR BUILDING DEPARTMENT APPROVAL AND MUST BE DRAWN PER PROVID88 AND NA083 STATE PLANE COORDINATE SYSTEM).
 - PERFORM BACTERIOLOGICAL AND PRESSURE TEST, AS REQUIRED BY HCUO AND FDEP.

