

ST	PROJECT NUMBER	SHEET NO.	TOTAL SHEETS
GA.	T.O. 16-024	6	68

DUDLEY LANE SUMMARY OF QUANTITIES			
Item Number	Unit	Item Description	Quantity
150-1000	LS	TRAFFIC CONTROL	1
163-0232	AC	TEMPORARY GRASSING	1
163-0550	EA	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	6
165-0010	LF	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	4210
165-0105	EA	MAINTENANCE OF INLET SEDIMENT TRAP	6
167-1000	EA	WATER QUALITY MONITORING AND SAMPLING	2
167-1500	MO	WATER QUALITY INSPECTIONS	8
165-0001	LF	COMPOST FILTER SOCK	250
171-0010	LF	TEMPORARY SILT FENCE, TYPE A	4210
210-0100	LS	GRADING COMPLETE PROJECT	1
310-5120	SY	GR AGGR BASE CRS, 1 1/2 INCH, 1 1/2 INCH MATL	1425
402-3103	TN	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	20
441-0016	SY	DRIVEWAY CONCRETE, 6 IN TK	710
441-0104	SY	CONCRETE SIDEWALK, 4 IN (INCLUDES DETECTABLE WARNING SURFACE)	1600
441-0220	LF	CONCRETE VALLEY GUTTER, 6 IN	240
441-0221	LF	CONC HEADER CURB/WALL	430
441-6000	LF	CONC CURB & GUTTER, 6 IN X 24 IN, TP 2	4300
500-3201	CY	MORTAR RUBBLE MASONRY GRAVITY WALL - WALL NO. 3	30
500-3201	CY	CLASS B CONC RETAINING WALL - WALL NO. 1A AND 1B	35
500-3201	CY	CLASS B CONC RETAINING WALL WITH SIDEWALK (INCLUDES REBAR)	20
500-3900	CY	CLASS B CONC INCL REINF STEEL FOR TURN DOWN SIDEWALK	130
500-9999	CY	CLASS B CONCRETE, BASE OR PVMT WIDENING	85
607-0001	SF	STONE FACING - WALL NO. 1A AND 1B	750
607-0002	SF	STONE CAP - WALL NO. 1A AND 1B	240
607-0001	SF	STONE FACING - WALL NO. 2	300
607-0002	SF	STONE CAP - WALL NO. 2	220
607-0003	SF	STONE CAP - WALL NO. 3	120
608-4001	SF	BLOCK WALL FOR TREES IN SLOPE	200
611-8120	EA	ADJUST/ RELOCATE EXIST WATER VALVE/WATER METER TO GRADE	28
636-1033	SF	HIGHWAY SIGNS, TP1 MATL, REFL SHEETING, TP 9	27
636-2070	LF	GALV STEEL POSTS, TP 7	60
643-8200	LF	BARRIER FENCE (ORANGE), 4 FT - TREE PROTECTION	3900
643-8300	LF	DECORATIVE FENCE	410
653-1704	LF	THERMOPLASTIC SOLID TRAF STRIPE, 24 IN, WHITE	24
653-1804	LF	THERMOPLASTIC SOLID TRAF STRIPE, 8 IN, WHITE	852
668-1100	EA	CATCH BASIN, GP 1	4
670-0001	EA	RELOCATE EXIST MAILBOX	8
700-7000	TN	AGRICULTURAL LIME	1
700-7010	GL	LIQUID LIME	200
700-8000	TN	FERTILIZER MIXED GRADE	1
700-8100	LB	FERTILIZER NITROGEN CONTENT	200
700-9300	SY	SOD	675
708-9025	SY	LANDSCAPE MULCH	525
900-0039	SF	BRICK PAVERS	500
900-0040	SF	DECORATIVE DRIVEWAY FLAGSTONE	275
900-0041	SF	DECORATIVE DRIVEWAY BRICK PAVERS	250
999-0001	EACH	RECONSTRUCT EXISTING IRRIGATION SYSTEM	19
999-9000	ALLOW	MISCELLANEOUS CONSTRUCTION ALLOWANCE	1

THE CONTRACTOR IS RESPONSIBLE TO VERIFY ALL QUANTITIES OF THE ITEMS TO CONSTRUCT THE PROJECT AS INDICATED IN THE CONSTRUCTION DRAWINGS. THIS MAY INCLUDE THE CONSTRUCTION OF ITEMS NOT PRESENT IN THE DETAILED ESTIMATE OF THE SUMMARY OF QUANTITIES OR THE BID SCHEDULE UNIT PRICES.

M:\COSS - Task Order 16-024 - Dudley Lane Sidewalk Project\CAD\06 SUMMARY OF QUANTITIES.dwg Mar 19, 2018 - 3:05pm hage8741

PROPERTY AND EXISTING R/W LINE  
 REQUIRED R/W LINE  
 CONSTRUCTION LIMIT  
 EASEMENT FOR CONSTRUCTION  
 & MAINTENANCE OF SLOPES  
 EASEMENT FOR CONSTR OF DRIVES  
 HISTORICAL PARCEL  
 BEGIN LIMIT OF ACCESS  
 END LIMIT OF ACCESS  
 EXIST. LIMIT OF ACCESS  
 REQ'D R/W & LIMIT OF ACCESS

**ATKINS**  
 1600 RIVEREDGE PARKWAY, NW  
 SUITE 700  
 ATLANTA, GEORGIA 30328  
 770-933-0280

**SANDY SPRINGS**  
 GEORGIA

**ATKINS**  
 JOB NO. 100051166  
 DRAWN RTD  
 DESIGNED JDB  
 CHECKED JDB  
 QC

NOT VALID FOR CONSTRUCTION  
 UNLESS SIGNED IN THIS BLOCK

DATE	REVISIONS
02-29-18	# 1 - STA. 139+50.00 - 143+20.67 LEFT

CITY OF SANDY SPRINGS  
 PUBLIC WORKS

**SUMMARY OF QUANTITIES**

DUDLEY LANE SIDEWALK  
 PROJECT (T.O. 16-024)

DRAWING NO.  
 6-01