

ELEVATION GENERAL NOTES:


- REFER TO EXTERIOR MATERIAL AND FINISH SCHEDULE (GARDEN GRILL) ON SHEET A2.3
- G.C. TO PROVIDE PRE-FORMED CORNERS AT ALL NEW FIBER CEMENT FINISH AREAS.
- REMOVE / MOVE EXIST. SECURITY CAMERAS AS REQ'D FOR NEW FINISH INSTALLATION. REINSTALL CAMERAS ONCE WORK IS COMPLETE. COORD. W/ SECURITY VENDOR & OWNER.
- EXISTING EIFS TO RECEIVE **NEW RE-COATING**, TYP.
- REMOVE & REPLACE EXISTING OUTDOOR LIGHTING. SEE ELEVATIONS FOR NEW LOCATIONS.
- EXTERIOR LIGHT FIXTURES TO BE SET AT 10'-0" A.F.F., U.S.A.O.

X ELEV. DEMO. KEYNOTES:


- REMOVE EXIST. SIGNAGE - SIGNS TO BE RETURNED TO OWNER. TO USE CARE IN REMOVAL TO PREVENT DAMAGE.
- REMOVE EXISTING MANSARD ROOF - DOWN.
- EXISTING DOWNSPOUTS TO BE REMOVED. PREPARE FOR REPLACEMENT.
- ALL EXISTING MTL. COPING TO BE REMOVED AND REPLACED WITH NEW PRE-FINISHED MTL. COPING.
- EXISTING STOREFRONT WINDOWS TO BE CLEANED & REPAIRED AS NEEDED. TYP. NO. ONLY EXISTING STOREFRONT WINDOWS W/ BROKEN GLAZING AND/OR GLAZING WITH CORROSION INSIDE TO BE REPLACED INSTEAD. REMOVE EXIST. MTL. OVERFLOW SLEEVES & PREPARE FOR NEW EXTENDED. SEE ROOF PLAN.
- REMOVE EXIST. DECORATIVE LIGHT BAND - LIGHT BAND TO BE RETURNED TO OWNER. G.C. TO USE CARE IN REMOVAL TO PREVENT DAMAGE TO EXIST.
- THIS UNIT OF EXIST. STOREFRONT TO BE REMOVED AND PREPARED TO HAVE OPENING INFILLED.
- REMOVE EXISTING COLUMNS & COLUMN BRICK COMPLETELY FOR DRIVE-THRU CANOPY.
- EXIST. DRIVE-THRU WINDOW TO REMAIN. REPAIR DAMAGED SECTIONS AND PREPARE SURFACE FOR NEW STONE TOWER.
- REMOVE EXISTING EXTERIOR LIGHTING.
- REMOVE ROTTED PORTIONS OF WOOD TRIM COLUMNS ALONG EXTERIOR WALLS. TYP. EXTENT/LINE OF REMOVAL TO MATCH WAINSCOT/NEW PAINT LINE.

X ELEV. CONST. KEYNOTES:


- NEW LIGHT BAND BY SIGN VENDOR - G.C. TO PROVIDE BLOCKING. G.C. TO RE-SEAL EXISTING ELECTRICAL OPENINGS AND ENSURE THAT ALL NEW LIGHT-BANDS HAVE SEALANT AT ALL / ANY PENETRATIONS.
- NEW SIGN(S) - G.C. TO PROVIDE POWER AND BLOCKING. PROVIDE SEALANT BETWEEN WALL SURFACE AND BACK OF SIGN.
- NEW DK. BRONZE ALUMINUM STOREFRONT DOOR.
- PROVIDE CONTROL JOINTS EQUALLY SPACED AS SHOWN - SEE 05/A2.1. REFER TO GENERAL NOTES REGARDING EIFS, THIS PAGE.
- NEW SCONCE LIGHTS - DK. BRONZE TO MATCH ALUM. STOREFRONT.
- NEW EXTENDED OVERFLOW SLEEVES, PAINTED TO MATCH EF-1G.
- REPLACE W/ NEW WOOD TRIM TO MATCH EXISTING AT PORTIONS OF WALL WHERE ROTTED PORTIONS ARE REMOVED. CAULK/FILL JOINTS BEFORE PAINTING FOR CONTINUOUS SMOOTH FINISH.
- NEW DOWNSPOUT LEADER; FIELD VERIFY TOTAL NUMBER & LOCATIONS.
- CANOPY PROVIDED BY OWNER & INSTALLED BY G.C. PROVIDE POWER FOR LIGHTS. COORDINATE W/ SITE PLAN.
- PROVIDE NEW COLUMN CAPS @ EXIST. COLUMNS - PREFINISHED METAL.




04 REAR CONSTRUCTION
A2.2 SCALE: 3/16" = 1'-0"



03 REAR DEMOLITION
A2.2 SCALE: 3/16" = 1'-0"



02 DRIVE-THRU SIDE CONSTRUCTION
A2.2 SCALE: 3/16" = 1'-0"



01 DRIVE-THRU SIDE DEMOLITION
A2.2 SCALE: 3/16" = 1'-0"

Order Plans @ WWW.LDILINC.COM

NO.	DATE	BY	FOR	REVISION
01	05/11/18	LDI	PERMIT SET	
02				
03				
04				
05				
06				
07				



PREMIER HOLDINGS OF GEORGIA, LLC
3636 Stewart Road, Unit A
Doraville, GA 30090

2124 North Avenue
Atlanta, GA 30303
Phone: (770) 322-1751
Fax: (770) 322-1778
email: info@hplha.com
www.hplha.com

James M. Huxester architect AIA
architecture • planning • interior design



PROJECT #1702615
Burger King
998 SUNSET BLVD.
JESUP, GA 31545
EXTERIOR ELEVATIONS