


GENERAL HVAC NOTES:

- COORDINATE DIFFUSER LOCATIONS WITH REFLECTED CEILING PLAN INCLUDING LIGHTS AND SPRINKLER HEAD LAYOUTS.
- PROVIDE DUCT MOUNTED SMOKE DETECTORS IN SUPPLY AND RETURN AIR DUCTS AS INDICATED ON THE FLOOR PLAN. DUCT DETECTORS SHALL BE PROVIDED AND INSTALLED IN THE DUCTWORK BY THE MECHANICAL CONTRACTOR AND WIRED BY THE ELECTRICAL CONTRACTOR. DETECTORS SHALL BE COMPATIBLE WITH THE BUILDING FIRE ALARM SYSTEM AND INSTALLED PER MANUFACTURER'S INSTRUCTIONS.
- COORDINATE DUCTWORK MOUNTING HEIGHT AND LOCATION WITH STRUCTURAL STEEL AND LIGHTS. MOUNT DUCTWORK AS HIGH AS POSSIBLE.
- TEMPERATURE AND HUMIDITY SENSORS ARE SHOWN FOR REFERENCE ONLY. AN ENERGY MANAGEMENT SYSTEM IS BEING PROVIDED. BY SIEMENS, UNDER A SEPARATE CONTRACT BY THE OWNER. THE EMS SHALL BE INSTALLED BY THE REFRIGERATION CONTRACTOR AND THE MECHANICAL CONTRACTOR SHALL COORDINATE WORK WITH THE ALDI PROJECT MANAGER, SIEMENS PROJECT MANAGER, AND REFRIGERATION CONTRACTOR. 512-903-3169. REFERENCE THE SIEMENS EMS DRAWINGS LOCATED ON THE SHARENOLOGY.COM WEBSITE IN THE VENDOR INFORMATION FOLDER.
- ALL DUCT DIMENSIONS REPRESENT FREE AREA.
- ALL MITERED ELBOWS & FITTINGS TO BE PROVIDED WITH TURNING VANES.
- ALL ROUND DUCTWORK SHALL BE SPIRAL ONLY.
- PROVIDE VOLUME DAMPERS AT ALL RETURN REGISTER TAKEOFFS.
- MAXIMUM FLEX DUCT LENGTH SHALL BE 4FT. FLEX DUCT ALLOWED ONLY ON CONCEALED DUCTWORK INSTALLED ABOVE A CEILING.
- FIELD VERIFY ALL NEW EQUIPMENT AND SCOPE OF WORK PRIOR TO BIDDING. NOTIFY OWNER IN WRITING 48 HOURS PRIOR TO BID DATE OF ANY QUESTIONS ON SCOPE OF WORK OR CONTRACT DOCUMENTS.
- PROVIDE 1 1/2" PVC CONDENSATE DRAIN & P-TRAP FOR ALL ROOFTOP UNITS.
- PROVIDE ACOUSTICAL INSULATION INSIDE ROOFTOP UNIT CURB FOR SOUND ATTENUATION. (TYPICAL)
- INSULATE ALL DUCTWORK CONCEALED ABOVE A CEILING AND EXPOSED IN THE BACK ROOM. SEE SPECIFICATION SECTION 230700 - HVAC INSULATION FOR DETAILS.

HVAC PLAN KEYNOTES:

- (H1) ALUMINUM SPIRAL DUCT MOUNTED SUPPLY GRILLE WITH DAMPER/EXTRACTOR MOUNTED ON SIDE OF DUCT. ADJUST HORIZONTAL DEFLECTORS TO 22.5° DOWNWARD FROM THE HORIZONTAL POSITION.
- (H2) DISCHARGE AIR TEMPERATURE SENSOR. SENSORS, WIRING AND CONDUIT SHALL BE PROVIDED AND INSTALLED BY OTHERS.
- (H3) DUCT MOUNTED SMOKE DETECTOR.
- (H4) 8X8 EXHAUST UP TO EF-1 LOCATED ON ROOF.
- (H5) 14X14 EXHAUST UP TO EF-2 LOCATED ON ROOF AND EXTENDED 1'-8" INTO SPACE. PROVIDE 18X18 WELDED DRAIN PAN BELOW DUCT OPENING.
- (H6) 10X10 EXHAUST UP TO EF-3 LOCATED ON ROOF.
- (H7) MOUNT BOTTOM OF UNIT HEATER AT A MINIMUM OF 10'-6" AFF.
- (H8) PENDENT MOUNT TEMPERATURE SENSOR/DIGITAL ZONE CONTROLLER AT REAR OF UNIT HEATER AT 10'-6" AFF.
- (H9) RUN SUPPLY DUCT BETWEEN ROOF JOISTS AND THROUGH JOIST GIRDER. PROVIDE OFFSETS AS REQUIRED AND MOUNT AS TIGHT TO THE ROOF DECK AS POSSIBLE. DUCT SHALL BE CENTERED ON THE JOIST BAY AND FOLLOW THE SLOPE OF THE ROOF.
- (H10) TEMPERATURE & HUMIDITY SENSORS MOUNTED ON WALL AT 5'-2" AFF TO BOTTOM OF EACH SENSOR. SENSORS, WIRING AND CONDUIT SHALL BE PROVIDED AND INSTALLED BY OTHERS.
- (H11) 30X30 LINED SUPPLY UP TO RTU-1. TRANSITION TO RTU SUPPLY CONNECTION.
- (H12) 40X22 LINED RETURN UP TO RTU-1. TRANSITION TO RTU RETURN CONNECTION.
- (H13) 28X12 LINED RETURN UP TO RTU-2. TRANSITION TO RTU RETURN CONNECTION.
- (H14) MOUNT TEMPERATURE SENSOR/DIGITAL ZONE CONTROLLER ON WALL AT 5'-0" AFF.
- (H15) 48X12 TRANSFER MOUNTED AT 8'-10" AFF.
- (H16) 48X24 RETURN GRILLE MOUNTED IN WALL. REFER TO ARCHITECTURAL INTERIOR ELEVATIONS.
- (H17) 4"Ø OUTSIDE AIR DUCT UP THROUGH ROOF. TERMINATE 1'-6" ABOVE ROOF WITH GOOSENECK. PROVIDE BACKDRAFT DAMPER IN RISER. INSTALL INLINE VENTILATION FAN IN RISER. SEE DUCTLESS SPLIT FAN COIL SCHEDULE FOR DETAILS.
- (H18) CEILING MOUNTED CASSETTE DUCTLESS SPLIT FAN COIL UNIT. SUSPEND FROM ROOF STRUCTURE WITH THREADED ROD.
- (H19) 3/8"RS & 1/4"RL INSULATED REFRIGERANT LINE KIT. REFRIGERANT PIPING SHALL BE SIZED PER MANUFACTURER'S RECOMMENDATIONS.
- (H20) SUSPEND AIR COOLED HEAT PUMP BETWEEN ROOF JOISTS WITH THREADED ROD AND UNISTRUT.
- (H21) 12X12 LINED SUPPLY UP TO RTU-2. TRANSITION TO RTU SUPPLY CONNECTION.
- (H22) DESTRATIFICATION FAN SUPPORTED FROM BUILDING STRUCTURE. MOUNT 1'-0" BELOW ROOF DECK. MAKE/MODEL: AIR-B. MOUNT A MINIMUM OF 4'-0" FROM FRONT FACE OF ROOF CURB. MOUNT IN VERTICAL POSITION.



Order Plans @


WWW.LDILINE.COM

Issued:	Date:
A Permit Set	12/05/17
B Client Review Set	05/03/18
C	
D	
Revisions:	Date:
1	
2	
3	
4	
5	
6	
7	
8	
9	

DO NOT SCALE PLANS
Copying, Printing, Software and other processes required to produce these prints can stretch or shrink the actual paper or layout. Therefore, scaling of this drawing may be inaccurate. Contact us consultants with any need for additional dimensions or clarifications.

DRAWN BY: MEM
REVIEWED BY: KFF

Seal



ALDI Inc.
1985 Old Union Church Road
Salisbury, NC 28146
(704) 642-0023
(704) 642-0078 fax

ALDI Inc. Store #: 65
Charlotte, NC
6113 Idlewild Road
Charlotte, NC 28212
Mecklenburg County
Project Name & Location:

HVAC Construction Plan	
Drawing Name:	
Prototype Rls. 09/07/17	Project No. 40452-13
Type: LHSD-V8	
	H-101
Scale: As Noted	Drawing No.

PLOTTED: 5/10/2018 12:08 PM