



Order Plans @ [www.LDOnline.com](http://www.LDOnline.com)

F-1 FLOOR PLAN  
A101 SCALE: 1/4" = 1'-0"

**LEGEND**

	NEW PARTITION & DOOR		1 HOUR RATED ASSEMBLY		PROJECT SCOPE
	EXISTING PARTITION & DOOR		2 HOUR RATED ASSEMBLY		
	DEMOL'D PARTITION & DOOR		3 HOUR RATED ASSEMBLY		

**NOTES**

- REPAIR ALL WHERE WALL PREVIOUSLY REMOVED
- INFILL EXISTING WINDOW OPENING WITH GWB REFER TO D1A501
- EXISTING DIRTY WALL ASSEMBLY TO REMAIN
- EXISTING COLUMNS TO BE V.I.F. BY CONTRACTOR TO CONFIRM ELECTRICAL ACCESS ALONG COLUMN FINISH
- EXISTING FLOOR FINISH TO REMAIN WHERE SPECIFIED - CONTRACTOR SHALL PROTECT AT ALL TIMES. ANY DAMAGE AS A RESULT OF CONSTRUCTION SHALL BE REPAIRED TO "PRE-CONSTRUCTION" CONDITION AT NO COST
- FURNITURE IS SHOWN FOR REFERENCE ONLY - N.I.C.
- NEW STOREFRONT WALL TO BE ALIGNED WITH EXISTING EDGE OF SOFFIT ABOVE
- EXISTING PORTION OF WALL TO BE FURD OUT TO ALIGN WITH PROJECTED PORTION OF WALL FOR DONOR WALL APPLICATION. CONTRACTOR TO VARY CONSTRUCTION IN FIELD
- EXISTING RECEPTION DESK TO REMAIN
- NEW SHAFT WALL TO ACCOMMODATE NEW RISER. REFER TO "P" DRAWING FOR MORE DETAILS
- CONTRACTOR SHALL USE THIS EXIT ENTRY INTO THE PROJECT SCOPE. CONTRACTOR'S LANDOWN AREA SHALL BE IN THE MUSIC "HORSE SHOE" JUST OUTSIDE OF THIS DOORWAY. OWNER/ARCHITECT WILL COORDINATE EXACT PARAMETERS PRIOR TO CONSTRUCTION

**GENERAL NOTES:**

GEN NOTE 1. PAINT ALL DISTURBED AND NEW WALLS. CORNER TO CORNER, INCLUDING SOFFITS.

**MUSC**  
MEDICAL UNIVERSITY  
of SOUTH CAROLINA

PROJECT NUMBER: H51-50068  
DHEC PROJECT NUMBER: 580145

**CONSTRUCTION DOCUMENTS**

**STORM EYE INSTITUTE**  
**OPTICAL SHOP**  
H51-50068  
167 ASHLEY AVE  
CHARLESTON, SC 29425

**ROSENBLUM COE ARCHITECTS, INC.**

1643 MEANS STREET  
CHARLESTON, SC 29412  
843.577.6073

**Keynote Legend**

Key Value	Keynote Text
078100.A	APPLIED FIREPROFFING
079200.A	JOINT SEALANTS
081113.A	HOLLOW METAL FRAMES
081416.A	FLUSH WOOD DOOR
084126.A	BUTT GLAZED STOREFRONT SYSTEM
088810.A	FIRE RATED GLASS AND FRAMING SYSTEM
092116.I	NON-STRUCTURAL METAL FRAMING
092900.A	GYPSON BOARD
092900.B	SOUND ATTENUATION BATTS
095113.A	ACOUSTICAL PANEL CEILINGS
095113.B	CEILING GRID
096513.B	RESILIENT BASE
099123.A	INTERIOR PAINTING
102600.A	BUMPER GUARD
104413.B	FIRE EXTINGUISHER CABINET
104416.C	FIRE EXTINGUISHER
123661.A	SOLID SURFACING COUNTERTOPS
260000.A	INTERIOR LIGHTING - SEE 'E' SHEETS

**FLOOR PLAN**

SHEET NAME	
PROJECT NUMBER	17016
DRAWN BY	RL
CHECKED BY	KEH
DATE	05/09/2018
SCALE	1/4" = 1'-0"

**A101**